



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

April 12, 2021

**Addendum No. 1**

RE: Contract # C204483

WBS # 49072.3.1

STATE FUNDED

**Cumberland County (BR-0014)**

BRIDGE #25 OVER BEAVER DAM CREEK ON NC-242

**April 20, 2021 Letting**

To Whom It May Concern:

Reference is made to the proposal form furnished to you on this project.

The following revisions have been made to the proposal:

| <b>Page No.</b> | <b>Revisions</b>   |
|-----------------|--|
| Proposal Cover  | Note added that reads "Includes Addendum No. 1 Dated 04-12-2021" |

Please void the above listed existing Page in your proposal and staple the revised Page thereto.

On the item sheets the following pay item revision has been made:

| <b><u>Item</u></b>       | <b><u>Description</u></b>  | <b><u>Old Quantity</u></b> | <b><u>New Quantity</u></b> |
|--------------------------|----------------------------|----------------------------|----------------------------|
| 0021-1245000000-E-<br>SP | SHOULDER<br>RECONSTRUCTION | 2.85 SMI                   | 5.7 SMI                    |

The Contractor's bid must include this pay item revision.

The electronic bidding file has been updated to reflect this revision. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

The contract will be prepared accordingly.


*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
CONTRACT STANDARDS AND DEVELOPMENT  
1591 MAIL SERVICE CENTER  
RALEIGH, NC 27699-1591

*Telephone:* (919) 707-6900  
*Fax:* (919) 250-4127  
*Customer Service:* 1-877-368-4968

*Website:* www.ncdot.gov

*Location:*  
1020 BIRCH RIDGE DR.  
RALEIGH, NC 27610

Sincerely,

DocuSigned by:  
  
F81B6038A47A442...  
Ronald E. Davenport, Jr., PE  
State Contract Officer

RED/jjr  
Attachments

cc: Mr. Lamar Sylvester, PE  
Mr. H.L. "Drew" Cox, PE  
Mr. Boyd Tharrington, PE  
Mr. Jon Weathersbee, PE  
Mr. Ken Kennedy, PE  
Project File (2)

Mr. Ray Arnold, PE  
Ms. Jaci Kincaid  
Ms. Lori Strickland  
Mr. Mike Gwyn  
Ms. Penny Higgins  
Mr. Kyle Kempf

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH, N.C.

PROPOSAL

**INCLUDES ADDENDUM No.1 DATED 04-12-2021**

DATE AND TIME OF BID OPENING: **APRIL 20, 2021 AT 2:00 PM**

CONTRACT ID C204483  
WBS 49072.3.1

FEDERAL-AID NO. STATE FUNDED  
COUNTY CUMBERLAND  
T.I.P. NO. BR-0014  
MILES 0.273  
ROUTE NO. NC 242  
LOCATION BRIDGE #25 OVER BEAVER DAM CREEK ON NC-242.

TYPE OF WORK GRADING, DRAINAGE, PAVING, AND STRUCTURE.

**NOTICE:**

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

**BIDS WILL BE RECEIVED AS SHOWN BELOW:**

**THIS IS A ROADWAY & STRUCTURE PROPOSAL**

**5% BID BOND OR BID DEPOSIT REQUIRED**

---

County : Cumberland

| Line #               | Item Number  | Sec # | Description  | Quantity   | Unit Cost | Amount |
|----------------------|--------------|-------|--|------------|-----------|--------|
| <b>ROADWAY ITEMS</b> |              |       |  |            |           |        |
| 0001                 | 0000100000-N | 800   | MOBILIZATION   | Lump Sum   | L.S.      |        |
| 0002                 | 0000400000-N | 801   | CONSTRUCTION SURVEYING   | Lump Sum   | L.S.      |        |
| 0003                 | 0028000000-N | SP    | TYPE I STANDARD APPROACH FILL<br>STATION *****<br>(21+37.00 -L REV-) | Lump Sum   | L.S.      |        |
| 0004                 | 0043000000-N | 226   | GRADING  | Lump Sum   | L.S.      |        |
| 0005                 | 0050000000-E | 226   | SUPPLEMENTARY CLEARING & GRUB-<br>BING                               | 1<br>ACR   |           |        |
| 0006                 | 0057000000-E | 226   | UNDERCUT EXCAVATION  | 400<br>CY  |           |        |
| 0007                 | 0194000000-E | 265   | SELECT GRANULAR MATERIAL,<br>CLASS III                               | 400<br>CY  |           |        |
| 0008                 | 0196000000-E | 270   | GEOTEXTILE FOR SOIL STABILIZA-<br>TION                               | 400<br>SY  |           |        |
| 0009                 | 0222000000-E | SP    | GEOTEXTILE FOR ROCK EMBANK-<br>MENTS                                 | 430<br>SY  |           |        |
| 0010                 | 0255000000-E | SP    | GENERIC GRADING ITEM<br>RIP RAP, CLASS A                             | 260<br>TON |           |        |
| 0011                 | 0255000000-E | SP    | GENERIC GRADING ITEM<br>RIP RAP, CLASS II                            | 925<br>TON |           |        |
| 0012                 | 0318000000-E | 300   | FOUNDATION CONDITIONING MATE-<br>RIAL, MINOR STRUCTURES              | 20<br>TON  |           |        |
| 0013                 | 0320000000-E | 300   | FOUNDATION CONDITIONING GEO-<br>TEXTILE                              | 40<br>SY   |           |        |
| 0014                 | 0343000000-E | 310   | 15" SIDE DRAIN PIPE  | 36<br>LF   |           |        |
| 0015                 | 0344000000-E | 310   | 18" SIDE DRAIN PIPE  | 32<br>LF   |           |        |
| 0016                 | 0582000000-E | 310   | 15" CS PIPE CULVERTS, 0.064"<br>THICK                                | 48<br>LF   |           |        |
| 0017                 | 0636000000-E | 310   | ***" CS PIPE ELBOWS, *****<br>THICK<br>(15", 0.064")                 | 4<br>EA    |           |        |

| Line # | Item Number  | Sec # | Description                                   | Quantity     | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0018   | 1077000000-E | SP    | #57 STONE                                     | 325<br>TON   |           |        |
| 0019   | 1121000000-E | 520   | AGGREGATE BASE COURSE                         | 836<br>TON   |           |        |
| 0020   | 1220000000-E | 545   | INCIDENTAL STONE BASE                         | 50<br>TON    |           |        |
| 0021   | 1245000000-E | SP    | SHOULDER RECONSTRUCTION                       | 5.7<br>SMI   |           |        |
| 0022   | 1330000000-E | 607   | INCIDENTAL MILLING                            | 1,235<br>SY  |           |        |
| 0023   | 1491000000-E | 610   | ASPHALT CONC BASE COURSE, TYPE B25.0C         | 2,090<br>TON |           |        |
| 0024   | 1503000000-E | 610   | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C | 660<br>TON   |           |        |
| 0025   | 1519000000-E | 610   | ASPHALT CONC SURFACE COURSE, TYPE S9.5B       | 7,590<br>TON |           |        |
| 0026   | 1575000000-E | 620   | ASPHALT BINDER FOR PLANT MIX                  | 635<br>TON   |           |        |
| 0027   | 2022000000-E | 815   | SUBDRAIN EXCAVATION                           | 112<br>CY    |           |        |
| 0028   | 2026000000-E | 815   | GEOTEXTILE FOR SUBSURFACE DRAINS              | 500<br>SY    |           |        |
| 0029   | 2036000000-E | 815   | SUBDRAIN COARSE AGGREGATE                     | 84<br>CY     |           |        |
| 0030   | 2044000000-E | 815   | 6" PERFORATED SUBDRAIN PIPE                   | 500<br>LF    |           |        |
| 0031   | 2070000000-N | 815   | SUBDRAIN PIPE OUTLET                          | 1<br>EA      |           |        |
| 0032   | 2077000000-E | 815   | 6" OUTLET PIPE                                | 6<br>LF      |           |        |
| 0033   | 2286000000-N | 840   | MASONRY DRAINAGE STRUCTURES                   | 2<br>EA      |           |        |
| 0034   | 2367000000-N | 840   | FRAME WITH TWO GRATES, STD 840.29             | 2<br>EA      |           |        |
| 0035   | 2556000000-E | 846   | SHOULDER BERM GUTTER                          | 34<br>LF     |           |        |
| 0036   | 3030000000-E | 862   | STEEL BEAM GUARDRAIL                          | 587.5<br>LF  |           |        |
| 0037   | 3150000000-N | 862   | ADDITIONAL GUARDRAIL POSTS                    | 5<br>EA      |           |        |

| Line # | Item Number  | Sec # | Description  | Quantity      | Unit Cost | Amount |
|--------|--------------|-------|--|---------------|-----------|--------|
| 0038   | 3287000000-N | SP    | GUARDRAIL END UNITS, TYPE TL-3                     | 4<br>EA       |           |        |
| 0039   | 3317000000-N | SP    | GUARDRAIL ANCHOR UNITS, TYPE B-77                  | 4<br>EA       |           |        |
| 0040   | 3649000000-E | 876   | RIP RAP, CLASS B                                   | 8<br>TON      |           |        |
| 0041   | 3656000000-E | 876   | GEOTEXTILE FOR DRAINAGE                            | 531<br>SY     |           |        |
| 0042   | 4400000000-E | 1110  | WORK ZONE SIGNS (STATIONARY)                       | 609<br>SF     |           |        |
| 0043   | 4405000000-E | 1110  | WORK ZONE SIGNS (PORTABLE)                         | 96<br>SF      |           |        |
| 0044   | 4410000000-E | 1110  | WORK ZONE SIGNS (BARRICADE MOUNTED)                | 139<br>SF     |           |        |
| 0045   | 4430000000-N | 1130  | DRUMS  | 65<br>EA      |           |        |
| 0046   | 4435000000-N | 1135  | CONES  | 65<br>EA      |           |        |
| 0047   | 4445000000-E | 1145  | BARRICADES (TYPE III)                              | 136<br>LF     |           |        |
| 0048   | 4455000000-N | 1150  | FLAGGER  | 100<br>DAY    |           |        |
| 0049   | 4516000000-N | 1180  | SKINNY DRUM  | 65<br>EA      |           |        |
| 0050   | 4650000000-N | 1251  | TEMPORARY RAISED PAVEMENT MARKERS                  | 185<br>EA     |           |        |
| 0051   | 4685000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 65,000<br>LF  |           |        |
| 0052   | 4810000000-E | 1205  | PAINT PAVEMENT MARKING LINES (4")                  | 118,400<br>LF |           |        |
| 0053   | 4900000000-N | 1251  | PERMANENT RAISED PAVEMENT MARKERS                  | 203<br>EA     |           |        |
| 0054   | 6000000000-E | 1605  | TEMPORARY SILT FENCE                               | 2,450<br>LF   |           |        |
| 0055   | 6006000000-E | 1610  | STONE FOR EROSION CONTROL, CLASS A                 | 75<br>TON     |           |        |
| 0056   | 6009000000-E | 1610  | STONE FOR EROSION CONTROL, CLASS B                 | 220<br>TON    |           |        |

| Line # | Item Number  | Sec # | Description                      | Quantity    | Unit Cost | Amount |
|--------|--------------|-------|----------------------------------|-------------|-----------|--------|
| 0057   | 6012000000-E | 1610  | SEDIMENT CONTROL STONE           | 165<br>TON  |           |        |
| 0058   | 6015000000-E | 1615  | TEMPORARY MULCHING               | 3<br>ACR    |           |        |
| 0059   | 6018000000-E | 1620  | SEED FOR TEMPORARY SEEDING       | 200<br>LB   |           |        |
| 0060   | 6021000000-E | 1620  | FERTILIZER FOR TEMPORARY SEEDING | 1<br>TON    |           |        |
| 0061   | 6024000000-E | 1622  | TEMPORARY SLOPE DRAINS           | 200<br>LF   |           |        |
| 0062   | 6029000000-E | SP    | SAFETY FENCE                     | 1,600<br>LF |           |        |
| 0063   | 6030000000-E | 1630  | SILT EXCAVATION                  | 220<br>CY   |           |        |
| 0064   | 6036000000-E | 1631  | MATTING FOR EROSION CONTROL      | 1,950<br>SY |           |        |
| 0065   | 6037000000-E | SP    | COIR FIBER MAT                   | 100<br>SY   |           |        |
| 0066   | 6042000000-E | 1632  | 1/4" HARDWARE CLOTH              | 60<br>LF    |           |        |
| 0067   | 6048000000-E | SP    | FLOATING TURBIDITY CURTAIN       | 92<br>SY    |           |        |
| 0068   | 6070000000-N | 1639  | SPECIAL STILLING BASINS          | 4<br>EA     |           |        |
| 0069   | 6071012000-E | SP    | COIR FIBER WATTLE                | 240<br>LF   |           |        |
| 0070   | 6071020000-E | SP    | POLYACRYLAMIDE (PAM)             | 35<br>LB    |           |        |
| 0071   | 6084000000-E | 1660  | SEEDING & MULCHING               | 3.5<br>ACR  |           |        |
| 0072   | 6087000000-E | 1660  | MOWING                           | 1.7<br>ACR  |           |        |
| 0073   | 6090000000-E | 1661  | SEED FOR REPAIR SEEDING          | 50<br>LB    |           |        |
| 0074   | 6093000000-E | 1661  | FERTILIZER FOR REPAIR SEEDING    | 0.25<br>TON |           |        |
| 0075   | 6096000000-E | 1662  | SEED FOR SUPPLEMENTAL SEEDING    | 75<br>LB    |           |        |
| 0076   | 6108000000-E | 1665  | FERTILIZER TOPDRESSING           | 2<br>TON    |           |        |
| 0077   | 6111000000-E | SP    | IMPERVIOUS DIKE                  | 165<br>LF   |           |        |

| Line # | Item Number  | Sec # | Description                  | Quantity  | Unit Cost | Amount |
|--------|--------------|-------|------------------------------|-----------|-----------|--------|
| 0078   | 6114500000-N | 1667  | SPECIALIZED HAND MOWING      | 10<br>MHR |           |        |
| 0079   | 6117000000-N | SP    | RESPONSE FOR EROSION CONTROL | 15<br>EA  |           |        |
| 0080   | 6117500000-N | SP    | CONCRETE WASHOUT STRUCTURE   | 2<br>EA   |           |        |

**STRUCTURE ITEMS**

|      |              |     |  |             |      |  |
|------|--------------|-----|--|-------------|------|--|
| 0081 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE<br>AT STATION *****<br>(21+37.00 -L REV-)        | Lump Sum    | L.S. |  |
| 0082 | 8065000000-N | SP  | ASBESTOS ASSESSMENT  | Lump Sum    | L.S. |  |
| 0083 | 8112730000-N | 450 | PDA TESTING  | 1<br>EA     |      |  |
| 0084 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA-<br>TION AT STATION *****<br>(21+37.00 -L REV-)  | Lump Sum    | L.S. |  |
| 0085 | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB  | 3,988<br>SF |      |  |
| 0086 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS   | 4,110<br>SF |      |  |
| 0087 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE)  | 49.9<br>CY  |      |  |
| 0088 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION<br>*****<br>(21+37.00 -L REV-)                  | Lump Sum    | L.S. |  |
| 0089 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE)   | 6,988<br>LB |      |  |
| 0090 | 8259000000-E | 430 | 36" PRESTRESSED CONCRETE GIR-<br>DERS  | 429<br>LF   |      |  |
| 0091 | 8328200000-E | 450 | PILE DRIVING EQUIPMENT SETUP<br>FOR *** STEEL PILES<br>(HP 12 X 53)            | 10<br>EA    |      |  |
| 0092 | 8328400000-E | 450 | PILE DRIVING EQUIPMENT SETUP<br>FOR *** GALVANIZED STEEL PILES<br>(HP 14 X 73) | 5<br>EA     |      |  |



| Line # | Item Number  | Sec # | Description                    | Quantity     | Unit Cost | Amount |
|--------|--------------|-------|--------------------------------|--------------|-----------|--------|
| 0093   | 8364000000-E | 450   | HP12X53 STEEL PILES            | 685<br>LF    |           |        |
| 0094   | 8384200000-E | 450   | HP14X73 GALVANIZED STEEL PILES | 330<br>LF    |           |        |
| 0095   | 8393000000-N | 450   | PILE REDRIVES                  | 9<br>EA      |           |        |
| 0096   | 8503000000-E | 460   | CONCRETE BARRIER RAIL          | 216.67<br>LF |           |        |
| 0097   | 8594000000-E | 876   | RIP RAP, CLASS B               | 35<br>TON    |           |        |
| 0098   | 8608000000-E | 876   | RIP RAP CLASS II (2'-0" THICK) | 540<br>TON   |           |        |
| 0099   | 8622000000-E | 876   | GEOTEXTILE FOR DRAINAGE        | 593<br>SY    |           |        |
| 0100   | 8657000000-N | 430   | ELASTOMERIC BEARINGS           | Lump Sum     | L.S.      |        |

1231/Apr09/Q229804.22/D439887062000/E100

Total Amount Of Bid For Entire Project :