

ECONOLITE ASC/3-2070 OVERLAP PROGRAMMING DETAIL

(program controller as shown)

1. From Main Menu select 2. CONTROLLER
2. From CONTROLLER Submenu select 2. VEHICLE OVERLAPS

OVERLAP A

Select TMG VEH OVLP [A] and 'PPLT FYA'

TMG VEH OVLP...[A] TYPE:PPLT FYA

PROTECTED LEFT TURN.... PHASE 1

OPPOSING THROUGH..... PHASE 2

FLASHING ARROW OUTPUT.....CH9 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0

ACTION PLAN SF BIT DISABLE..... 0

Toggle Twice

OVERLAP C

Select TMG VEH OVLP [C] and 'PPLT FYA'

TMG VEH OVLP...[C] TYPE:PPLT FYA

PROTECTED LEFT TURN.... PHASE 5

OPPOSING THROUGH..... PHASE 6

FLASHING ARROW OUTPUT.....CH11 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0

ACTION PLAN SF BIT DISABLE..... 0

END PROGRAMMING

Project #: 180914

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 07-0903T2
DESIGNED: April 2020
SEALED: 04/20/2020
REVISED: N/A

DAVENPORT
HOME OFFICE:
119 BROOKSTOWN AVENUE, SUITE PH1
WINSTON-SALEM, NC 27101
336.744.1636 www.davenportworld.com
NCBELS FIRM LICENSE NO. C-2522

Electrical Detail - Sheet 2 of 2 Temporary Design 2
(TMP Phase III - Step 1&2; Phase IV - Step 3)

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

<p style="font-size: small;">ELECTRICAL AND PROGRAMMING DETAILS FOR:</p> <div style="text-align: center;"> <p style="font-size: x-small;">Prepared For:</p> <p style="font-size: x-small;">750 N. Greenfield Hwy, Garner, NC 27529</p> </div>	<p style="font-weight: bold; font-size: large;">SR 4771 (Reedy Fork Parkway) at SR 2526 (Summit Avenue)/ Dixie Sales Driveway</p> <p style="font-size: x-small;">Division 7 Guilford County Greensboro</p> <p style="font-size: x-small;">PLAN DATE: April 2020 REVIEWED BY: L. Boyer</p> <p style="font-size: x-small;">PREPARED BY: T.S. Warren REVIEWED BY:</p> <table border="1" style="width: 100%; border-collapse: collapse; font-size: x-small;"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>	REVISIONS	INIT.	DATE										<p style="font-weight: bold; font-size: large;">SEAL</p> <div style="text-align: center;"> <p style="font-size: x-small;">L. M. BOYER 04/20/2020 1FC9650A812463</p> </div> <p style="font-size: x-small;">DATE</p>
REVISIONS	INIT.	DATE												
SIG. INVENTORY NO. 07-0903T2														