



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

May 10, 2021

**Addendum No. 1**

RE: Contract # C204469

WBS # 38356.3.2

STATE FUNDED

**Anson and Stanly Counties (B-4407)**

BRIDGE #70 OVER ROCKY RIVER ON US-52

**May 18, 2021 Letting**

To Whom It May Concern:

Reference is made to the proposal form furnished to you on this project.

The following revisions have been made to the proposal:

<b>Page No.</b>	<b>Revisions</b>
Proposal Cover	Note added that reads "Includes Addendum No. 1 Dated 05-10-2021"
TC-2	Revised Unit Project Special Provision entitled <b>PROTECTIVE CANOPY</b>

Please void the above listed Pages in your proposal and staple the revised Pages thereto.

On the item sheets the following pay item revisions have been made:

<b><u>Item</u></b>	<b><u>Description</u></b>	<b><u>Old Quantity</u></b>	<b><u>New Quantity</u></b>
0058-4465000000-N-1160	TEMPORARY CRASH CUSHIONS	5 EA	6 EA
0059-4470000000-N-1160	REMOVE & RESET TEMPORARY CRASH CUSHION	2 EA	DELETED
0060-4485000000-E-1170	PORTABLE CONCRETE BARRIER	652 LF	1,380 LF
0061-4500000000-E-1170	REMOVE AND RESET PORTABLE CONCRETE BARRIER	266 LF	DELETED

*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
CONTRACT STANDARDS AND DEVELOPMENT  
1591 MAIL SERVICE CENTER  
RALEIGH, NC 27699-1591

*Telephone:* (919) 707-6900  
*Fax:* (919) 250-4127  
*Customer Service:* 1-877-368-4968

*Location:*  
1020 BIRCH RIDGE DR.  
RALEIGH, NC 27610

*Website:* www.ncdot.gov

The Contractor's bid must include these pay item revisions.

The electronic bidding file has been updated to reflect these revisions. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

The contract will be prepared accordingly.

Sincerely,

DocuSigned by:  
*Ronald E. Davenport, Jr.*  
F81B6038A47A442...

Ronald E. Davenport, Jr., PE  
State Contract Officer

RED/jjr  
Attachments

cc: Mr. Lamar Sylvester, PE  
Mr. Brett D. Canipe, PE  
Mr. Boyd Tharrington, PE  
Mr. Jon Weathersbee, PE  
Mr. Ken Kennedy, PE  
Project File (2)

Mr. Ray Arnold, PE  
Ms. Jaci Kincaid  
Ms. Lori Strickland  
Mr. Mike Gwyn  
Ms. Penny Higgins  
Mr. Kyle Kempf

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH, N.C.

PROPOSAL

**INCLUDES ADDENDUM No.1 DATED 05-10-2021**

DATE AND TIME OF BID OPENING: **MAY 18, 2021 AT 2:00 PM**

CONTRACT ID C204469  
WBS 38356.3.2

FEDERAL-AID NO. STATE FUNDED  
COUNTY ANSON, STANLY  
T.I.P. NO. B-4407  
MILES 0.647  
ROUTE NO. US 52  
LOCATION BRIDGE #70 OVER ROCKY RIVER ON US-52.

TYPE OF WORK GRADING, DRAINAGE, PAVING & STRUCTURE.

**NOTICE:**

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

**BIDS WILL BE RECEIVED AS SHOWN BELOW:**

**THIS IS A ROADWAY & STRUCTURE PROPOSAL**

**5% BID BOND OR BID DEPOSIT REQUIRED**

---

## TC-2

Anson/Stanly County

### **PROTECTIVE CANOPY:**

(06/28/2013)

#### **Description**

The Contractor shall provide a 10' x 20' protective canopy to protect pedestrians from falling debris along the existing sidewalk beneath the US-52 Bridge 70 bridge structure at all times during construction.

#### **Construction Methods**

The protective canopy shall be constructed in accordance with local governing building codes, and requirements of the Americans with Disabilities Act (ADA). The protective canopy shall be adequately lit for nighttime use. At no time shall materials or equipment be stored on the canopy roof. All waste or falling debris is to be removed from the canopy roof on a daily basis or as directed by the engineer. The Contractor is to investigate and secure all necessary permits required by the governing bodies aforementioned prior to commencing work.

#### **Measurement and Payment**

The measurement and payment for the Protective Canopy shall be Lump Sum. The Lump Sum price shall include any costs associated with the installation, maintenance and removal.

#### **Pay Item**

Protective Canopy

#### **Pay Unit**

Lump Sum

County : Anson, Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0028000000-N	SP	TYPE I STANDARD APPROACH FILL STATION ***** (32+31.61 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1,100 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	140 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	3,750 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	4,450 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	3,010 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRUCTURES	50 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	150 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	20 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	300 LF		
0015	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	68 LF		
0016	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	52 LF		
0017	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0018	0995000000-E	340	PIPE REMOVAL	36 LF		

County : Anson, Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 3")	204 SY		
0020	1330000000-E	607	INCIDENTAL MILLING	20 SY		
0021	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,520 TON		
0022	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,440 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,060 TON		
0024	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	325 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0026	2000000000-N	806	RIGHT-OF-WAY MARKERS	19 EA		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0028	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	250 SY		
0029	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	42 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0031	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-E	815	6" OUTLET PIPE	6 LF		
0033	2253000000-E	840	PIPE COLLARS	0.447 CY		
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0035	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.74 LF		
0036	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		

County : Anson, Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
0038	2556000000-E	846	SHOULDER BERM GUTTER	504 LF		
0039	3030000000-E	862	STEEL BEAM GUARDRAIL	850 LF		
0040	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	137.5 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0042	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0043	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	3 EA		
0044	3317000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0045	3360000000-E	863	REMOVE EXISTING GUARDRAIL	853 LF		
0046	3578000000-N	SP	GENERIC FENCING ITEM RESET EXISTING GATE	1 EA		
0047	3649000000-E	876	RIP RAP, CLASS B	475 TON		
0048	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,665 SY		
0049	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0050	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (E)	9 EA		
0051	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	1 EA		
0052	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	132 SF		
0053	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0054	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	63 SF		
0055	4430000000-N	1130	DRUMS	106 EA		

County : Anson, Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0057	4455000000-N	1150	FLAGGER	7 DAY		
0058	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6 EA		
0060	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,380 LF		
0062	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM PROTECTIVE CANOPY	Lump Sum	L.S.	
0063	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	96 EA		
0064	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	13,963 LF		
0065	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	1,665 LF		
0066	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,925 LF		
0067	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	74 LF		
0068	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKERS	89 EA		
0069	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	7 EA		
0070	6000000000-E	1605	TEMPORARY SILT FENCE	5,880 LF		
0071	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	180 TON		
0072	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,680 TON		
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	770 TON		
0074	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		



County : Anson, Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0076	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2 TON		
0077	6024000000-E	1622	TEMPORARY SLOPE DRAINS	525 LF		
0078	6029000000-E	SP	SAFETY FENCE	1,902 LF		
0079	6030000000-E	1630	SILT EXCAVATION	4,090 CY		
0080	6036000000-E	1631	MATTING FOR EROSION CONTROL	18,695 SY		
0081	6037000000-E	SP	COIR FIBER MAT	1,575 SY		
0082	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,270 SY		
0083	6042000000-E	1632	1/4" HARDWARE CLOTH	625 LF		
0084	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		
0085	6070000000-N	1639	SPECIAL STILLING BASINS	8 EA		
0086	6071012000-E	SP	COIR FIBER WATTLE	420 LF		
0087	6071020000-E	SP	POLYACRYLAMIDE (PAM)	360 LB		
0088	6071030000-E	1640	COIR FIBER BAFFLE	570 LF		
0089	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0090	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0091	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0092	6087000000-E	1660	MOWING	3 ACR		
0093	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0094	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Anson, Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0096	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0097	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0098	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0099	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0100	6123000000-E	1670	REFORESTATION	0.43 ACR		
0101	6126000000-E	SP	STREAMBANK REFORESTATION	0.21 ACR		

**STRUCTURE ITEMS**

0102	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (32+31.61 -L-)	Lump Sum	L.S.	
0103	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (32+31.61 -L-)	Lump Sum	L.S.	
0104	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0105	8105500000-E	411	***-*** DIA DRILLED PIERS IN SOIL (4'-6")	136.8 LF		
0106	8105600000-E	411	***-*** DIA DRILLED PIERS NOT IN SOIL (4'-6")	208 LF		
0107	8111000000-E	411	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6")	35.4 LF		
0108	8112730000-N	450	PDA TESTING	2 EA		
0109	8113000000-N	411	SID INSPECTIONS	12 EA		

County : Anson, Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	8115000000-N	411	CSL TESTING	4 EA		
0111	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (32+31.61 -L-)	Lump Sum	L.S.	
0112	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	19,469 SF		
0113	8161000000-E	420	GROOVING BRIDGE FLOORS	17,586 SF		
0114	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	338.8 CY		
0115	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (32+31.61 -L-)	Lump Sum	L.S.	
0116	8217000000-E	425	REINFORCING STEEL (BRIDGE)	71,086 LB		
0117	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	19,733 LB		
0118	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	2,604.17 LF		
0119	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12 X 53)	12 EA		
0120	8364000000-E	450	HP12X53 STEEL PILES	390 LF		
0121	8503000000-E	460	CONCRETE BARRIER RAIL	1,046.67 LF		
0122	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,740 TON		
0123	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	1,933 SY		
0124	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0125	8860000000-N	SP	GENERIC STRUCTURE ITEM STRIP SEAL EXPANSION JOINTS	Lump Sum	L.S.	