PROJECT REFERENCE NO.	SHEET NO.
B-5980	EC-03
R/W SHEET NO.	

Prepared in the Office of: AECOM
NC FIRM LICENSE No: F-0342
701 Corporate Center Drive, Suite 475
Raleigh, NC 27610
(919) 854-6200 - (919) 854-6259 (FAX)

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
5	-PRC-	13+91	14+94	LT	125
5	-RPD-	16+50	19+00	RT	205
5	-RPD-	18+00	20+39	LT	770
5	-Y1-	44+50	45+52	LT	250
5	-Y1-	47+59	49+00	RT	150
5	-DW1-	10+41	11+90	LT	240
8	-Y1-	23+00	33+00	LT	3210
8	-Y2-	11+50	14+40	RT	305
8	-Y1-	49+00	50+00	RT	105
			SUBTOTAL		5,360
	MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER				2,410
			TOTAL		7,770
			SAY		7,800

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)

5/14/99
3:56:46 PM
R:\Environmental\Design\B5980_REU_EC03.dgn