

5/14/99

PROJECT REFERENCE NO.	SHEET NO.
B-5980	EC-03A
RW SHEET NO.	
<small>Prepared in the Office of:</small> <b>AECOM</b>	
<small>NC FIRM LICENSE No.F-0342  701 Corporate Center Drive, Suite 475  Raleigh, NC 27607  (919) 854-6200 • (919) 854-6259(FAX)</small>	

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

---



---

# ***SOIL STABILIZATION TIMEFRAMES***

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

R:\Enviro\101\Design\B5980\REU\_EC03A.dgn  
3:56:46 PM  
RMB