

SEE SHEET 3 FOR PLAN SHEET LAYOUT
AT TIME OF INVESTIGATION

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	B-4863	1	12

CONTENTS

LINE	STATION	PLAN	PROFILE
-L-	10+00.00 - 55+05.00	4-7	8-11
-Y-	10+00.00 - 11+30.00	4	12
-DRIVE-	10+00.00 - 11+40.00	4	12

**ROADWAY
SUBSURFACE INVESTIGATION**

COUNTY CARTERET
PROJECT DESCRIPTION BR 73 OVER THE STRAITS AT
HARKERS ISLAND ON SR 1335

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT 1919 TOTT-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
1. THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 2. BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

PAUL, A. S.

SWARTLEY, J. R.

WHITE, T. J.

INVESTIGATED BY PAUL, A. S.

DRAWN BY HUNSBERGER, W. S.

CHECKED BY HAMM, J. R.

SUBMITTED BY FALCON ENG.

DATE FEBRUARY 2018

REFERENCE: B-4863

PROJECT: 40212



DocuSigned by:
W. Scott Hunsberger 3/5/2018
EA39AB9EDF5845A...
SIGNATURE DATE

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS																																																																																																																																																																					
<p>SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 208, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, <i>VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6</i></p>										<p>WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.</p>										<p>HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p>										<p>ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLOGGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS, MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (ROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>																																																																																																																																																																					
SOIL LEGEND AND AASHTO CLASSIFICATION										ANGULARITY OF GRAINS										WEATHERED ROCK (WR)										CRYSTALLINE ROCK (CR)																																																																																																																																																																					
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="5">GRANULAR MATERIALS (≤ 35% PASSING #200)</th> <th colspan="5">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="5">ORGANIC MATERIALS</th> </tr> <tr> <th>GROUP CLASS.</th> <th>A-1</th> <th>A-3</th> <th>A-2</th> <th>A-4</th> <th>A-5</th> <th>A-6</th> <th>A-7</th> <th>A-1, A-2</th> <th>A-3</th> <th>A-4, A-5</th> <th>A-6, A-7</th> <th colspan="5"></th> </tr> <tr> <th>SYMBOL</th> <td colspan="2">[Pattern]</td> <td colspan="2">[Pattern]</td> <td colspan="2">[Pattern]</td> <td colspan="2">[Pattern]</td> <td colspan="2">[Pattern]</td> <td colspan="2">[Pattern]</td> <td colspan="5"></td> </tr> <tr> <th>% PASSING #10 #40 #200</th> <td colspan="2">50 MX 30 MX 15 MX</td> <td colspan="2">50 MX 25 MX 10 MX</td> <td colspan="2">50 MN 35 MX 35 MX</td> <td colspan="2">50 MN 35 MX 35 MX</td> <td colspan="2">50 MN 36 MN 36 MN</td> <td colspan="2">50 MN 36 MN 36 MN</td> <td colspan="5"></td> </tr> <tr> <th>MATERIAL PASSING #40 LL PI</th> <td colspan="2">-</td> <td colspan="2">NP</td> <td colspan="2">40 MX 41 MN</td> <td colspan="2">40 MX 41 MN</td> <td colspan="2">40 MX 41 MN</td> <td colspan="2">40 MX 41 MN</td> <td colspan="5"></td> </tr> <tr> <th>GROUP INDEX</th> <td colspan="2">0</td> <td colspan="2">0</td> <td colspan="2">4 MX</td> <td colspan="2">8 MX</td> <td colspan="2">12 MX</td> <td colspan="2">16 MX</td> <td colspan="5"></td> </tr> <tr> <th>USUAL TYPES OF MAJOR MATERIALS</th> <td colspan="2">STONE FRAGS. GRAVEL, AND SAND</td> <td colspan="2">FINE SAND</td> <td colspan="2">SILTY OR CLAYEY GRAVEL AND SAND</td> <td colspan="2">SILTY SOILS</td> <td colspan="2">CLAYEY SOILS</td> <td colspan="5"></td> </tr> <tr> <th>GEN. RATING AS SUBGRADE</th> <td colspan="5">EXCELLENT TO GOOD</td> <td colspan="5">FAIR TO POOR</td> <td colspan="5">FAIR TO POOR POOR UNSUITABLE</td> </tr> <tr> <td colspan="10">PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30</td> <td colspan="10"></td> </tr> </table>										GRANULAR MATERIALS (≤ 35% PASSING #200)					SILT-CLAY MATERIALS (> 35% PASSING #200)					ORGANIC MATERIALS					GROUP CLASS.	A-1	A-3	A-2	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7						SYMBOL	[Pattern]		[Pattern]		[Pattern]		[Pattern]		[Pattern]		[Pattern]							% PASSING #10 #40 #200	50 MX 30 MX 15 MX		50 MX 25 MX 10 MX		50 MN 35 MX 35 MX		50 MN 35 MX 35 MX		50 MN 36 MN 36 MN		50 MN 36 MN 36 MN							MATERIAL PASSING #40 LL PI	-		NP		40 MX 41 MN		40 MX 41 MN		40 MX 41 MN		40 MX 41 MN							GROUP INDEX	0		0		4 MX		8 MX		12 MX		16 MX							USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS							GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD					FAIR TO POOR					FAIR TO POOR POOR UNSUITABLE					PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30																				<p>THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.</p>										<p>NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.</p>										<p>FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.</p>									
GRANULAR MATERIALS (≤ 35% PASSING #200)					SILT-CLAY MATERIALS (> 35% PASSING #200)					ORGANIC MATERIALS																																																																																																																																																																																									
GROUP CLASS.	A-1	A-3	A-2	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7																																																																																																																																																																																								
SYMBOL	[Pattern]		[Pattern]		[Pattern]		[Pattern]		[Pattern]		[Pattern]																																																																																																																																																																																								
% PASSING #10 #40 #200	50 MX 30 MX 15 MX		50 MX 25 MX 10 MX		50 MN 35 MX 35 MX		50 MN 35 MX 35 MX		50 MN 36 MN 36 MN		50 MN 36 MN 36 MN																																																																																																																																																																																								
MATERIAL PASSING #40 LL PI	-		NP		40 MX 41 MN		40 MX 41 MN		40 MX 41 MN		40 MX 41 MN																																																																																																																																																																																								
GROUP INDEX	0		0		4 MX		8 MX		12 MX		16 MX																																																																																																																																																																																								
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS																																																																																																																																																																																										
GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD					FAIR TO POOR					FAIR TO POOR POOR UNSUITABLE																																																																																																																																																																																								
PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30																																																																																																																																																																																																			
MINERALOGICAL COMPOSITION										COMPRESSION										NON-CRYSTALLINE ROCK (NCR)										COASTAL PLAIN SEDIMENTARY ROCK (CP)																																																																																																																																																																					
<p>MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.</p>										<p>SLIGHTLY COMPRESSIBLE LL < 31 MODERATELY COMPRESSIBLE LL = 31 - 50 HIGHLY COMPRESSIBLE LL > 50</p>										<p>FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.</p>										<p>COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.</p>																																																																																																																																																																					
PERCENTAGE OF MATERIAL										GROUND WATER										WEATHERING										MISCELLANEOUS SYMBOLS																																																																																																																																																																					
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>ORGANIC MATERIAL</th> <th>GRANULAR SOILS</th> <th>SILT - CLAY SOILS</th> <th>OTHER MATERIAL</th> </tr> <tr> <td>TRACE OF ORGANIC MATTER</td> <td>2 - 3%</td> <td>3 - 5%</td> <td>TRACE</td> </tr> <tr> <td>LITTLE ORGANIC MATTER</td> <td>3 - 5%</td> <td>5 - 12%</td> <td>LITTLE</td> </tr> <tr> <td>MODERATELY ORGANIC</td> <td>5 - 10%</td> <td>12 - 20%</td> <td>SOME</td> </tr> <tr> <td>HIGHLY ORGANIC</td> <td>> 10%</td> <td>> 20%</td> <td>HIGHLY</td> </tr> <tr> <td></td> <td></td> <td></td> <td>35% AND ABOVE</td> </tr> </table>										ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME	HIGHLY ORGANIC	> 10%	> 20%	HIGHLY				35% AND ABOVE	<p>▽ WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING ▽ STATIC WATER LEVEL AFTER 24 HOURS ▽ PW PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA ○ SPRING OR SEEP</p>										<p>FRESH ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE. VERY SLIGHT (IV SLI) ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE. SLIGHT (SLI) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS. MODERATE (MOD.) SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK. MODERATELY SEVERE (MOD. SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. IF TESTED, WOULD YIELD SPT REFUSAL SEVERE (SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF VERY SEVERE (IV SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.</p>										<p>ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION SOIL SYMBOL ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT INFERRED SOIL BOUNDARY INFERRED ROCK LINE ALLUVIAL SOIL BOUNDARY</p>																																																																																																																																													
ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL																																																																																																																																																																																																
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE																																																																																																																																																																																																
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE																																																																																																																																																																																																
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME																																																																																																																																																																																																
HIGHLY ORGANIC	> 10%	> 20%	HIGHLY																																																																																																																																																																																																
			35% AND ABOVE																																																																																																																																																																																																
TEXTURE OR GRAIN SIZE										RECOMMENDATION SYMBOLS										ABBREVIATIONS										ROCK HARDNESS																																																																																																																																																																					
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>U.S. STD. SIEVE SIZE OPENING (MM)</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> <tr> <td></td> <td>4.75</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> <tr> <th>BOULDER (BLDR.)</th> <th>COBBLE (COB.)</th> <th>GRAVEL (GR.)</th> <th>COARSE SAND (CSE. SD.)</th> <th>FINE SAND (F SD.)</th> <th>SILT (SL.)</th> <th>CLAY (CL.)</th> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>GRAIN SIZE</th> <th>MM</th> <th>305</th> <th>75</th> <th>2.0</th> <th>0.25</th> <th>0.05</th> <th>0.005</th> </tr> <tr> <td></td> <td>IN.</td> <td>12</td> <td>3</td> <td></td> <td></td> <td></td> <td></td> </tr> </table>										U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.75	2.00	0.42	0.25	0.075	0.053	BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)								GRAIN SIZE	MM	305	75	2.0	0.25	0.05	0.005		IN.	12	3					<p>UNDERCUT SHALLOW UNDERCUT UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL</p>										<p>AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - CONE PENETRATION TEST CSE - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F - FINE FOSS. - FOSSILIFEROUS FRAC. - FRACTURED, FRACTURES FRAGS. - FRAGMENTS HI. - HIGHLY MED. - MEDIUM MICA - MICACEOUS MOD. - MODERATELY NP - NON PLASTIC ORG. - ORGANIC PMT - PRESSUREMETER TEST SAP. - SAPROLITIC SD. - SAND, SANDY SL. - SILT, SILTY SLI. - SLIGHTLY TCR - TRICONE REFUSAL w - MOISTURE CONTENT V - VERY VST - VANE SHEAR TEST WEA. - WEATHERED W - UNIT WEIGHT W_g - DRY UNIT WEIGHT SAMPLE ABBREVIATIONS S - BULK SS - SPLIT SPOON ST - SHELBY TUBE RS - ROCK RT - RECOMPACTED TRIAXIAL CBR - CALIFORNIA BEARING RATIO</p>										<p>VERY HARD CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK. HARD CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN. MODERATELY HARD CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS. MEDIUM HARD CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK. SOFT CAN BE GROOVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE. VERY SOFT CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.</p>																																																																																																																									
U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																																																																																																																																																													
	4.75	2.00	0.42	0.25	0.075	0.053																																																																																																																																																																																													
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)																																																																																																																																																																																													
GRAIN SIZE	MM	305	75	2.0	0.25	0.05	0.005																																																																																																																																																																																												
	IN.	12	3																																																																																																																																																																																																
SOIL MOISTURE - CORRELATION OF TERMS										EQUIPMENT USED ON SUBJECT PROJECT										FRACTURE SPACING										BEDDING																																																																																																																																																																					
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> <tr> <td rowspan="3">LL PLASTIC RANGE (PI) PL</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>OM SL</td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </table>										SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL PLASTIC RANGE (PI) PL	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	OM SL	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	<p>DRILL UNITS: <input type="checkbox"/> CME-45C <input type="checkbox"/> CME-55 <input type="checkbox"/> CME-550 <input type="checkbox"/> VANE SHEAR TEST <input type="checkbox"/> PORTABLE HOIST <input checked="" type="checkbox"/> CME-45B <input checked="" type="checkbox"/> DRAG BIT</p> <p>ADVANCING TOOLS: <input type="checkbox"/> CLAY BITS <input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER <input type="checkbox"/> 8" HOLLOW AUGERS <input type="checkbox"/> HARD FACED FINGER BITS <input type="checkbox"/> TUNG-CARBIDE INSERTS <input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER <input type="checkbox"/> TRICONE * STEEL TEETH <input type="checkbox"/> TRICONE * TUNG-CARB. <input type="checkbox"/> CORE BIT</p> <p>HAMMER TYPE: <input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL CORE SIZE: <input type="checkbox"/> -B <input type="checkbox"/> -H <input type="checkbox"/> -N HAND TOOLS: <input type="checkbox"/> POST HOLE DIGGER <input checked="" type="checkbox"/> HAND AUGER <input type="checkbox"/> SOUNDING ROD <input type="checkbox"/> VANE SHEAR TEST</p>										<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>TERM</th> <th>SPACING</th> <th>TERM</th> <th>THICKNESS</th> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> <td>VERY THICKLY BEDDED</td> <td>4 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FOOT</td> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td></td> <td></td> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </table>										TERM	SPACING	TERM	THICKNESS	VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET	WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET	MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET	CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET	VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET			THINLY LAMINATED	< 0.008 FEET	<p>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC. FRIABLE RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE. MODERATELY INDURATED GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER. INDURATED GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER. EXTREMELY INDURATED SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</p>																																																																																																																												
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																																	
LL PLASTIC RANGE (PI) PL	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																																	
	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																	
	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																																	
OM SL	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																	
TERM	SPACING	TERM	THICKNESS																																																																																																																																																																																																
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET																																																																																																																																																																																																
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET																																																																																																																																																																																																
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET																																																																																																																																																																																																
CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET																																																																																																																																																																																																
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET																																																																																																																																																																																																
		THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																																
PLASTICITY										INDURATION										FRAC. SPACING										BEDDING																																																																																																																																																																					
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NON PLASTIC</th> <th colspan="2">PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td></td> <td>0-5</td> <td></td> <td>VERY LOW</td> </tr> <tr> <td>SLIGHTLY PLASTIC</td> <td>6-15</td> <td></td> <td>SLIGHT</td> </tr> <tr> <td>MODERATELY PLASTIC</td> <td>16-25</td> <td></td> <td>MEDIUM</td> </tr> <tr> <td>HIGHLY PLASTIC</td> <td>26 OR MORE</td> <td></td> <td>HIGH</td> </tr> </table>										NON PLASTIC	PLASTICITY INDEX (PI)		DRY STRENGTH		0-5		VERY LOW	SLIGHTLY PLASTIC	6-15		SLIGHT	MODERATELY PLASTIC	16-25		MEDIUM	HIGHLY PLASTIC	26 OR MORE		HIGH	<p>DRILL UNITS: <input checked="" type="checkbox"/> CME-45C <input checked="" type="checkbox"/> DRAG BIT</p>										<p>FRAC. SPACING: VERY WIDE, WIDE, MODERATELY CLOSE, CLOSE, VERY CLOSE</p>										<p>BEDDING: VERY THICKLY BEDDED, THICKLY BEDDED, THINLY BEDDED, VERY THINLY BEDDED, THICKLY LAMINATED, THINLY LAMINATED</p>																																																																																																																																																	
NON PLASTIC	PLASTICITY INDEX (PI)		DRY STRENGTH																																																																																																																																																																																																
	0-5		VERY LOW																																																																																																																																																																																																
SLIGHTLY PLASTIC	6-15		SLIGHT																																																																																																																																																																																																
MODERATELY PLASTIC	16-25		MEDIUM																																																																																																																																																																																																
HIGHLY PLASTIC	26 OR MORE		HIGH																																																																																																																																																																																																
COLOR										FRAC. SPACING										BEDDING										NOTES																																																																																																																																																																					
<p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>										<p>FRAC. SPACING: VERY WIDE, WIDE, MODERATELY CLOSE, CLOSE, VERY CLOSE</p>										<p>BEDDING: VERY THICKLY BEDDED, THICKLY BEDDED, THINLY BEDDED, VERY THINLY BEDDED, THICKLY LAMINATED, THINLY LAMINATED</p>										<p>BENCH MARK: BORING ELEVATIONS TAKEN FROM B4863-Is.tin.tin DATED 08/16 ELEVATION: FEET NOTES: FIAD - FILLED IMMEDIATELY AFTER DRILLING</p>																																																																																																																																																																					

13-FEB-2018 09:52 I:_Projects\2017\G17063.00 NCDOT GEU B-4863 Roadway\B4863_NCDOT_Geotech\InvestigationDesign\B4863_GEO_RDWY\CADD_GEO\TECH\PlanProj\B4863_GEO_rsh.dgn 09/08/19

CONTRACT: TIP PROJECT: B-4863


STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CARTERET COUNTY

**LOCATION: REPLACEMENT OF BRIDGE NOS. 73 AND 96 CARRYING
SR 1335 (ISLAND RD) OVER THE STRAITS**


TYPE OF WORK: GRADING, DRAINAGE, PAVING, AND STRUCTURE

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	B-4863	3	12
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
40212.1.3	N/A	PE	




15% LINE & GRADE PLANS

VICINITY MAP



BEGIN TIP PROJECT B-4863
-L- POC Sta.10+00.00




END TIP PROJECT B-4863
-L- POT Sta.55+05.00



THERE IS NO CONTROL OF ACCESS ON THIS PROJECT.
THIS PROJECT IS NOT WITHIN ANY MUNICIPAL BOUNDARIES.
CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

INCOMPLETE PLANS
DO NOT USE FOR R/W ACQUISITION
DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

GRAPHIC SCALES



DESIGN DATA

ADT 2019 = 3,300
ADT 2040 = 4,200
K = 10 %
D = 60 %
T = 4 % *
V = 50 MPH
*(TTST=2% + DUAL=2%)
FUNC CLASS = MAJOR
COLLECTOR

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT B-4863 = 0.247 MILE +/-
LENGTH STRUCTURE TIP PROJECT B-4863 = 0.606 MILE +/-
TOTAL LENGTH TIP PROJECT B-4863 = 0.853 MILE +/-

PLANS PREPARED BY:

1520 SOUTH BLVD, SUITE 200
CHARLOTTE, NC 28203
704-752-0610

FOR THE NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
2018 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
MONTH XX, XXXX

LETTING DATE:
MONTH XX, XXXX


JENNIFER FARINO, PE
PROJECT ENGINEER
DREW MORROW, PE
PROJECT DESIGN ENGINEER
MARIA ROGERSON, PE
NCDOT CONTACT

HYDRAULICS ENGINEER

SIGNATURE: _____ P.E.

ROADWAY DESIGN ENGINEER

SIGNATURE: _____ P.E.





Roadway Subsurface Investigation Report - Inventory

Bridge No. 73 Over the Straits at Harkers Island on SR 1335
Carteret County, North Carolina
WBS: 40212.1.1, TIP: B-4863
Falcon Project No.: G17063.00

Prepared for:
NCDOT Geotechnical Engineering Unit
1020 Birch Ridge Drive
Raleigh, NC 27610

Submitted by:
Falcon Engineering, Inc.
1210 Trinity Road, Suite 110
Cary, North Carolina 27513
(919) 871-0800
www.falconengineers.com

February 28, 2018

TIP: B-4863
WBS: 40212.1.1
Project ID: 30978
COUNTY: Carteret
DESCRIPTION: Bridge No. 73 Over the Straits at Harkers Island on SR 1335
SUBJECT: Roadway Subsurface Investigation – Inventory

PROJECT DESCRIPTION

This project consists of proposed new grading, widening, and realignment related to the construction of a new bridge structure to replace Bridge 73 and 96 on SR 1335 (Harkers Island Rd.) over the Straits at Harkers Island in Carteret County, NC. The total project length is 0.853 miles, although the roadway approach work will occur over a total of 0.247 miles, divided between both approaches.

In addition, approximately 0.106 miles of temporary detour pavement will be constructed at the End Bent 2 approach to accommodate phasing of construction.

The investigation was conducted on November, 2017 in general accordance with our Scope and Fee Estimates for Geotechnical Investigation and Engineering Services. The recommendations provided in this report are based solely on our site reconnaissance, soil test borings and laboratory test data, engineering evaluation of these data, and generally accepted soil and foundation engineering practices and principles.

A total of nine (9) Hand Auger borings were performed for the proposed roadway alignments. Representative soil samples, collected with a hand auger, were selected for laboratory testing to verify visual field classifications.

Additional SPT borings received from S&ME were incorporated into this report.



Portions of the following alignments, totaling approximately 0.865 miles were investigated. Other minor driveways are included on the project but improvements are not anticipated to be significant enough to warrant investigation.

<u>Alignment</u>	<u>Station (ft)</u>
-L- (Harkers Island Road)	10+00.00 - 55+05.00
-Y- (Sparks Road)	10+00.00 - 11+30.00
-DRIVE-	10+00.00 - 11+40.00
-LDET-	10+00.00 - 16+68.48

AREAS OF SPECIAL GEOTECHNICAL INTEREST

- I. The following locations contain shallow groundwater within 6 feet of the ground surface:

<u>Station (ft)</u>	<u>Alignment</u>
10+00 – 14+00	-L-
17+50 – 18+80	-L-
50+75 – 55+00	-L-
10 +00 – 11+30	-Y-
10+00 – 11+40	-DRIVE-

- II. Roadway Embankment soils were encountered at the tie in points of the new alignment associated with prior construction of existing SR 1335.

PHYSIOGRAPHY AND GEOLOGY

The project site is in the Coastal Plain Physiographic Province of North Carolina. According to the *Geologic Map of North Carolina* (1985), the site is underlain by Surficial Deposits of the Quaternary Period in the Coastal Plain Physiographic Province.

Existing site topography is flat in the general project vicinity along the proposed alignments typical of this far eastern extremity of the Coastal Plain. The existing roadway is supported on a shallow embankment which increases in height toward the existing bridge. Roadway embankment varies from several inches to several feet. Shallow drainage ditches or swales parallel the existing roadway and drain toward bottoms, swamps, or The Straits.

SOIL PROPERTIES

A variety of soils were encountered along the project, including existing roadway embankments and undivided coastal plain soils.

Topsoil was encountered in grassy areas ranging in thickness up to 0.5 feet, typically on the order of 0.3 feet and consisting of silty sand (A-2-4).

Roadway Embankment soils were encountered at the ground surface adjacent to existing roadways. These soils consist of up to 6 feet of moist to saturated, silty and clean sand (A-1-a, A-2-4, and A-3).

Undivided Coastal Plain soils were encountered beneath the roadway embankment soils. These soils consist of moist to saturated, silty, clayey, and clean sand (A-2-4, A-2-6, A-3) and sandy and silty clay (A-6, A-7-6).

GROUNDWATER PROPERTIES

Groundwater levels were measured at the time of boring completion, and after a waiting period of at least 24 hours.

Detailed groundwater measurements are included in the attached subsurface profiles, and noted areas of shallow groundwater are included in the Areas of Special Geotechnical Interest earlier in this report.



CLOSING

Falcon appreciates the opportunity to have provided our geotechnical engineering services for the above referenced project. If you have any questions concerning the contents of this report or need additional information, please do not hesitate to contact our office.

FALCON ENGINEERING, INC.

DOCUMENT NOT CONSIDERED FINAL UNTIL ALL SIGNATURES COMPLETED



Report Prepared By:

Report Reviewed By:

W. Scott Hunsberger, PE
Geotechnical Engineer


Jeremy R. Hamm, PE
Geotechnical Engineering Manager





FOR -L- PROFILE, SEE SHEET NO. 8
 FOR -Y- PROFILE, SEE SHEET NO. 12
 FOR -DRIVE- PROFILE, SEE SHEET NO. 12

	BRIDGE APPROACH SLAB
	PAVEMENT REMOVAL



-L- CURVE DATA

PI Sta 16+00.02
 $\Delta = 13^\circ 24' 02.8''$ (RT)
 $D = 116' 23.7''$
 $L = 1052.50'$
 $T = 528.66'$
 $R = 4500.00'$
 $SE = 03$
 $INC = 24'$

-Y- CURVE DATA

PI Sta 10+42.79
 $\Delta = 2^\circ 18' 49.0''$ (LT)
 $D = 446' 28.7''$
 $L = 48.46'$
 $T = 24.23'$
 $R = 1200.00'$
 $SE = NC$
 $INC = N/A$


-DRIVE- CURVE DATA

PI Sta 10+49.62
 $\Delta = 71^\circ 10' 05.0''$ (RT)
 $D = 143' 14' 22.0''$
 $L = 49.68'$
 $T = 28.62'$
 $R = 40.00'$
 $SE = NC$
 $INC = N/A$

REVISIONS
 15-FEB-2018 14:04
 F:\Projects\2017\617063.00 NCDOT GEU B-4863 Roadway\B4863.GEO\RDWY\CADD\GEO\TECH\PlanProf\B4863_GEO_psh_04.dgn
 8/17/99

PROJECT REFERENCE NO. B-4863	SHEET NO. 5
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR A/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

NAD 83/NA 2011



MATCH TO SHEET 4 -L- STA. 22+00

MATCH TO SHEET 6 -L- STA. 35+00

PROPOSED SUPERELEVATION TRANSITION LOCATED WITHIN TANGENT SECTION ON BRIDGE

-L- HIGH POINT STA. 27+61.76 ELEV. 54.60'

TEMPORARY CONSTRUCTION EASEMENT FOR 40' WIDE WORK BRIDGE WITH 10' CLEARANCE TO PROPOSED BRIDGE

-L- CURVE DATA
 PI Sta 34+74.21
 $\Delta = 27^\circ 28' 03.8''$ (LT)
 $D = 1^\circ 08' 45.3''$
 $L = 2,397.01'$
 $T = 1,222.00'$
 $R = 5,000.00'$
 $SE = RC$
 $INC = 24'$


NOTE: NO BORINGS ON THIS SHEET
 FOR -L- PROFILE, SEE SHEET NO. 9

REVISIONS
 70-NOV-2017 10:30
 T:\Projects\2017\17063\00 NCDOT GEU B-4863 NCDOT-Electronic-File_Tree\Geotech\InvestigationDesign\B4863.GEO_RDWY\CADD\GEO\TECH\PlanProf\B4863_GEO_psh_05.dgn
 8/17/99

30-NOV-2017 10:37
 I:\Projects\2017\17063\00 NCDOT GEU B-4863 NCDOT-EElectronic-File_Tree\Geotech\InvestigationDesign\B4863.GEO_RDWY\CADD.GEOTECH\PlanProf\B4863_GEO_psh_06.dgn
 B:\17\99

REVISIONS

MATCH TO SHEET 5 -L- STA. 35+00



NAD 83/NA 2011

PROJECT REFERENCE NO. B-4863	SHEET NO. 6
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR A/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

-L- PT Sta. 46+49.23


MATCH TO SHEET 7 -L- STA. 48+00

PROPOSED SUPERELEVATION TRANSITION LOCATED WITHIN TANGENT SECTION ON BRIDGE

NOTE: NO BORINGS ON THIS SHEET

FOR -L- PROFILE, SEE SHEET NO. 10

PROJECT REFERENCE NO.	SHEET NO.
B-4863	7
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	




-L- DET CURVE DATA

PI Sta 11+70.73 Δ = 8° 00' 42.0" (RT) D = 5° 40' 22.3" L = 141.23' T = 70.73' R = 1,010.00' SE = 0.034 INC = 20.5	PI Sta 13+34.04 Δ = 10° 30' 02.3" (RT) D = 5° 40' 22.3" L = 185.10' T = 92.81' R = 1,010.00' SE = 0.034 INC = 20.5	PI Sta 14+99.03 Δ = 8° 14' 03.4" (LT) D = 5° 40' 22.3" L = 145.15' T = 72.70' R = 1,010.00' SE = 0.034 INC = 20.5
--	---	--

-L- CURVE DATA

PI Sta 51+04.28 Δ = 14° 20' 50.1" (RT) D = 2° 23' 14.4" L = 600.98' T = 302.07' R = 2,400.00' SE = 0.3 INC = 24'



FOR -L- PROFILE, SEE SHEET NO. 11	
	BRIDGE APPROACH SLAB
	PAVEMENT REMOVAL

REVISIONS
 28-FEB-2018 14:02
 I:\Projects\2017\2017063.00 NCDOT GEU B-4863 Roadway\B4863_NCDOT_Electronic_File_Tree\Geotech\InvestigationDesign\B4863_GEO_RDWY\CADD_GEDTECH\PlanPro\B4863_GEO_psh_07.dgn
 8/17/99


5/14/99
 I:\FEB-2018\0645\14\FR\cjs\1207\17\017063.00 NCDOT GEU B-4863 Roadway\B4863_NCDOT_Electronic_File_Tree\Geotech\InvestigationDesign\B4863_GEO_ROWY\CADD_GEO\TECH\PlanProf\B4863_GEO_pf1.08.dgn

-L-

PROJECT REFERENCE NO.	SHEET NO.
B-4863	8
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS	
DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL	
UNLESS ALL SIGNATURES COMPLETED	

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-1	15 FT RT	11+00	0.5'-1.7'	A-2-4	ND	NP	42	50	2	6	100	91	8	7	0.8
S-2	0	15+01	0.3'-1.2'	A-2-4	ND	NP	38	51	4	7	84	69	10	11	-

- (A) ROADWAY EMBANKMENT: GRAY TAN AND BLACK, MOIST, MED. DENSE TO DENSE, SILTY & CLAYEY SAND
- (B) UCP: GRAY, MOIST TO SAT., V. SOFT TO SOFT, SANDY SILT AND SANDY AND SILTY CLAY W/ SHELL FRAGMENTS
- (C) UCP: TAN BROWN YELLOW GRAY AND ORANGE, MOIST TO SAT., V. LOOSE TO MED. DENSE, SILTY & CLAYEY SAND



NOTE: BORINGS LOCATED AT 16+25, 16+75, 17+40, AND 18+75 DRILLED BY OTHERS

FOR -L- ALIGNMENT, SEE SHEET NO. 4


10 11 12 13 14 15 16 17 18 19 20 21 22

5/14/99
C:\NOV-2007\0328
T:\Projects\2007\017063\00 NCDOT GEU B-4863 Roadway\B4863.NCDOT.Electronic.File.Tree\Geotech\InvestigationDesign\B4863.GEO.ROWY\CADD.GEOTECH\PlanProf\B4863.GEO.pfl.09.dgn

PROJECT REFERENCE NO.	SHEET NO.
B-4863	9
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

-L-

NOTE: NO BORINGS ON THIS SHEET



FOR -L- ALIGNMENT, SEE SHEET NO. 5


5/14/99
D:\NOV-2017\407
Projects\2017\017063.00 NCDOT GEU B-4863 Roadway\B4863.NCDOT.Electronic.File.Tree\Geotech\InvestigationDesign\B4863.GEO.RDWY\CADD.GEOTECH\PlanProf\B4863.GEO.pfl.10.dgn

PROJECT REFERENCE NO. <i>B-4863</i>	SHEET NO. <i>10</i>
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

-L-

NOTE: NO BORINGS ON THIS SHEET


[Empty Signature Box]



FOR -L- ALIGNMENT, SEE SHEET NO. 6

-L-

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-4	44' LT	51+20	0.3'-3.0'	A-2-4	ND	NP	9	87	0	4	100	99	7	6	0.4
S-5	23' RT	52+61	3.2'-3.9'	A-2-4	ND	NP	19	68	5	8	99	95	14	22	-
S-6	13' LT	54+11	3.1'-4.8'	A-2-6	28	12	12	55	5	28	100	98	34	19	1.6



- (A) ROADWAY EMBANKMENT: GRAY TAN AND BLACK, MOIST, LOOSE, SILTY & CLAYEY SAND
- (B) UCP: GRAY, MOIST TO SAT., V. SOFT TO SOFT, SANDY SILT
- (C) UCP: TAN BROWN YELLOW GRAY AND ORANGE, MOIST TO SAT., V. LOOSE TO MED. DENSE, SILTY & CLAYEY SAND

COASTAL PLAIN: GRAY, WET, SOFT, SILTY & SANDY CLAY (YORKTOWN FORMATION)

COASTAL PLAIN: GRAY AND GREEN, SAT., SOFT, SILTY & CLAYEY SAND W/ TRACE FOSSILS (YORKTOWN FORMATION)

NOTE: BORINGS LOCATED AT 50+75, 51+30, AND 51+75 DRILLED BY OTHERS

FOR -L- ALIGNMENT, SEE SHEET NO. 7


5/14/99
 15-FEB-2018 08:46
 I:_Frac\jcs\1207\017063.00 NCDOT GEU B-4863 Roadway\B4863.NCDOT.Electronic.File_Tree\Geotech\InvestigationDesign\B4863.GEO_ROWY\CADD\GEO\TECH\PlanProf\B4863.GEO.plt.1.dgn

5/14/99
 I:\FEB-2018\426\14\Projects\12617\G17063.00 NCDOT GEU B-4863 Roadway\B4863.NCDOT.Electronic.File.Tree\Geotech\InvestigationDesign\B4863.GEO.RDWY\CADD.GEOTECH\PlanProf\B4863.GEO.pfl.12.dgn

-Y-

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-7	4 FT RT	11+00	1.2'-2.3'	A-2-4	ND	NP	60	33	1	6	100	84	7	8	1.4

- (A) ROADWAY EMBANKMENT: BROWN GRAY AND TAN, MOIST, LOOSE, SILTY SAND W/ GRAVEL AND SHELL FRAGMENTS
- (B) UCP: GRAY AND TAN, SAT., MED. DENSE, CLEAN SAND.



FOR -Y- ALIGNMENT, SEE SHEET NO. 4

10 11 12 13

-DRIVE-

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-3	1 FT RT	11+05	1.3'-2.4'	A-6	33	17	13	43	15	29	100	95	47	20	-

- (A) ROADWAY EMBANKMENT: TAN AND GRAY, DRY, LOOSE, CLEAN SAND W/ GRAVEL AND SHELL FRAGMENTS
- (B) UCP: GRAY, WET TO SAT., MED. DENSE, CLEAN SAND
- (C) UCP: BLACK AND GRAY, WET, SOFT, SANDY CLAY



FOR -DRIVE- ALIGNMENT, SEE SHEET NO. 4

10 11 12 13