PROJECT NO.	SHEET NO.	TOTAL NO.
I-5746C 52024.3.4	14	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	3030000000-E STEEL BEAM GUARDRAIL	3210000000-N GUARDRAIL END UNITS, CAT-1	3287000000-N GUARDRAIL END UNITS, TYPE TL-3	3317000000-N GUARDRAIL ANCHOR UNITS, TYPE B-77	3360000000-E REMOVE EXISTING GUARDRAIL	3533000000-E CHAIN LINK FENCE, 60" FABRIC	3539000000-E METAL LINE POSTS FOR 60" CHAINLINK FENCE	3545000000-E METAL TERMINAL POSTS FOR 60" CHAIN LINK FENCE	4600000000-N INTERSTATE LANE CLOSURE	4600000000-N RAMP/LOOP CLOSURE	4600000000-N STREET LANE CLOSURE	5255000000-N PORTABLE LIGHTING	6000000000-E TEMPORARY SILT FENCE	6029000000-E SAFETY FENCE	6071010000-E WATTLE	6117500000-N CONCRETE WASHOUT STRUCTURE	7444000000-E INDUCTIVE LOOP SAWCUT
										MI	FT	LF	EA	EA	EA	LF	LF	EA	EA	EA	EA	EA	LS	LF	LF	LF	EA	LF
52024.3.4	Mecklenburg	1	I-277 WB BROOKSHIRE FRWY	FROM 10TH ST. TO JOHNSON ST (MP 2.72 TO MP 4.04)	1,2,3,4,7	3		NO	NO	1.32	42									306				300	150	200	3	
TOTAL FOR MAP NO. 1										**1.32**										**306**				**300**	**150**	**200**	**3**	
52024.3.4	Mecklenburg	2	I-277 EB BROOKSHIRE FRWY	FROM JOHNSON ST BRIDGE TO 10TH ST BRIDGE (MP 0.38 TO MP 1.69)	1,2,3,4,7	3		NO	NO	1.32	42									306				300	150	200	3	
TOTAL FOR MAP NO. 2										**1.32**										**306**				**300**	**150**	**200**	**3**	
52024.3.4	Mecklenburg	33	WB LOOP ON RAMP	FROM PAVEMENT JOINT AT GRAHAM ST TO CONCRETE PAVEMENT JOINT	6,11	1		NO	NO	0.065	17										9			100	50	100	1	
TOTAL FOR MAP NO. 33										**0.065**											**9**			**100**	**50**	**100**	**1**	
52024.3.4	Mecklenburg	34	WB ON RAMP	FROM CROSSWALK AT 12TH ST TO ASPHALT PAVEMENT JOINT	5,6,10	1		NO	NO	0.08	16										9			100	50	100	1	
TOTAL FOR MAP NO. 34										**0.08**											**9**			**100**	**50**	**100**	**1**	
52024.3.4	Mecklenburg	35	WB OFF RAMP	FROM ASHALT PAVEMENT JOINT TO BRIDGE DECK OVER N. TRYON ST	5,6	1		NO	NO	0.048	16										9			100	50	100	1	
TOTAL FOR MAP NO. 35										**0.048**											**9**			**100**	**50**	**100**	**1**	
52024.3.4	Mecklenburg	36	WB ON RAMP	FROM CONCRETE JOINT AT N. CADWELL ST TO BEGINNING OF PHYSICAL GORE	6,12,13	1		NO	NO	0.057	16										9			100	50	100	1	
TOTAL FOR MAP NO. 36										**0.057**											**9**			**100**	**50**	**100**	**1**	
52024.3.4	Mecklenburg	37	WB OFF RAMP	FROM END PHYSICAL GORE TO ASPHALT PAVEMENT JOINT AT 12TH ST	5,6,12,13	1		NO	NO	0.12	16										10		*	100	50	100	1	
TOTAL FOR MAP NO. 37										**0.12**											**10**			**100**	**50**	**100**	**1**	
52024.3.4	Mecklenburg	38	EB ON RAMP	FROM BEGINNING OF PHYSICAL GORE AT N. DAVIDSON ST TO ASPHALT PAVEMENT JOINT AT BOTTOM OF RAMP	6,8	1		NO	NO	0.169	16										10			300	50	150	1	
TOTAL FOR MAP NO. 38										**0.169**											**10**			**300**	**50**	**150**	**1**	
52024.3.4	Mecklenburg	39	EB ON RAMP	FROM PHYSICAL GORE AT N. BREVARD ST TO ASPHALT PAVEMENT JOINT AT TOP OF RAMP	5	1		NO	NO	0.041	16										20			300	50	150	1	
TOTAL FOR MAP NO. 39										**0.041**											**20**			**300**	**50**	**150**	**1**	
52024.3.4	Mecklenburg	40	EB OFF RAMP	FROM ASPHALT PAVEMENT JOINT AT TOP OF RAMP TO N. COLLEGE ST	6,9,10	1		NO	NO	0.055	17										20			300	50	150	1	200
TOTAL FOR MAP NO. 40										**0.055**											**20**			**300**	**50**	**150**	**1**	**200**
52024.3.4	Mecklenburg	41	EB OFF RAMP	FROM ASPHALT PAVEMENT JOINT TO N CHURCH ST	6,10,12,13	1		NO	NO	0.083	21										9			100	50	100	1	420
TOTAL FOR MAP NO. 41										**0.083**											**9**			**100**	**50**	**100**	**1**	**420**
52024.3.4	Mecklenburg	42	EB LOOP OFF RAMP	FROM ASHALT PAVEMENT JOINT TO ASPHALT PAVEMENT JOINT AT 10TH ST.	6	1		NO	NO	0.094	25										15			100	50	100	1	
TOTAL FOR MAP NO. 42										**0.094**											**15**			**100**	**50**	**100**	**1**	
52024.3.4	Mecklenburg	43	NONE INTERSTATE STREETS	ALL UNDER PASS STREETS		2		NO	NO	0.25	44											62						
TOTAL FOR MAP NO. 43										**0.25**												**62**						
TOTAL FOR PROJ NO. 52024.3.4										**3.702**		**12,237**	**6**	**12**	**20**	**12,237**	**9,460**	**946**	**237**	**612**	**120**	**62**	**1**	**2,200**	**800**	**1,550**	**16**	**620**
GRAND TOTAL										**3.702**		**12,237**	**6**	**12**	**20**	**12,237**	**9,460**	**946**	**237**	**612**	**120**	**62**	**1**	**2,200**	**800**	**1,550**	**16**	**620**