PROJ. REFERENCE NO.	SHEET NO.
17BP.2.R.92	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+65.00	0	0
11+00.00	20	0
11+50.00	36	0
12+00.00	58	1
12+50.00	75	2
13+00.00	70	8
13+34.63	44	9

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+22.37	0	0
14+50.00	28	18
15+00.00	58	24
15+50.00	53	8
16+00.00	33	2
16+50.00	26	4
16+61.00	6	1

Station Drv	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+16.42	0	0
10+25.00	1	7
10+50.00	17	10
10+75.00	23	0
11+00.00	12	0