



Map 4 Patterson St SR1225 From Main St SR2739 to end of curb approx. 180' past Elizabeth St Mill 2" entire width to be flush with gutter Mill 0-11/2" 7' width along gutter Patching to be done by DOT forces Pave 11/2" S9.5B

Map 5 Patterson St SR1225 From approx 180' past Elizabeth St to NC152 Mill 0-11/2" incidental milling beginning, end and at all SR intersections Asphalt surface treatment, Matcoat #67M stone Pave 11/2" S9.5B Patching to be done by DOT forces

Map 6 Ketchie St SR1227 From NC152 to Main St SR2739 Mill 1 1/2" entire width, curb reveal Mill 0-11/2" 7' width along gutter Pave 11/2" S9.5B

Map 11 Stirewalt Rd SR1419 From Patterson St SR1225 to NC152 Mill 0-11/2" incidental milling at end and all SR intersections Asphalt surface treatment, Matcoat #78M stone Pave 11/2" S9.5B

