12-3T3O8H2

| COMPUTED BY: | LEAH YOUNG, PE | DATE: | 11/19/2021 |
|---|---|---|---|
| CHECKED BY: | GREG BRICKHAM, PE | DATE: | 11/19/2021 |

| PROJECT NO. | SHEET NO. |
|---|---|
| U-5738 | 3D-4 |

# NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
# DIVISION OF HIGHWAYS

**Note: Invert Elevations indicated are for Bid Purposes only and shall not be used for project construction stakeout.**
**See "Standard Specifications For Roads and Structures, Section 300-5".**

## *LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48 INCHES & UNDER)*

| LINE & STATION / SIZE / THICKNESS OR GAUGE | OFFSET | | STRUCTURE NUMBER FROM | STRUCTURE NUMBER TO | TOP ELEVATION FT. | INVERT ELEVATION FT. | INVERT ELEVATION FT. | MINIMUM REQUIRED SLOPE % | Side Drain Pipe (RCP, CSP, CAAP, HDPE, or PVC) 12 | 15 | 18 | 24 | DO NOT USE RCP | DO NOT USE CSP | DO NOT USE CAAP | DO NOT USE HDPE | DO NOT USE PVC | C. S. PIPE 12 .064 | 15 .064 | 18 .064 | 24 .064 | R. C. PIPE CLASS IV 12 | 15 | 18 | 24 | 30 | 36 | 42 | 48 | 54 | 60 | 66 | 72 | 78 | 84 | 36" WELDED STEEL PIPE 0.500" THICK, GRADE B IN SOIL | 36" WELDED STEEL PIPE 0.500" THICK, GRADE B NOT IN SOIL | ENDWALLS STD. 838.01 OR STD. 838.11 (UNLESS NOTED OTHERWISE) CY | REINFORCED ENDWALLS CY | DRAINAGE STRUCTURE MASONRY CY | QUANTITIES FOR DRAINAGE STRUCTURES (NOTE: TOTAL LIN. FT. FOR PAY QUANTITY SHALL BE A + (1.3 X B)) 0' THRU 5' EACH | A 5' THRU 10' LIN. FT. | B 10' AND ABOVE LIN. FT. | C.B. STD. 840.01 OR STD. 840.02 | FRAME, GRATES, AND HOOD STD. 840.03 GRATE TYPE E | F | G | | CONCRETE TRANSITIONAL SECTION D.I. STD. 852.04 OR STD. 852.06 | C.B. STD. 852.05 | OPEN THROAT C.B. STD. 840.04 OR STD. 840.05 | D.I. STD. 840.14 OR STD. 840.15 | D.I. FRAME AND GRATES STD. 840.16 | G.D.I. TYPE "A" STD. 840.17 OR STD. 840.26 | G.D.I. TYPE "B" STD. 840.18 OR STD. 840.27 | G.D.I. TYPE "D" STD. 840.19 OR STD. 840.28 | G.D.I. (W.S. FLAT) FRAME WITH GRATE STD. 840.20 | G.D.I. (W.S. FLAT) FRAME W/ 2 GRATES STD. 840.20 | G.D.I. (W.S. SAG) FRAME W/ GRATE STD. 840.22 | G.D.I. (W.S. SAG) FRAME W/ 2 GRATES STD. 840.22 | G.D.I. (N.S. SAG) FRAME W/ GRATE STD. 840.24 | G.D.I. (N.S. SAG) FRAME W/ 2 GRATES STD. 840.24 | G.D.I. (N.S. FLAT) FRAME W/ GRATE STD. 840.29 | G.D.I. (N.S. FLAT) FRAME W/ 2 GRATES STD. 840.29 | J.B. STD. 840.31 OR STD. 840.32 | ANGLED VANE GRATES AND FRAMES STD. 840.33 | T.B.J.B. STD. 840.34 | T.B.D.I. STD. 840.35 | T.B.D.I. FOR STEEL GRATES STD. 840.36 | SPRING BOX STD. 840.41 | 36" PIPE END SECTION | M.H. STD. 840.51, STD. 840.52, OR STD. 840.53 | M.H. FRAME AND COVER STD. 840.54 | ADJUST C.B. | ADJUST D.I. | 15" ELBOW | 18" ELBOW | 24" ELBOW | PIPE CLEAN OUT EA | FLOWABLE FILL CY | CONCRETE COLLARS CL. "B" STD. 840.72 CY | CONCRETE AND BRICK PIPE PLUG STD. 840.71 CY | PIPE REMOVAL LIN. FT. | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| L 76+12 | 42 | RT | 0817 | | 730.2 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | 1 | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | 0817 | 0814 | | 727.2 | 722.2 | | | | | | | | | | | | | | | | 172 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| L 76+53 | 48 | RT | 0818 | | 731.2 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | 1 | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | 0818 | 0817 | | 728.2 | 727.2 | | | | | | | | | | | | | | | | 40 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Y8 10+75 | 0 | CL | 0819 | | | 730.7 | 730.4 | | | | | | | | | | | | | | | 56 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | DRIVEWAY PIPE |
| Y5 11+00 | 25 | LT | 0822 | | 734.3 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | OPEN ENDED PIPE |
| | | | 0822 | 0821 | | 732.8 | 731.5 | | | | | | | | | | | | | | | | | 44 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Y5 11+00 | 19 | RT | 0821 | | 733.7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | | | | | | | | | | | 1 | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | 0821 | 0820 | | 731.5 | 730.7 | | | | | | | | | | | | | | | | | 52 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| L 20+26 | 45 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.6 | | | 8 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| RPA 11+43 | 25 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.3 | | | 4 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| RPA 11+44 | 31 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.2 | | | 4 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 76+89 | 46 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.065 | | PIPE PLUG |
| L 76+99 | 40 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.065 | | PIPE PLUG |
| L 41+42 | 25 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 2.0 | | | 44 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 41+99 | 17 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1.0 | | | 32 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 41+99 | 73 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1.4 | | | 45 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 40+51 | 24 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1.1 | | | 36 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 39+53 | 46 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 2.7 | | | 58 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 38+89 | 75 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1.6 | | | 53 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 35+87 | 67 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1.4 | | | 47 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 46+39 | 34 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 4.2 | | | 63 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 55+05 | 4 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.8 | | | 25 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 56+21 | 44 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 6.8 | | | 149 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 57+76 | 45 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 7.2 | | | 157 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 60+32 | 5 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 2.1 | | | 45 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 62+25 | 52 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 47.4 | | | 181 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 63+71 | 62 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 29.6 | | | 113 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 64+44 | 72 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 8.7 | | | 33 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 64+64 | 72 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1.0 | | | 4 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 63+15 | 62 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.5 | | | 10 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 76+38 | 65 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 7.0 | | | 107 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 76+89 | 42 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.6 | | | 9 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L76+96 | 19 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 2.4 | | | 36 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 77+02 | 20 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 2.7 | | | 41 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 77+30 | 66 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.9 | | | 19 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 77+52 | 7 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 9.8 | | | 150 | REMOVE OR PLUG AND FILL PER FIELD ENG. |
| L 25+53 | 246 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | CLEAN OUT EX. 24" CMP |
| L 31+84 | 51 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | CLEAN OUT EX. 15" CMP |
| Y2 10+00 | 6 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | CLEAN OUT EX. 18" RCP |
| Y2 13+46 | 10 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | CLEAN OUT EX. 18" RCP |
| L 73+77 | 59 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | CLEAN OUT EX. 24" RCP |
| L 75+59 | 87 | RT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | CLEAN OUT EX. 24" RCP |
| Y5 10+34 | 18 | LT | 0000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | CLEAN OUT EX. 12" RCP |
| SHEET TOTALS | | | | | | | | | | | | | | | | | | | | | | 56 | 212 | 96 | | | | | | | | | | | | | | | | | 3 | | | 2 | | | 2 | | | | | | | | | 1 | | | | 1 | | | | | | | | | | | | | | | | | | | 7 | 144 | | 0.130 | 1473 | |
| PROJECT TOTALS | | | | | | | | | | 668 | | | | | | | | | | | | 56 | 4020 | 188 | | | 320 | | | | | | | | | 54 | 54 | 3.400 | | | 73 | 7.3 | | 49 | 4 | 15 | 30 | | 19 | 6 | 1 | 19 | 19 | | | 2 | | | | 1 | | 1 | | | 1 | | 1 | | | | 1 | | 2 | 1 | | 26 | | | 7 | 144 | 1.2920 | 0.130 | 1473 | |

**ABBREVIATIONS**

| | |
|---|---|
| C.A.A. | CORRUGATED ALUMINIUM ALLOY |
| C.B. | CATCH BASIN |
| C.S. | CORRUGATED STEEL |
| D.I. | DROP INLET |
| G.D.I. | GRATED DROP INLET |
| H.D.P.E. | HIGH DENSITY POLYETHYLENE |
| J.B. | JUNCTION BOX |
| M.H. | MANHOLE |
| N.S. | NARROW SLOT |
| P.V.C. | POLYVINYL CHLORIDE |
| R.C. | REINFORCED CONCRETE |
| T.B.D.I. | TRAFFIC BEARING DROP INLET |
| T.B.J.B. | TRAFFIC BEARING JUNCTION BOX |
| W.S. | WIDE SLOT |