



## SECTION AT END BENT 1

\* #5 GI BAR MAY BE SHIFTED SLIGHTLY, AS NECESSARY, TO CLEAR DIAPHRAGM AND REINFORCING STEEL.




CONTRACTION JOINT DETAIL



#### PLAN AT BENT


\* NO WELDING OF FORMS OR FALSEWORK TO THE TOP OF GIRDER WILL BE PERMITTED IN THE LINK SLAB AREA



# SECTION THRU BENT


A  $\frac{3}{8}$ "X  $1\frac{1}{2}$ "DEEP CONTRACTION JOINT AT BENT CONTROL LINE SHALL BE SAWN WITHIN 24 HOURS OF POURING THE DECK. THE JOINT SHALL BE FILLED WITH JOINT SEALER MATERIAL. THE JOINT SEALER MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF TYPE B LOW MODULUS SILICONE SEALANT. SEE SECTION 1028 OF THE STANDARD SPECIFICATIONS.

NO WELDING OF FORMS OR FALSEWORK TO THE TOP OF THE GIRDER WILL BE PERMITTED IN THE LINK SLAB AREA.



## SECTION AT END BENT 2

#5 GIBAR MAY BE SHIFTED SLIGHTLY, AS NECESSARY, TO CLEAR DIAPHRAGM AND REINFORCING STEEL.



### NOTES

PROVIDE 11/4" BEAM BOLSTERS UPPER AT 4'-0" CENTERS ATOP THE METAL STAY-IN-PLACE FORMS TO SUPPORT THE BOTTOM MAT OF 'A' BARS.

CONCRETE PARAPET, SIDEWALK, AND MEDIAN BARRIER IN A CONTINUOUS UNIT SHALL NOT BE CAST UNTIL ALL SLAB CONCRETE HAS BEEN CAST AND HAS ATTAINED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.

THE CONTRACTOR MAY. WHEN NECESSARY. PROPOSE A SCHEME FOR AVOIDING INTERFERENCE BETWEEN METAL STAY-IN-PLACE FORM SUPPORTS OR FORMS AND GIRDER STIFFENERS OR CONNECTOR PLATES. THE PROPOSAL SHALL BE INDICATED, AS APPROPRIATE, ON EITHER THE STEEL WORKING DRAWINGS OR THE METAL STAY-IN-PLACE FORM WORKING DRAWINGS.

DOWELS SHALL BE PLACED IN THE SAME HORIZONTAL PLANE AS THE TOP AND BOTTOM SLAB REINFORCEMENT STEEL.

STRUCTURAL STEEL ERECTION IN A CONTINUOUS UNIT SHALL BE COMPLETE BEFORE FALSEWORK OR FORMS ARE PLACED ON THE UNIT.

SEE "SECTION THRU SIDEWALK" FOR SIDEWALK REINFORCING AND RUSTICATION GROOVE DETAILS.

SEE "SECTION THRU RAISED MEDIAN" FOR MEDIAN REINFORCING DETAILS.

FOR END RAIL POST AND PARAPET REINFORCING, SEE THREE BAR METAL RAIL DETAILS



Copyright © 2006 Vaughn & Melton, Inc. All Rights Reserved

PROJECT NO. <u>U-5738</u>

ROWAN COUNTY

STATION: 70+72.50 -L-

SHEET 2 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

> SUPERSTRUCTURE TYPICAL SECTION DETAILS

12/13/2021

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DWN.BY: FRJ CHKD. BY: CDB

SHEET NO REVISIONS S-7 NO. BY: DATE: BY: DATE: TOTAL SHEETS

DATE: 11/18 DATE: 11/18 DES. EGR. OF RECORD: CDB DATE: 11/18