

PLAN OF SIDEWALK (STAGE I & STAGE II)

<u>span a</u>

NOTES

CONCRETE DECK SLAB."

BEEN SCREEDED OFF.

OF 3000 PSI.

FT. IN LENGTH.

THE CONCRETE AND REINFORCING STEEL REQUIRED FOR THE SIDEWALKS

IS INCLUDED IN THE SUPERSTRUCTRE BILL OF MATERIAL AND PAYMENT IS INCLUDED IN THE SQUARE FOOT PRICE BID FOR "REINFORCED

THE #4U1 BARS MAY BE PUSHED INTO GREEN CONCRETE AFTER SPAN HAS

SIDEWALK SHALL NOT BE CAST UNTIL ALL SLAB CONCRETE IN THE UNIT

THE JOINT IN THE DECK AT THE END BENTS AND LINK SLAB AT THE BENT

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE SIDEWALK IN ACCORDANCE WITH ARTICLE 825-10(B)

OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINTS SHALL BE

LOCATED AT A SPACING OF 8 FT. TO 10 FT. BETWEEN EXPANSION JOINTS.


NO CONTRACTION JOINT WILL BE REQUIRED FOR SEGMENTS LESS THAN 10

HAS BEEN CAST AND HAS REACHED A MINIMUM COMPRESSIVE STRENGTH

SHALL BE SAWED PRIOR TO THE CASTING OF THE SIDEWALKS.

ALL REINFORCING STEEL IN SIDEWALKS SHALL BE EPOXY COATED.

RIGHT SIDE SHOWN, LEFT SIDE SIMILAR



SECTION THRU SIDEWALK

* ''U'' BARS MAY BE PUSHED INTO GREEN CONCRETE AFTER SPAN HAS BEEN SCREEDED OFF.

<u>SPAN B</u>

□ Boone, NC 828·355·9933 ☐ Tri-Cities, TN 423 • 467 • 8401 ☐ Knoxville, TN 865 • 546 • 5800 **Vaughn & Melfon** □ Spartanburg,SC Consulting Engineers Asheville, ☐ Charleston, SC ■ North Carolina 843 • 974 • 5650 770 • 627 • 3509

828 · 253 · 2796 ☐ Middlesboro, KY 606 • 248 • 6600 Raleigh, NC 🔲 Charlotte, NC 919·977·9455 704·357·0488 🗆 Atlanta, GA

Copyright © 2006 Vaughn & Melton,Inc. All Rights Reserved

NESSI ON 12/13/2021

SUPERSTRUCTURE

STATION: 70+72.50 -L-

PROJECT NO. <u>U-5738</u>

SHEET 4 OF 4

PLAN OF SPANS SIDEWALKS

STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

ROWAN_ COUNTY

DWN.BY: FRJ

SHEET NO REVISIONS S-11 DATE: BY: DATE: NO. BY: TOTAL SHEETS

DATE: 11/18 DATE: 11/18 DES. EGR. OF RECORD: CDB DATE: 11/18

OCUMENT NOT CONSIDERED | CHKD. BY: CDB FINAL UNLESS ALL SIGNATURES COMPLETED