PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.05.17.10921.1, Etc.	22	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-N BORROW	0264000000-E SHOULDER GRADING	0122000000-E INCIDENTAL STONE BASE	0126000000-E AGGREGATE SHOULDER BORROW	0129700000-E 1½" MILLING	1308000000-E 0" TO 1.5" MILLING	0" TO 1.25" MILLING	1330000000-E INCIDENTAL MILLING	0151900000-E SURFACE COURSE, S9.5B	0523000000-E SURFACE COURSE, S9.5C	0575000000-E ASPHALT BINDER FOR PLANT MIX	0704000000-E PATCHING EXISTING PAVEMENT	0849000000-E 2'-6" CURB & GUTTER	0591000000-E 4" CONCRETE SIDEWALK	0600000000-E RETROFIT EXISTING CURB RAMP	0613000000-N REMOVE AND REPLACE CURB RAMPS	0738000000-E GENERIC PAVING ITEM REMOVE SIDEWALK	0759000000-E GENERIC PAVING ITEM, REMOVE CURB RAMPS	0830000000-N ADJUST MANHOLES	0845000000-N ADJUST METER OR VALVE BOX	4600000000-N GENERIC TRAFFIC CONTROL ITEM PEDESTRIAN TRANSPORT SERVICE	GENERIC TRAFFIC CONTROL ITEM AUDIBLE WARNING DEVICES	0000000000 TEMPORARY SILT FENCE	0710100000 WATTLE	6084000000-E SEED & MULCHING	1170000000-N RESPONSE FOR EROSION CONTROL	4440000000-E INDUCTIVE LOOP SAWCUT
									MI	FT	CY	SMI	TONS	TON	SY	SY	SY	SY	TONS	TONS	TON	TONS	LF	SY	EA	EA	SY	EA	EA	EA	EA	EA	LF	LF	AC	EA	LF
2022CPT.05.17.20921.1	Wake	35	SR 3599 - KEYNES CT	SR 3598 - OLD WARDEN RD TO CUL-DE-SAC	2	2	NO	NO	0.08	20	8	0.16	4						93		6	55											12	30	0.12		
		36	SR 4227 - N HAWTHORNE WAY	SR 1834 - NORWOOD RD TO CUL-DE-SAC	3	2	NO	NO	1.116	20	109	2.18	56			120		272	1,169		78	1,073							13				159	400	1.59	1	
		37	SR 4437 - HENNING DR	SR 1844 - MT.VERNON CHURCH RD TO CUL-DE-SAC	2	2	NO	NO	0.165	20	16	0.33	8					70	159		11	205											24	60	0.24		
		38	SR 4438 - ETHRIDGE CT	SR 4437 - HENNING ST TO CUL-DE-SAC	2	2	NO	NO	0.248	20	25	0.50	12						235		16	270											36	100	0.36		
		39	SR 4439 - MERSEY LN	SR 4437 - HENNING ST TO SR 3595 - GRAFTON RD	2	2	NO	NO	0.23	20	23	0.46	12						196		13	450											33	90	0.33		
		40	SR 4440 - LOGSDON LN	SR 4439 - MERSEY LN TO CUL-DE-SAC	2	2	NO	NO	0.061	20	6	0.12	3						75		5	110											9	30	0.09		
		41	SR 4444 - TREDWOOD DR	SR 1844 - MT.VERNON CHURCH RD TO CUL-DE-SAC	2	2	NO	NO	0.166	20	16	0.33	8					70	165		11	150											24	70	0.24		
		42	SR 4445 - NOLSTEAD CT	SR 4444 - TREDWOOD DR TO CUL-DE-SAC	2	2	NO	NO	0.094	20	9	0.19	5						100		7	105											14	40	0.14		
		43	SR 4483 - BOULDER CREEK LN	SR 1841 - VICTORY CHURCH TO DEAD END	2	2	NO	NO	0.798	20	80	1.60	40					94	679		46	1,590											116	300	1.16	1	
		44	SR 4484 - LAUREL ROCK LN	CUL-DE-SAC TO CUL-DE-SAC	2	2	NO	NO	0.26	18	7	0.52	13						235		16	385											38	100	0.38		
		45	SR 4485 - ROCK CANYON RD	CUL-DE-SAC TO CUL-DE-SAC	2	2	NO	NO	0.215	18	21	0.43	11						207		14	340								2			31	80	0.31		
		46	SR 4486 - SAND PEBBLE PL	SR 4483 - BOULDER CREEK LN TO CUL-DE-SAC	2	2	NO	NO	0.107	18	10	0.21	5						103		7	200											16	40	0.16		
		47	SR 4487 - STONE CANYON CT	SR 4486 - SAND PEBBLE PL TO CUL-DE-SAC	2	2	NO	NO	0.068	18	7	0.14	3						72		5	245											10	30	0.10		
		48	SR 4488 - SUNNYSTONE WAY	SR 1841 - VICTORY CHURCH TO CUL-DE-SAC	2	2	NO	NO	0.152	18	15	0.30	8					63	140		9	325											22	60	0.22		
		49	SR 4489 - WEATHER ROCK CT	SR 4483 - BOULDER CREEK LN TO CUL-DE-SAC	2	2	NO	NO	0.071	18	7	0.14	4						73		5	145											10	30	0.10		
		50	SR 4640 - WILD ORCHID TRL	SR 1841 - VICTORY CHURCH TO SR 1841 - VICTORY CHURCH	2	2	NO	NO	0.505	21	50	1.01	25					250	473		32	692											73	190	0.73	1	
		51	SR 4641 - SCARLET SAGE CT	SR 4640 - WILD ORCHID TR TO CUL-DE-SAC	2	2	NO	NO	0.043	20	4	0.09	2						61		4	65											6	20	0.06		
		52	SR 4642 - BARTON RIDGE CT	SR 4640 - WILD ORCHID TR TO CUL-DE-SAC	2	2	NO	NO	0.04	18	4	0.08	2						53		4	45											6	20	0.06		
		53	SR 4643 - HIDEAWAY CT	SR 4640 - WILD ORCHID TR TO CUL-DE-SAC	2	2	NO	NO	0.055	18	6	0.11	3						62		4	20											8	20	0.08		
		54	SR 4664 - ORCHID VALLEY RD	SR 4640 - WILD ORCHID TR TO CUL-DE-SAC	2	2	NO	NO	0.233	20	23	0.47	12						216		14	200											34	90	0.34		
		55	SR 4665 - PRIMROSE VALLEY CT	SR 4664 - ORCHID VALLEY TO CUL-DE-SAC	2	2	NO	NO	0.12	20	12	0.24	6						120		8	120											17	50	0.17		
		56	SR 4666 - VALLY MIST CT	SR 4640 - WILD ORCHID TR TO CUL-DE-SAC	2	2	NO	NO	0.061	20	6	0.12	3						71		5	70											9	30	0.09		
		57	SR 4667 - SWEET BIRCH CT	SR 4664 - ORCHID VALLEY TO CUL-DE-SAC	2	2	NO	NO	0.045	20	5	0.09	2						58		4	45											7	20	0.07		
		58	SR 4688 - SUNNYSTONE WAY	SR 4689 - JASPER LN TO SR 4939 - SUNNYSTONE WAY	2	2	NO	NO	0.21	20	25	0.42	13					70	170		11	270							3				37	100	0.37		
		59	SR 4690 - WILD ORCHID TRL	SR 1841 - VICTORY CHURCH TO CUL-DE-SAC	2	2	NO	NO	0.155	18	15	0.31	8					76	141		9	50							2				23	60	0.23		
		60	SR 4933 - STONE SPRING RD	SR 1841 - VICTORY CHURCH TO CUL-DE-SAC	2	2	NO	NO	0.155	18	15	0.31	8					63	137		9	305											23	60	0.23		
		61	SR 4970 - LARKA CT	SR 4227 - N HAWTHORNE WAY TO CUL DE-SAC	2	2	NO	NO	0.092	20	9	0.18	5						97		6	40								1			13	40	0.13		
		62	SR 4977 - TREDWOOD DR	SR 1844 - MT.VERNON CHURCH RD TO CUL-DE-SAC	2	2	NO	NO	0.166	20	16	0.33	8					167	168		11	110											24	70	0.24		
		63	SR 4986 - CLAYBANK PL	SR 3298 TO SR 4986 - TREDWOOD DR	2	2	NO	NO	0.44	20	44	0.88	22					73	380		25	225											64	160	0.64		
		64	SR 4989 - SUNNYSTONE WAY	CUL-DE-SAC TO SR 4688 - SUNNYSTONE WAY	3	2	NO	NO	0.613	20	61	1.23	31						543		36	775							1				89	230	0.89	1	
		65	SR 4990 - AMORRETTO WAY	SR 1840 - HICKORY GROVE TO CUL-DE-SAC	2	2	NO	NO	0.894	20	89	1.79	45					87	979		66	1,150							4				130	330	1.30	1	
		66	SR 4991 - BIG CREEK RD	SR 5606 - BARTONS ENCLAVE LN TO SR 4989 - SUNNYSTONE WAY	2	2	NO	NO	0.494	20	49	0.99	25						421		28	585							1				72	180	0.72		
		67	SR 5109 - OVERLEAF CT	SR 3594 - KINGSDALE DR TO CUL-DE-SAC	2	2	NO	NO	0.18	20	18	0.36	9						177		12	10											26	70	0.26		
		68	SR 5141 - SIMTREE CT	SR 3593 - DARFIELD DR TO CUL-DE-SAC	2	2	NO	NO	0.06	20	6	0.12	3					63	77		5	120											9	30	0.09		
		69	SR 5142 - CARLOW CT	SR 3596 - HEARTLEY DR TO SR 5142 - CARLOW CT	2	2	NO	NO	0.169	20	14	0.29	8				115		144		10	235											21	60	0.21		
		70	SR 5143 - HOVIS CT	SR 3595 - GRAFTON RD TO CUL-DE-SAC	2	2	NO	NO	0.03	20	3	0.06	2						48		3	60											4	20	0.04		
		71	SR 5606 - BARTONS ENCLAVE LN	SR 4990 - AMMORETTO WAY TO SR 4990 - AMMORETTO WAY	2	2	NO	NO	0.83	20	49	1.66	25					75	712		48	775								2			72	180	0.72		
		72	SR 5607 - INDIGO MOON WAY	SR 5606 - BARTONS ENCLAVE LN TO CUL-DE-SAC	2	2	NO	NO	0.432	20	43	0.86	22						384		26	660								2			63	160	0.63		
		73	SR 5608 - SORRENTO CT	SR 5607 - INDIGO MOON WAY TO CUL-DE-SAC	2	2	NO	NO	0.04	20	4	0.08	2						53		4	30								2			6	20	0.06		
		74	SR 5609 - MARTIN FARM RD	SR 4990 - AMMORETTO WAY TO CUL-DE-SAC	2	2	NO	NO	0.175	20	17	0.35	9						171		11	115							2				25	70	0.25		
		75	SR 5610 - KISSING CT	SR 5607 - INDIGO MOON WAY TO CUL-DE-SAC	2	2	NO	NO	0.086	20	8	0.17	4						95		6	210							1	2			13	40	0.13		
		76	SR 5611 - SIX PENCE CT	SR 4989 - SUNNYSTONE WAY TO CUL-DE-SAC	2	2	NO	NO	0.04	18	4	0.08	2						52		3	45											6	20	0.06		
TOTAL FOR PROJ NO. 2022CPT.05.17.20921.1									**21.217**		**2,020**	**42.34**	**1,053**	**70**		**120**	**115**	**4,088**	**20,669**		**1,383**	**24,670**							**28**	**11**			**2,982**	**7,820**	**29.83**	**14**	
																235																				