

| | | |
|---------------------|-----------|-----------|
| PROJECT NO. | SHEET NO. | TOTAL NO. |
| 2023CPT.09.06.20341 | 13 | |

SUMMARY OF QUANTITIES

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | 0106000000-E | 1220000000-E | 1245000000-E | 1297000000-E | | | | 1308000000-E | | 1330000000-E | 1491000000-E | 1519000000-E | 1523000000-E | 1575000000-E | 1704000000-E | 1775000000-E | 1838000000-E | 2830000000-N | 2845000000-N | 5255000000-N | 6000000000-E | 6071010000-E |
|---|---------|--------|---|--|--------|-------|-----------|--------------------------------|---------------------------|--------|-------|-------------------|-----------------------|-------------------------|--|--|--|--|--------------------|---------------------|-----------------------|-----------------------|------------------------------|----------------------------|---|--|------------------|----------------------------|-------------------|----------------------|--------------|--------------|--------------|
| | | | | | | | | | | | | BORROW EXCAVATION | INCIDENTAL STONE BASE | SHOULDER RECONSTRUCTION | MILLING ASPHALT PAVEMENT, 1 1/2" DEPTH | MILLING ASPHALT PAVEMENT, 5 1/2" DEPTH | MILLING ASPHALT PAVEMENT, 0" TO 2.5" DEPTH | MILLING ASPHALT PAVEMENT, 0" TO 1 1/2" DEPTH | INCIDENTAL MILLING | BASE COURSE, B25.0C | SURFACE COURSE, S9.5B | SURFACE COURSE, S9.5C | ASPHALT BINDER FOR PLANT MIX | PATCHING EXISTING PAVEMENT | ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE | EMULSION FOR ASPHALT SURFACE TREATMENT | ADJ. OF MANHOLES | ADJ. OF METER OR VALVE BOX | PORTABLE LIGHTING | TEMPORARY SILT FENCE | WATTLE | | |
| MI | FT | CY | TONS | SMI | SY | SY | SY | SY | SY | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | EA | EA | LS | LF | LF | |
| 2023CPT.09.06.20341 | Forsyth | 1 | YADKINVILLE RD SR1525 | FROM NC67 TO END OF CURB WEST OF SWICEGOOD DR SR1434 | 2 | 2 | ZWU | NO | NO | 2.516 | 23-52 | 302 | 20 | 5.03 | 38,503 | | 1,470 | | 1,410 | | | 3,824 | 230 | 10 | | | 7 | 6 | | 1,006 | 101 | | |
| TOTAL FOR MAP NO. 1 | | | | | | | | | | | | 2.516 | | 302 | 20 | 5.03 | 38,503 | | 1,470 | | 1,410 | | 3,824 | 230 | 10 | | | 7 | 6 | | 1,006 | 101 | |
| 2023CPT.09.06.20341 | Forsyth | 2 | WALLBURG RD SR2691 | FROM BUSINESS PARK TO BEGINNING OF CURB AND GUTTER | 1 | 2 | ZWU | NO | NO | 0.237 | 24-54 | 28 | 10 | 0.47 | | 700 | | 1,712 | 239 | 493 | | | 44 | 10 | | | | | | 95 | 9 | | |
| TOTAL FOR MAP NO. 2 | | | | | | | | | | | | 0.237 | | 28 | 10 | 0.47 | 700 | | 1,712 | 239 | 493 | | 44 | 10 | | | | | | | 95 | 9 | |
| 2023CPT.09.06.20341 | Forsyth | 3 | CONRAD RD SR1305/ YADKINVILLE RD SR1525 | FROM SHALLOWFORD RD SR1001 TO PVT JOINT ON YADKINVILLE RD SR1525 | 3 | 2 | ZWU | NO | NO | 3.098 | 24-26 | 372 | 15 | 6.20 | | | | 2,258 | | | 4,358 | 288 | 553 | | | | 1 | 1 | | 1,239 | 124 | | |
| TOTAL FOR MAP NO. 3 | | | | | | | | | | | | 3.098 | | 372 | 15 | 6.20 | | | 2,258 | | 4,358 | 288 | 553 | | | 1 | 1 | | 1,239 | 124 | | | |
| 2023CPT.09.06.20341 | Forsyth | 4 | PINEY GROVE RD SR1969 | FROM US158 TO VANCE RD SR2014 | 10 | 2 | ZWU | NO | NO | 4.756 | 24.5 | 571 | 275 | 9.51 | | | | 3,384 | | | 7,040 | 469 | 972 | 73,982 | 29,593 | | | 5 | | 1,902 | 190 | | |
| TOTAL FOR MAP NO. 4 | | | | | | | | | | | | 4.756 | | 571 | 275 | 9.51 | | | 3,384 | | 7,040 | 469 | 972 | 73,982 | 29,593 | | 5 | | 1,902 | 190 | | | |
| 2023CPT.09.06.20341 | Forsyth | 5 | PINEY GROVE RD SR1969 | FROM VANCE RD SR2014 TO NC150 | 2,6 | 2 | MU | NO | NO | 1.919 | 24-53 | 230 | 60 | 3.84 | 41,382 | | | 995 | | | 4,091 | 246 | 10 | | | 15 | 10 | | 768 | 77 | | | |
| TOTAL FOR MAP NO. 5 | | | | | | | | | | | | 1.919 | | 230 | 60 | 3.84 | 41,382 | | 995 | | 4,091 | 246 | 10 | | 15 | 10 | | 768 | 77 | | | | |
| 2023CPT.09.06.20341 | Forsyth | 6 | W CLEMMONSVILLE RD SR1120 | FROM OLD SALISBURY RD SR3011 TO EBERT RD SR2902 | 4 | 2 | ZWU | NO | NO | 1.082 | 25-51 | 130 | 35 | 2.16 | 18,929 | | | 506 | | 1,844 | | | 128 | 100 | | | 1 | 9 | | 433 | 43 | | |
| TOTAL FOR MAP NO. 6 | | | | | | | | | | | | 1.082 | | 130 | 35 | 2.16 | 18,929 | | 506 | | 1,844 | | 128 | 100 | | 1 | 9 | | 433 | 43 | | | |
| 2023CPT.09.06.20341 | Forsyth | 7 | OLD RURAL HALL RD SR2207/ N LIBERTY ST SR2456 | FROM NORTH OF MOTOR RD TO NEW PVT JOINT AT N LIBERTY ST SR2456 | 7,8,9 | 2 | ZWU | NO | NO | 0.897 | 23-60 | 108 | 15 | 1.79 | 2,811 | | | 2,738 | | 4,164 | | 2,157 | 130 | 10 | 18,129 | 7,251 | 20 | 10 | | 359 | 36 | | |
| TOTAL FOR MAP NO. 7 | | | | | | | | | | | | 0.897 | | 108 | 15 | 1.79 | 2,811 | | 2,738 | | 4,164 | | 2,157 | 130 | 10 | 18,129 | 7,251 | 20 | 10 | | 359 | 36 | |
| 2023CPT.09.06.20341 | Forsyth | 8 | HANES MALL BLVD SR3153 | FROM US158/STRATFORD RD TO JONESTOWN RD SR1122 | 2,5,6 | 4 | MD | NO | NO | 1.648 | 48-60 | 25 | 10 | 0.50 | 69,532 | | | | | | 6,727 | 425 | 450 | | | 35 | 24 | 1 | 75 | 7 | | | |
| TOTAL FOR MAP NO. 8 | | | | | | | | | | | | 1.648 | | 25 | 10 | 0.50 | 69,532 | | | | 6,727 | 425 | 450 | | 35 | 24 | 1 | 75 | 7 | | | | |
| TOTAL FOR PROJ NO. 2023CPT.09.06.20341 | | | | | | | | | | | | 16.153 | | 1,766 | 440 | 29.50 | 171,157 | 700 | 1,470 | 2,738 | 14,429 | 239 | 2,337 | 28,197 | 1,960 | 2,115 | 92,111 | 36,844 | 79 | 65 | 1 | 5,877 | 587 |
| GRAND TOTAL | | | | | | | | | | | | 16.153 | | 1,766 | 440 | 29.50 | 171,157 | 700 | 1,470 | 2,738 | 14,429 | 239 | 2,337 | 28,197 | 1,960 | 2,115 | 92,111 | 36,844 | 79 | 65 | 1 | 5,877 | 587 |

Note: All quantities listed include turn lanes and are estimates; Payment will be based on actual field measurements and quantities received