

PROJECT NO. 2023CPT.08.06.10771, 2023CPT.08.06.20771, 50526	SHEET NO. 11	TOTAL NO.
---	-----------------	-----------

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGT H	WIDT H	1245000000-E	1260000000-E	1297000000-E	1330000000-E	1491000000-E	1519000000-E	1523000000-E	1575000000-E	1704000000-E	2830000000-N	2845000000-N	7444000000-E	7456000000-E				
												SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	1.5" MILLING	INCIDENTAL MILLING	BASE COURSE, B25.0C	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ADJUST MANHOLES	ADJUST METER OR VALVE BOX	INDUCTIVE LOOP SAWCUT	LEAD-IN CABLE (14-2 PAIR)				
											MI	FT	SMI	TON	SY	SY	TONS	TONS	TONS	TONS	TONS	EA	EA	LF	LF			
2023CPT.08.06.10771	Richmond	1	US 220	FROM BRIDGE OVER INTERSTATE 73/74 TO C.J. SOUTH OF ELLERBE CITY LIMITS	1,2	2	MU	NO	NO	1.57	58																	
<b>TOTAL FOR MAP NO. 1</b>											<b>1.57</b>					<b>42,168</b>			<b>3,520</b>		<b>229</b>							
<b>TOTAL FOR PROJ NO. 2023CPT.08.06.10771</b>											<b>1.57</b>					<b>42,168</b>			<b>3,520</b>		<b>229</b>							
2023CPT.08.06.20771	Richmond	2	SR 1309 (PAGE ST. EXT.)	FROM SR 1310 (BENNETT RD) TO SR 1307 (PLEASANT HILL CHURCH RD)	3	2	2WU	NO	NO	1.74	20		3.49	488.00		410		2,041		136	67							
<b>TOTAL FOR MAP NO. 2</b>											<b>1.74</b>			<b>3.49</b>	<b>488.00</b>		<b>410</b>		<b>2,041</b>		<b>136</b>	<b>67</b>						
2023CPT.08.06.20771	Richmond	3	SR 1475 (CADELL RD.)	FROM C.J. TO SR 1487(MILLSTONE RD)	4	2	2WU	NO	NO	3.09	24		6.20	869.00		533		3,951		261	95							
<b>TOTAL FOR MAP NO. 3</b>											<b>3.09</b>			<b>6.20</b>	<b>869.00</b>		<b>533</b>		<b>3,951</b>		<b>261</b>	<b>95</b>						
2023CPT.08.06.20771	Richmond	4	SR 1925 (BILTMORE DR.)	FROM US HWY 74 BUS.(E. BROAD AVE) TO SR 1903(MILL RD)	5,6,7	2	2WU	NO	NO	0.59	24		0.05	10.00		12,151			1,103	65	6	8	1	1,440	36			
<b>TOTAL FOR MAP NO. 4</b>											<b>0.59</b>			<b>0.05</b>	<b>10.00</b>		<b>12,151</b>			<b>1,103</b>	<b>65</b>	<b>6</b>	<b>8</b>	<b>1</b>	<b>1,440</b>	<b>36</b>		
<b>TOTAL FOR PROJ NO. 2023CPT.08.06.20771</b>											<b>5.42</b>			<b>9.74</b>	<b>1,367.00</b>		<b>12,151</b>	<b>943</b>		<b>5,992</b>	<b>1,103</b>	<b>462</b>	<b>168</b>	<b>8</b>	<b>1</b>	<b>1,440</b>	<b>36</b>	
50526	Richmond	3	SR 1475 (CADELL RD)	FROM C.J. TO SR 1487(MILLSTONE RD)	4	2	2WU	NO	NO	3.09	24									102								
<b>TOTAL FOR MAP NO. 3</b>											<b>3.09</b>										<b>102</b>							
<b>TOTAL FOR PROJ NO. 50526</b>											<b>3.09</b>									<b>102</b>								
<b>GRAND TOTAL</b>											<b>10.08</b>			<b>9.74</b>	<b>1,367.00</b>		<b>54,319</b>	<b>943</b>		<b>2,275</b>	<b>9,512</b>	<b>1,103</b>	<b>793</b>	<b>168</b>	<b>8</b>	<b>1</b>	<b>1,440</b>	<b>36</b>