COMPUTED BY:	CJP	DATE:	5/25/2022
CHECKED BY:	RBH	DATE:	12/5/2022

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
W-5701B	3D-3

Note: Invert Elevations indicated are for Bid Purposes only and shall not be used for project construction stakeout. See "Standard Specifications for Roads and Structures, Section 300-5."

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

| LINE & STATION / SIZE / THICKNESS OR GAUGE | OFFSET | | STRUCTURE NO. FROM | STRUCTURE NO. TO | TOP ELEVATION | INVERT ELEVATION | INVERT ELEVATION | % MINIMUM REQUIRED SLOPE | SIDE DRAIN PIPE (RCP, CSP, CAAP, HDPE, PP or PVC) 15" | 18" | DO NOT USE RCP | DO NOT USE CSP | DO NOT USE CAAP | DO NOT USE HDPE, PP, OR PVC | C.S. PIPE 15" 0.064 | 18" 0.064 | R.C. PIPE CLASS III 15" | 18" | 24" | 30" | 36" | R.C. PIPE CLASS IV 15" | 18" | ENDWALLS STD. 838.01 OR STD. 838.11 (UNLESS NOTED OTHERWISE) CU. YARDS R.C.P. | C.S.P. | QUANTITIES FOR DRAINAGE STRUCTURES PER EACH (0' THRU 5.0') | *TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. 'A' + (1.3 X COL. 'B') LIN. FT. A 5.0' THRU 10.0' | B 10.0' AND ABOVE | C.B. STD. 840.01 OR STD. 840.02 | FRAME, GRATES, AND HOOD STANDARD 840.03 TYPE OF GRATE E | F | G | SEE DETAIL SHEET NO. 2C-3 FOR PLACING A TBDI IN CONCRETE ISLANDS DROP INLET | CATCH BASIN | D.I. STD. 840.14 OR STD. 840.15 | D.I. FRAME AND GRATE STD. 840.16 | G.D.I. TYPE "A" STD. 840.17 OR 840.26 | G.D.I. TYPE "B" STD. 840.18 OR 840.27 | G.D.I. TYPE "D" STD. 840.19 OR 840.28 | G.D.I. FRAME WITH TWO FLAT GRATES STD. 840.20 | G.D.I. FRAME WITH TWO GRATES STD. 840.22 | G.D.I. (N.S.) FRAME WITH TWO GRATES STD. 840.24 | G.D.I. (N.S.) FR. WITH TWO FLAT GRATES. STD. 840.29 | J.B. STD. 840.31 OR 840.32 | TBJB STD. 840.34 | T.B.D.I. STD. 840.36 | STEEL GRATE AND FRAME STD. 840.37 | M.H. FRAME AND COVER STD. 840.54 | ADJUST MH | ADJUST CB | ADJUST DI | CONV DI TO JBMH SEE DETAIL SHEET NO. 2C-4 | FLOWABLE FILL (CY) | C.S. PIPE ELBOWS NO. & SIZE | CONC. & BRICK PIPE PLUG, C.Y. STD. 840.71 | CONC. COLLARS CL. "B" C.Y. STD. 840.72 | PIPE REMOVAL LIN. FT. | REMARKS |
|---|---|---|---