PROJECT REFERENCE NO.	SHEET NO.
W-5701B	SIGN-3

APPROVED: DocuSigned by: David T Sears — 095183F28E5741E...

DATE: 1/9/2023

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 044558 ENGINEER DAVID T. SEARS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

(401) QUANTITY REQ'D 4

R2-1
36"X 48"

TWO WOOD POSTS PER SIGN

(402) QUANTITY REQ'D 5

R4-7
24"X 30"

ONE WOOD POST PER SIGN

(403) QUANTITY REQ'D 6

OM1-3
18"X 18"

MOUNT BELOW SIGN 402 IN 5 INSTALLATIONS. MOUNT BELOW SIGN 414 IN 1 INSTALLATION.

(404) QUANTITY REQ'D 1

W6-3
48"X 48"

TWO WOOD POSTS

(405) QUANTITY REQ'D 5

R6-1L
54"X 18"

TWO WOOD POSTS PER SIGN

(406) QUANTITY REQ'D 2

W4-2L
48"X 48"

TWO WOOD POSTS PER SIGN

(407) QUANTITY REQ'D 10

W12-1
30"X 30"

ONE WOOD POST PER SIGN

(408) QUANTITY REQ'D 2

W9-1L
48"X 48"

TWO WOOD POSTS PER SIGN

(409) QUANTITY REQ'D 5

R6-1R
36"X 12"

MOUNT ABOVE SIGN 410 IN 5 INSTALLATIONS

(410) QUANTITY REQ'D 5

R1-1
36"X 36"

TWO WOOD POSTS PER SIGN

(411) QUANTITY REQ'D 5

R1-2
36"X36"X36"

ONE WOOD POST PER SIGN

(412) QUANTITY REQ'D 1

W3-1
30"X 30"

ONE WOOD POST

(413) QUANTITY REQ'D 1

R2-1
24"X 30"

ONE WOOD POST

(414) QUANTITY REQ'D 1

R4-7
36"X 48"

TWO WOOD POSTS PER SIGN

(415) QUANTITY REQ'D 1

W6-2
48"X 48"

TWO WOOD POSTS PER SIGN

RK&K
P: (919) 878-9560
8601 Six Forks Road, Forum 1,Suite 700
Raleigh, North Carolina 27615-3960
NC License No. F-0112
Engineers | Construction Managers | Planners | Scientists
www.rkk.com
Responsive People | Creative Solutions

TYPE "E" SIGNS

1/9/2023
Traffic\Signing\CADD\Signing Layout Plans\W5701B_SGN_E.dgn