SCOPE OF WORK

PARTIALLY REMOVE TOP OF BRIDGE DECK CONCRETE BY SCARIFICATION AND SHOTBLASTING.

OVERLAY PREPARED TOP OF BRIDGE DECK WITH POLYMER CONCRETE (PC). REMOVE EXISTING JOINT MATERIAL AND INSTALL FOAM JOINTS SEALS FOR PRESERVATION

GROOVE PC BRIDGE DECK.

MILL AND REPAVE ASPHALT APPROACH ROADWAYS.

CLEAN, REPAIR, AND PAINT EXISTING STRUCTURAL STEEL.

REMOVE DEBRIS FROM TOP OF EXISTING END BENT AND BENT CAPS AND APPLY EPOXY COATING.

EPOXY RESIN INJECTION OF CONCRETE CRACKS.

REMOVE UNSOUND CONCRETE AND PROPERLY PREPARE EXISTING END BENT AND BENT AREAS FOR SHOTCRETE AND CONCRETE REPAIRS.

I HEREBY CERTIFY THAT THIS STRUCTURE WAS REHABILITATED ACCORDING TO THESE PLANS OR AS NOTED HEREIN.

RESIDENT ENGINEER

1/11/2023

5430 Wade Park Blvd, Suite 410

Raleigh, NC 27607 Tel. 919-854-0344 Fax. 919-854-0355 NC License No. F-0765

DATE

PROJECT NO. I-5927 POLK COUNTY


740023 STATION:_

SHEET 1 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

GENERAL DRAWING FOR WBL BRIDGE
ON I-26 OVER SR 1501
(HUNTING COUNTRY ROAD)
BETWEEN NC 108 AND
SOUTH CAROLINA LINE

REVISIONS SHEET NO. S-1 DATE: DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



PLAN OF WBL BRIDGE

D. A. GLADDEN DATE: 5/21
E.MURRAY DATE: 12/22

TO SOUTH CAROLINA LINE

DRAWN BY :

CHECKED BY : ___