

SECTION ALONG & WBL BRIDGE

(SECTION @ END BENTS AND BENTS ARE TAKEN AT RIGHT ANGLES)

NOTES

PROFILE INFORMATION IS TAKEN FROM THE ORIGINAL PLANS AND ROUTINE INSPECTION REPORT DATED 9/24/2019.

BRIDGE ORIENTATION CONFORMS TO EXISTING BRIDGE PLANS.

SCOPE OF WORK

PARTIALLY REMOVE TOP OF BRIDGE DECK CONCRETE BY SCARIFICATION AND SHOTBLASTING.

OVERLAY PREPARED TOP OF BRIDGE DECK WITH POLYMER CONCRETE (PC). REMOVE EXISTING JOINT MATERIAL AND INSTALL FOAM JOINTS SEALS FOR PRESERVATION.

GROOVE PC BRIDGE DECK.


MILL AND REPAVE ASPHALT APPROACH ROADWAYS.

CLEAN, REPAIR, AND PAINT EXISTING STRUCTURAL STEEL.

REMOVE DEBRIS FROM TOP OF EXISTING END BENT AND BENT CAPS AND APPLY APOXY COATING.

EPOXY RESIN INJECTION OF CONCRETE CRACKS.

REMOVE UNSOUND CONCRETE AND PROPERLY PREPARE EXISTING END BENT AND BENT AREAS FOR SHOTCRETE AND CONCRETE REPAIRS.



I-5927 PROJECT NO. POLK COUNTY

740048 STATION:

SHEET 1 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

DATE

GENERAL DRAWING

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

5430 Wade Park Blvd, Suite 410

Tel. 919-854-0344 Fax. 919-854-0355

Raleigh, NC 27607

NC License No. F-0765

FOR WBL BRIDGE ON I-26 OVER PACOLET RIVER AND SR1516 (RIVER ROAD) BETWEEN SR1501 AND NC 108

REVISIONS SHEET NO. S-29 DATE: BY: DATE: TOTAL SHEETS

PLAN OF WBL BRIDGE

D. A. GLADDEN DATE: 5/21

E. MURRAY

_ DATE : 12/22

DRAWN BY :

CHECKED BY : _