

AS-BUILT REPAIR QUANTITY TABLE TOP OF DECK REPAIRS APPROACH SLAB @ END BENT 1 ESTIMATE ACTUAL 75**.**6 SY SCARIFYING BRIDGE DECK 75.6 SY SHOTBLASTING OF BRIDGE DECK 2.9 SY CLASS II SURFACE PREPARATION 616**.**7 SF GROOVING BRIDGE FLOORS CONCRETE DECK REPAIR FOR PC OVERLAY SY 2.9 3.7 CY POLYMER CONCRETE MATERIALS PLACING AND FINISHING POLYMER CONCRETE OVERLAY 75.6 SY SPAN A ESTIMATE ACTUAL 316.3 SY SCARIFYING BRIDGE DECK 316.3 SY SHOTBLASTING OF BRIDGE DECK 5.9 CLASS II SURFACE PREPARATION SY 2620.3 SF GROOVING BRIDGE FLOORS CONCRETE DECK REPAIR FOR PC OVERLAY 5.9 SY 15.4 $\mathsf{C}\mathsf{Y}$ CONCRETE MATERIALS PLACING AND FINISHING POLYMER CONCRETE OVERLAY 316.3 SY UNDERSIDE OF DECK REPAIRS ESTIMATE ACTUAL SHOTCRETE REPAIRS VOLUME VOLUME AREA AREA CF UNDERSIDE OF DECK 16.2 5.4 OVERHANG DIAPHRAGMS 0.0 0.0 UNDERSIDE OF OVERHANG 0.0 0.0 INTERIOR DIAPHRAGMS 0.0 0.0

QUANTITIES IN TABLE REPRESENT ESTIMATED VALUES OF CLASS II SURFACE PREPARATION AND CONCRETE DECK REPAIR FOR POLYMER OVERLAY AFTER REMOVAL OF UNSOUND CONCRETE (MIN. 2" CLEAR TO SAW CUT). SEE OVERLAY SURFACE PREPARATION FOR POLYMER CONCRETE SPECIAL PROVISION.

APPROXIMATE CLASS II AREA

UNDERSIDE EPOXY RESIN INJECTION

UNDERSIDE REPAIR

I-5927 PROJECT NO. ____ POLK COUNTY 740048 BRIDGE NO. __

ESTIMATE

LF

ACTUAL

SHEET NO.

S-32

TOTAL SHEETS

DATE:

SHEET 1 OF 6

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

PLAN OF SPAN A

NO. BY:

REVISIONS DOCUMENT NOT CONSIDERED FINAL UNLESS ALL BY: DATE: SIGNATURES COMPLETED

` SEAL ' 025516

-A689F83FD9D74F8.. 1/11/2023

5430 Wade Park Blvd, Suite 410

Raleigh, NC 27607

DRAWN BY: ____D.A.GLADDEN DATE: ___5/21 Tel. 919-854-0344 Fax. 919-854-0355 CHECKED BY: E. MURRAY DATE: 12/22 NC License No. F-0765