

PLAN OF SPAN C

NOTES

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ADJUST THE ACTUAL QUANTITIES ENTERED INTO THE AS-BUILT REPAIR QUANTITY TABLE.

FOR SECTION A-A AND B-B, SEE "JOINT REPAIR DETAILS" SHEET.

5430 Wade Park Blvd, Suite 410 Raleigh, NC 27607 Tel. 919-854-0344 Fax. 919-854-0355

AS-BUILT REPAIR QUANTITY TABLE TOP OF DECK REPAIRS SPAN C ESTIMATE ACTUAL 212.8 SY SCARIFYING BRIDGE DECK 212**.**8 SY SHOTBLASTING OF BRIDGE DECK CLASS II SURFACE PREPARATION 6.1 SY 1759.3 SF GROOVING BRIDGE FLOORS CONCRETE DECK REPAIR FOR PC OVERLAY SY POLYMER CONCRETE MATERIALS 10.3 $\mathsf{C}\mathsf{Y}$ PLACING AND FINISHING POLYMER 212**.**8 SY CONCRETE OVERLAY UNDERSIDE OF DECK REPAIRS ESTIMATE ACTUAL SHOTCRETE REPAIRS AREA AREA VOLUME VOLUME CF UNDERSIDE OF DECK 0.0 0.0 0.0 OVERHANG DIAPHRAGMS 0.0 0.0 UNDERSIDE OF OVERHANG 0.0 0.0 INTERIOR DIAPHRAGMS 0.0

QUANTITIES IN TABLE REPRESENT ESTIMATED VALUES OF CLASS II SURFACE PREPARATION AND CONCRETE DECK REPAIR FOR POLYMER OVERLAY AFTER REMOVAL OF UNSOUND CONCRETE (MIN. 2" CLEAR TO SAW CUT). SEE OVERLAY SURFACE PREPARATION FOR POLYMER CONCRETE SPECIAL PROVISION.

APPROXIMATE CLASS II AREA

UNDERSIDE EPOXY RESIN INJECTION

UNDERSIDE REPAIR

I-5927 PROJECT NO.___ POLK COUNTY 740048 BRIDGE NO._

ESTIMATE

LF

0.0

ACTUAL

SHEET 3 OF 6

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

PLAN OF SPAN C

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL BY: SIGNATURES COMPLETED

SEAL 025516 Emily E. Murray 1/11/2023

SHEET NO. REVISIONS S-34 NO. BY: DATE: DATE: TOTAL SHEETS 79

NC License No. F-0765

D. A. GLADDEN DATE: _ DRAWN BY : __ CHECKED BY: E. MURRAY DATE: 12/22