

ECONOLITE ASC/3-2070 EMERGENCY VEHICLE PREEMPT PROGRAMMING DETAIL

(program controller as shown)

1. From Main Menu select 4. PREEMPTOR/TSP
2. From PREEMPTOR/TSP/SCP Submenu select 1. PREEMPT PLAN 1-10

Place cursor in [] next to Preempt Plan and press 3. Then press the right cursor arrow and toggle the controller to YES. Next cursor down. This will select Emergency Vehicle Preempt #3.

```

PREEMPT PLAN [ 3]  ENABLE....YES
VEH/PED 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6
OVERLAP A B C D E F G H I J K L M N O P
TRKCLR V . . . . .
TRKCLR O . . . . .
ENA TRL . . . . .
DWEL VEH . X . . . . .
DWEL PED . . . . .
DWEL OLP . . . . .
CYC VEH . . . . .
CYC PED . . . . .
CYC OLP . . . . .
EXIT PH . . . X . . . X . . . . .
EXIT CAL . . . . .
SP FUNC . . . . .

ENABLE... YESIPMT OVRIDE.. IINTERLOCK. NO
DET LOCK... XIDELAY.. 0IINHIBIT... 0
OVERIDE FL. . IDURATION 0ICLR-GRN... NO
TERM OLP. NOIPC>YEL NOITERM PH NO
PED DARK.. NOITC RESRV NOIDWELL FL OFF
LINK PMT...0IX FLCOLR REDIEXIT OPT. OFF
X TMG PLN...0IRE-SERV.. 0IFLT TYPE.HARD
FREE DUR PMTIR1 NOIR2 NOIR3 NOIR4 NO
--TIMING-----WALKIPED CLIMN GRI YELI RED
ENTRANCE TM. 255I 255I 1I25.5I25.5
-----MIN GRIEXT GRIMX GRI YELI RED
TRACK CLEAR 0I 0I 0I25.5I25.5
-----MIN DLIPMTEXTIMX TMI YELI RED
DWL/CYC-EXIT 12I 0.0I 120I25.5I25.5
PMT ACTIVE OUT..ON PMT ACT DWELL...NO
OTHER - PRI PMT.OFF NON-PRI PMT.....OFF
INH EXT TIME... 0.0 PED PR RETURN...OFF
PRIORITY RETURN.OFF QUEUE DELAY.... OFF
COND DELAY.....OFF

PHASES 1 2 3 4 5 6 7 8
PR RTN% 0 0 0 0 0 0 0 0
PHASES 9 10 11 12 13 14 15 16
PR RTN% 0 0 0 0 0 0 0 0
  
```

PROGRAM EXTEND TIME ON OPTICAL DETECTOR UNITS FOR 2.0 SEC.

ECONOLITE ASC/3-2070 PREEMPT FILTERING PROGRAMMING DETAIL



(program controller as shown)

1. From Main Menu select 4. PREEMPTOR/TSP
2. From PREEMPT/TSP/SCP Submenu select 2. ENABLE PREEMPT FILTERING & TSP/SCP

```

ENABLE PREEMPT FILTERING & TSP/SCP
FILTERED SOLID PULSING
INPUT 1 ...BYPASSED.. ...BYPASSED..
2 ...BYPASSED.. ...BYPASSED..
3 ..PREEMPT 3. ...BYPASSED..
4 ...BYPASSED.. ...BYPASSED..
5 ...BYPASSED.. ...BYPASSED..
6 ...BYPASSED.. ...BYPASSED..
7 ...BYPASSED.. ...BYPASSED..
8 ...BYPASSED.. ...BYPASSED..
9 ...BYPASSED.. ...BYPASSED..
10 ...BYPASSED.. ...BYPASSED..
  
```

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 10-0446T1
DESIGNED: January 2022
SEALED: 1/14/2022
REVISED:

Electrical Detail - Temp 1 - Sheet 2 of 2		DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
ELECTRICAL AND PROGRAMMING DETAILS FOR:	US 29-601 (Concord Parkway North) at SR 1394 (Poplar Tent Rd) / McGill Avenue	SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 031001 TODD JOYCE
Prepared In the Offices of:  750 N. Greenfield Pkwy, Garner, NC 27529	Division 10 Cabarrus County Concord PLAN DATE: January 2022 REVIEWED BY: T. Joyce PREPARED BY: C. Strickland REVIEWED BY:	Discussed by:  01/18/2022 DATE
REVISIONS		INIT. DATE
SIC. INVENTORY NO. 10-0446T1		

14-1116-2022 12:52
*10046T1.dwg
C:\Users\jck101\OneDrive\...
C:\Users\jck101\OneDrive\...