STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
R-2561CA	X-1C

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Summary No. 5 (Lt.) Cont.

Station Y4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
12+75.00	0	0	0
13+00.00	10	0	0
13+25.00	36	0	0
13+50.00	64	0	0
13+75.00	54	3	0
14+00.00	17	20	0
14+24.21	3	35	0

Station Dr1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
10+75.00	0	0	0
11+00.00	5	0	27
11+25.00	2	2	33
11+50.00	0	12	28
11+73.42	0	9	19

Station Dr2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
10+75.00	0	0	0
11+00.00	5	0	24
11+25.00	2	2	31
11+50.00	0	11	29
11+78.32	0	10	20

Summary No. 6 (Rt.)

Station L1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
11+00.00	0	0	0
11+50.00	32	4	0
12+00.00	46	5	0
12+50.00	55	8	0
13+00.00	68	9	0
13+50.00	93	6	0
14+00.00	103	4	0
14+50.00	106	5	0
15+00.00	77	7	0
15+50.00	36	31	0
16+00.00	31	37	0
16+50.00	63	17	0
17+00.00	91	16	0
17+50.00	92	19	0
18+00.00	76	20	0
18+50.00	44	28	0
19+00.00	33	32	0
19+50.00	40	24	0
20+00.00	53	11	0
20+50.00	61	8	0
21+00.00	62	14	0
21+50.00	58	15	0
22+00.00	54	15	0
22+50.00	63	16	0

Summary No. 6 (Rt.) Cont.

Station L1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
23+00.00	84	14	0
23+50.00	105	12	0
24+00.00	115	10	0
24+50.00	111	8	0
25+00.00	94	11	0
25+50.00	68	20	0
26+00.00	47	21	0
26+50.00	43	21	0
27+00.00	22	13	0
27+50.00	19	0	0
28+00.00	62	0	0
28+31.59	55	0	0

Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
10+12.00	0	0	0
10+25.00	0	74	0
10+50.00	0	167	0
10+75.00	14	163	0
11+00.00	23	132	0
11+25.00	19	116	0
11+50.00	19	87	25
11+75.00	20	63	25
12+00.00	19	49	0
12+25.00	17	42	0
12+50.00	23	38	0
12+75.00	31	26	0
13+00.00	29	12	0
13+25.00	23	6	0
13+50.00	22	3	0
13+75.00	20	1	0
14+00.00	12	1	0
14+25.00	10	1	0
14+50.00	6	0	0

Summary No. 7 (Rt.)

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
28+31.59	0	0	0
28+50.00	44	17	0
29+00.00	132	35	0
29+50.00	118	42	0
30+00.00	86	66	0
30+50.00	115	61	0
31+00.00	140	71	0
31+50.00	125	94	0
32+00.00	95	94	0
32+50.00	70	74	0
33+00.00	64	68	0
33+50.00	68	76	0
34+00.00	69	52	0
34+50.00	74	22	0

Summary No. 7 (Rt.) Cont.

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
35+00.00	79	41	0
35+50.00	66	75	0
36+00.00	54	86	0
36+50.00	49	99	0
37+00.00	52	112	0
37+50.00	28	122	0
38+00.00	19	128	0
38+50.00	45	131	0
39+00.00	69	115	0
39+50.00	84	114	0
40+00.00	92	130	0
40+50.00	103	122	0
41+00.00	117	132	0
41+50.00	126	136	0
42+00.00	129	133	0
42+50.00	137	140	0
43+00.00	150	134	0
43+50.00	147	131	0
44+00.00	149	101	0
44+50.00	144	69	0
45+00.00	117	88	0
45+50.00	102	106	0
46+00.00	91	106	0
46+50.00	81	112	0
47+00.00	43	119	0
47+50.00	8	124	0
48+00.00	11	119	0
48+50.00	15	111	0
49+00.00	19	102	0
49+50.00	25	92	0
50+00.00	33	85	0
50+50.00	30	109	0
51+00.00	17	144	0
51+50.00	19	197	0
52+00.00	41	249	0
52+50.00	72	295	0
53+00.00	116	339	0
53+50.00	124	431	0
54+00.00	89	536	0
54+50.00	39	326	0
55+00.00	10	51	0
55+50.00	19	6	0
56+00.00	17	41	0
56+50.00	9	402	0
57+00.00	23	715	0
57+50.00	48	452	0
58+00.00	107	179	0
58+50.00	164	136	0
59+00.00	272	201	0

Station Rpd	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
14+50.00	0	0	0
15+00.00	889	0	0
15+50.00	802	2	0
16+00.00	626	13	0
16+50.00	481	21	76
17+00.00	346	34	145
17+50.00	205	128	95
18+00.00	97	236	49
18+50.00	46	306	32
19+00.00	33	447	9
19+50.00	21	755	0
20+00.00	13	1017	0
20+50.00	5	1201	0
21+00.00	0	1544	0
21+50.00	36	2181	0
22+00.00	67	2466	0
22+50.00	56	2576	0
23+00.00	41	3017	0
23+50.00	28	3276	0
24+00.00	12	3387	0
24+50.00	0	3772	0
24+74.89	0	2047	0

Station Lpd	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
12+27.00	0	0	0
12+75.00	188	43	77
13+00.00	93	25	76
13+50.00	206	42	156
14+00.00	144	20	161
14+50.00	44	18	163
15+00.00	31	38	157
15+55.00	22	59	76

Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
11+00.00	0	0	0
11+50.00	147	3	0
12+00.00	117	7	0
12+50.00	72	42	0
13+00.00	78	98	0
13+50.00	100	61	0
14+00.00	172	6	0
14+50.00	183	14	0
15+00.00	104	28	0
15+50.00	114	41	0
16+00.00	147	49	0
16+48.00	239	53	0