


**STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION**

**SIGNING PLAN  
EDGECOMBE COUNTY**

**LOCATION: US-64 AT MILEPOST 485.8 IN TARBORO**

PROJECT REFERENCE NO. <b>I-6041</b>	SHEET NO. <b>SIGN-1</b>
APPROVED: <i>David M. Eaton</i> <small>DDA1C5F247484F7...</small>	
DATE: 01/24/2023	
SEAL 	
<b>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</b>	

**SUMMARY OF QUANTITIES**

ITEM NO.	ITEM DESCRIPTION		QUANTITY	UNIT
4057000000	DESC. NO.	SECT. NO.		
4082100000	SP	906	20	C.Y.
			1	L.S.
		OVERHEAD FOOTING		
		SUPPORTS, OVERHEAD SIGN STRUCTURE @ STA. US-64 MILEPOST 485.8		

**GENERAL NOTES**


- SIGNS FURNISHED BY STATE
- CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- DO NOT BEGIN FABRICATION FOR TYPES A & B SIGNS MOUNTED ON OVERHEAD STRUCTURES OR STEEL SUPPORTS UNTIL "S" DIMENSIONS HAVE BEEN FIELD VERIFIED.
- MINIMUM ROADWAY VERTICAL CLEARANCE IS 17 FEET TO BOTTOM OF OVERHEAD SIGN ASSEMBLIES
- INSTALL GUARDRAIL, SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

**ROADWAY STANDARD DRAWING**

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.10	TYPE 'A' SIGNS
901.20	TYPE 'B' SIGNS
901.50	ARROWS AND SHIELDS
901.70	SIGN STRINGERS AND SUPPORT SPACING
901.80	SIGN MOUNTING DETAILS - FOR TYPE A AND TYPE B SIGNS
904.20	SECONDARY SIGN MOUNTING

**T.I.P.: I-6041**




**INDEX**

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET, QUANTITIES, NOTES, AND SIGN LOCATION
SIGN-2	OVERHEAD SIGN STRUCTURE DRAWING
SIGN-3	TYPE "A" AND "B" SIGN DESIGNS

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

**A. I. ALQUDWAH, PE** SIGNING & DELINEATION REGIONAL ENGINEER

**D. M. EATON, PE** SIGNING & DELINEATION PROJECT DESIGN ENGINEER



01/24/23 C:\Data\stuf\I6041\I6041\_sgn\_title.dgn