SUMMARY OF QUANTITIES

PROJECT NO.	SHEET NO.	TOTAL NO.
I-6042 47991.3.1	9	16

PROJECT NO	COUNTY	MAP NO	SEGMENT	ROUTE	DESCRIPTION	TYPICAL SECTION NO.	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	0106000000-E BORROW EXCAVATION CY	0318000000-E FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES TON	0320000000-E FOUNDATION CONDITIONING GEOTEXTILE SY	0448200000-E 15" RC PIPE CULVERTS, CLASS IV LF	0448300000-E 18" RC PIPE CULVERTS, CLASS IV LF	0448400000-E 24" RC PIPE CULVERTS, CLASS IV LF	0995000000-E PIPE REMOVAL LF	1220000000-E INCIDENTAL STONE BASE TON	1297000000-E MILLING ASPHALT PAVEMENT, 2" DEPTH SY	1297000000-E MILLING ASPHALT PAVEMENT, 2.75" DEPTH SY	1330000000-E INCIDENTAL MILLING SY	1524200000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5D TON	1577000000-E POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TON	1662000000-E OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED TON	1840000000-E MILLED RUMBLE STRIPS (ASPHALT CONCRETE) LF
I-6042 47991.3.1	EDGECOMBE	3	1	EB EXIT RAMP SR-1523	PHYSICAL GORE TO SR-1523	4	1	MD	NO	NO	0.24	22	20								3470			410	30		
					TOTAL FOR MAP 3						0.24		20								3470			410	30		
		4	1	EB ENTRANCE RAMP SR-1523	SR-1523 TO PHYSICAL GORE	4	1	MD	NO	NO	0.23	22	30								3240			390	30		
					TOTAL FOR MAP 4						0.23		30								3240			390	30		
		5	1	EB EXIT RAMP SR-1524	PHYSICAL GORE TO SR-1524	4	1	MD	NO	NO	0.22	22									3210			380	30		
					TOTAL FOR MAP 5						0.22										3210			380	30		
		6	1	EB ENTRANCE RAMP SR-1524	PHYSICAL GORE TO SR-1524	4	1	MD	NO	NO	0.24	22									3430			410	30		
					TOTAL FOR MAP 6						0.24										3430			410	30		
		7	1	EB EXIT RAMP NC-42	NC-42 TO PHYSICAL GORE	4	1	MD	NO	NO	0.24	22									3470			410	30		
					TOTAL FOR MAP 7						0.24										3470			410	30		
		8	1	EB ENTRANCE RAMP NC-42	PHYSICAL GORE TO NC-42	4	1	MD	NO	NO	0.24	22									3470			410	30		
					TOTAL FOR MAP 8						0.24										3470			410	30		
		9	1	EB EXIT RAMP NC-11	NC-11 TO PHYSICAL GORE	4	1	MD	NO	NO	0.26	22									3710			440	30		
					TOTAL FOR MAP 9						0.26										3710			440	30		
		10	1	EB ENTRANCE RAMP NC-11	PHYSICAL GORE TO NC-11	4	1	MD	NO	NO	0.24	22									3460			410	30		
					TOTAL FOR MAP 10						0.24										3460			410	30		
		11	1	WB EXIT RAMP NC-11	NC-11 TO PHYSICAL GORE	4	1	MD	NO	NO	0.23	22									3440			410	30		
					TOTAL FOR MAP 11						0.23										3440			410	30		
		12	1	WB ENTRANCE RAMP NC-11	PHYSICAL GORE TO NC-11	4	1	MD	NO	NO	0.27	22									3930			470	30		
					TOTAL FOR MAP 12						0.27										3930			470	30		
		13	1	WB EXIT RAMP NC-42	PHYSICAL GORE TO NC-42	4	1	MD	NO	NO	0.21	22									3100			370	30		
					TOTAL FOR MAP 13						0.21										3100			370	30		
		14	1	WB ENTRANCE RAMP NC-42	NC-42 TO PHYSICAL GORE	4	1	MD	NO	NO	0.25	22									3600			430	30		
					TOTAL FOR MAP 14						0.25										3600			430	30		
		15	1	WB EXIT RAMP SR-1524	SR-1524 TO PHYSICAL GORE	4	1	MD	NO	NO	0.21	22									3130			370	30		
					TOTAL FOR MAP 15						0.21										3130			370	30		
		16	1	WB ENTRANCE RAMP SR-1524	PHYSICAL GORE TO SR-1524	4	1	MD	NO	NO	0.26	22									3670			440	30		
					TOTAL FOR MAP 16						0.26										3670			440	30		
		17	1	WB EXIT RAMP SR-1523	SR-1523 TO PHYSICAL GORE	4	1	MD	NO	NO	0.26	22									3780			450	30		
					TOTAL FOR MAP 17						0.26										3780			450	30		
		18	1	WB ENTRANCE RAMP SR-1523	PHYSICAL GORE TO SR-1523	4	1	MD	NO	NO	0.25	22									3540			420	30		
					TOTAL FOR MAP 18						0.25										3540			420	30		
TOTAL											24.21		190	18	50	104	8	32	144		126380	388290	11930	62210	5020	18430	214270
SAY																				1000							
GRAND TOTAL													190	18	50	104	8	32	144	1000	126380	388290	11930	62210	5020	18430	214270
PAY ITEM TOTAL													190	18	50	104	8	32	144	1000	126380	388290	11930	62210	5020	18430	214270