

PROJECT NO.	SHEET NO.	TOTAL NO.
48234.3.1 15BPR.35	8	

THERMOPLASTIC AND PAINT QUANTITIES ROADWAY & BRIDGE

PROJECT NO	COUNTY	PROJECT AREA	WORK LOCATION	STRUCTURE LOCATION	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4400000000-E	4434000000-N	5100000000-	4892000000-N	4726110000-E			4815000000-E		4825000000-E	4847096000-E		4847096000-E	4890000000-E	4905100000-N			
												STATIONARY WORK ZONE SIGN	SEQUENTIAL FLASHING WARNING LIGHTS	LAW ENFORCEMENT	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING CHARACTER	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING SYMBOL RT ARROW (90 MILS)	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING SYMBOL MERGE ARROW (90 MILS)	6" WHITE PAINT	6" YELLOW PAINT	12" WHITE PAINT	POLYUREA PAVEMENT MARKING YELLOW LINES (6", 30 MILS) (STANDARD GLASS BEADS)	POLYUREA PAVEMENT MARKING WHITE LINES (6", 30 MILS) (STANDARD GLASS BEADS)	POLYUREA PAVEMENT MARKING WHITE LINES (12", 30 MILS) (STANDARD GLASS BEADS)	CONTRAST COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE II (9")	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKER				
												SF	EA	HR	EA	EA	EA	LF	LF	LF	LF	LF	LF	LF	LF	EA			
48234.3.1	Mecklenburg	1	1,2,3,4,5,7		I-277 EB BROOKSHIRE FRWY	FROM PHYSICAL GORE TO BRIDGE OVER NB I-77	1,2	2	MD	0.27	24					4	2					1,210	1,215	400	550	61			
TOTAL FOR WORK LOCATION NO. 1,2,3,4,5,7															4	2						1,210	1,215	400	550	61			
48234.3.1	Mecklenburg	1	6		I-277 WB BROOKSHIRE FRWY	FROM BRIDGE OVER IRWIN CREEK NB FOR APPROX. 1200 FT	3	2	MD	0.27	24											1,190	1,420	435	490	50			
TOTAL FOR WORK LOCATION NO. 6																													
48234.3.1	Mecklenburg	1		590339	BRIDGE 590339 I-277 MAINLINE	EB BRIDGE OVER NB I-77		3	MD	0.05	70											275	290	615	290	275	615	160	
TOTAL FOR STRUCTURE NO. 590339																													
48234.3.1	Mecklenburg	1		590337	BRIDGE 590337 I-277 MAINLINE	WB BRIDGE OVER NB I-77		2	MD	0.05	45											290	280	280	290	80			
TOTAL FOR STRUCTURE NO. 590337																													
48234.3.1	Mecklenburg	1		590338	BRIDGE 590338 I-277 MAINLINE	WB BRIDGE OVER SB I-77		2	MD	0.04	40											290	280	290	80				
TOTAL FOR STRUCTURE NO. 590338																													
48234.3.1	Mecklenburg	1		590341	BRIDGE 590341 I-277 MAINLINE	EB BRIDGE OVER SB I-77		2	MD	0.04	40											230	225	225	230	60			
TOTAL FOR STRUCTURE NO. 590341																													
48234.3.1	Mecklenburg	1		590342	BRIDGE 590342 I-277 MAINLINE	EB BRIDGE OVER IRWIN CREEK		2	MD	0.05	81											270	235	235	270	80			
TOTAL FOR STRUCTURE NO. 590342																													
48234.3.1	Mecklenburg	1		590342	BRIDGE 590342 I-277 MAINLINE	EB BRIDGE OVER IRWIN CREEK		2	MD	0.05	81											270	235	235	270	80			
TOTAL FOR STRUCTURE NO. 590342																													
48234.3.1	Mecklenburg	1		590281	BRIDGE 590281 I-77 SB RAMP	EB BRIDGE OVER SB I-77		1		0.04	30											300	275	500	275	300	500	80	
TOTAL FOR STRUCTURE NO. 590281																													
48234.3.1	Mecklenburg	1		590282	BRIDGE 590282 I-77 NB RAMP	WB BRIDGE OVER SB I-77		1		0.04	300											225	225	225	235	235			
TOTAL FOR STRUCTURE NO. 590282																													
48234.3.1	Mecklenburg	1		590283	BRIDGE 590283 I-77 SB RAMP	WB BRIDGE OVER IRWIN CREEK		2		0.06	25											225	220	220	225	225			
TOTAL FOR STRUCTURE NO. 590283																													
TOTAL FOR PROJ NO. 48234.3.1												384	14	6,258	4	2	2	2,160	2,095	1,115	4,495	4,795	1,950	1,500	111				
TOTAL FOR PROJ NO. 48234.3.1															4			4,255			9,290								
15BPR.35	Mecklenburg	1		590345	BRIDGE 590345 I-277 MAINLINE	WB BRIDGE OVER IRWIN CREEK		3	MD	0.06	55											365	360	130	360	365	130	180	
TOTAL FOR STRUCTURE NO. 590345																													
TOTAL FOR PROJ NO. 15BPR.35																													
TOTAL FOR PROJ NO. 15BPR.35																		365	360	130	360	365	130	180					
TOTAL FOR PROJ NO. 15BPR.35																		725			725								
GRAND TOTAL												384	28	6,546	4	2	2	2,525	2,455	1,245	4,855	5,160	2,080	1,680	111				
GRAND TOTAL															4			4,980			10,015								