NOTES:

PROFILE INFORMATION IS TAKEN FROM THE ORIGINAL PLANS AND THE ROUTINE INSPECTION REPORT DATED 09/06/2022.

BRIDGE ORIENTATION CONFORMS TO EXISTING BRIDGE PLANS AND ROUTINE INSPECTION REPORT.

SCOPE OF WORK:

- PARTIALLY REMOVE BRIDGE DECK CONCRETE USING SCARIFICATION AND HYDRO-DEMOLITION METHODS.
- PERFORM CLASS II SURFACE PREPARATION AND REPAIR ON DECK SURFACES.
- OVERLAY PREPARED BRIDGE DECK WITH LATEX MODIFIED CONCRETE VERY EARLY STRENGTH (LMC-VES).
- RECONSTRUCT BRIDGE DECK JOINT AND INSTALL JOINT SEALS.
- GROOVE LMC-VES BRIDGE DECK.
- SUBSTRUCTURE REPAIRS USING EPOXY RESIN INJECTION AND SHOTCRETE.
- EPOXY COATING OF TOP OF CAPS.
- STRUCTURAL STEEL REPAIRS.
- INSTALL STEEL BEARING KEEPER ANGLE ASSEMBLY.
- CLEANING AND PAINTING STEEL BEAMS.
- CLEANING AND PAINTING BEARINGS WITH HRCSA.

I HEREBY CERTIFY THAT THIS STRUCTURE HAS REHABILITATED ACCORDING TO THESE PLANS OR AS NOTED HEREIN.

RESIDENT ENGINEER

DATE

PROJECT NO. I-6052

MECKLENBURG COUNTY

590281 BRIDGE NO.____

SHEET 1 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
RALEIGH

GENERAL DRAWING

FOR BRIDGE ON I-77 SOUTHBOUND RAMP OVER I-77/US 21 SBL

REVISIONS 11 SCHAUB DRIVE, SUITE 100 NO. RALEIGH, NC 27606 (919) 851-6606 FIRM PE NUMBER : P-0671 S1-1 NO. BY: TOTAL SHEETS 108



