PROJECT REFERENCE NO.	SHEET NO.
B-5721	EC-03
R/W SHEET NO.	

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
5	-L-	26+42	28+00	LT	435
5	-L-	29+50	30+00	LT	115
		DITCH SUBTOTAL			550
	SLOPE PROTECTION MATTING				
5	-L-	15+50	20+00	LT	1,750
5	-L-	15+50	20+00	RT	1,500
5	-L-	15+50	17+50	RT	560
5	-L-	23+00	24+00	LT	225
6	-L-	24+00	26+00	LT	445
		SLOPE SUBTOTAL			4,480
			SUBTOTAL		5,030
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					7,720
				TOTAL	12,750
				SAY	13,000

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
5	-Y-	10+31	11+35	LT	108
5	-Y-	10+39	11+35	RT	100
			SUBTOTAL		208
	ADDITIONAL PSRM TO BE INSTALLED				0
			TOTAL		208
			SAY		225

5/14/99
DOT SMU B5721_EC_03_Soil Stabilization Summary.dgn 7/20/13 PM
R:\CAD GIS\910_CAD\70_NCDOT_TIP\Erosion Control\Design\230_B5721_EC_03_Soil Stabilization Summary.dgn