STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
U-6229	X-1A

Note: Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement, and removal of existing pavement will be paid for at the contract lump sum price for Grading.

NOTE: EMBANKMENT COLUMN DOES INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
20+50.00	0	0
21+00.00	56	0
21+50.00	56	0
22+00.00	56	1
22+50.00	47	3
23+00.00	41	5
23+50.00	42	6
24+00.00	42	6
24+50.00	39	6
25+00.00	36	6
25+50.00	35	8
26+00.00	33	13
26+50.00	30	19
27+00.00	29	24
27+50.00	30	21
28+00.00	31	12
28+50.00	36	7
29+00.00	48	4
29+50.00	49	3
30+00.00	43	6
30+50.00	44	5
31+00.00	43	4
31+50.00	41	4
32+00.00	37	2
32+50.00	32	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
38+00.00	0	0
38+50.00	15	0
39+00.00	21	0
39+50.00	33	6
40+00.00	45	11
40+50.00	48	9
41+00.00	49	9
41+50.00	50	8
42+00.00	50	6
42+50.00	48	6
43+00.00	51	6
43+50.00	59	2
44+00.00	54	0
44+50.00	37	18
45+00.00	30	35
45+50.00	30	35
46+00.00	30	38
46+50.00	39	20
47+00.00	50	0
47+50.00	51	2
48+00.00	49	4
48+50.00	45	5
49+00.00	42	6
49+50.00	39	7

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
50+00.00	33	9
50+50.00	32	11
51+00.00	33	13
51+50.00	22	8
52+00.00	14	1
52+50.00	18	0
53+00.00	23	0
53+50.00	26	0
54+00.00	26	0
54+50.00	28	0
55+00.00	30	0
55+50.00	27	0
56+00.00	21	0
56+50.00	19	0
57+00.00	19	0
57+50.00	19	0
58+00.00	30	0
58+50.00	39	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
60+00.00	0	0
60+50.00	49	0
61+00.00	63	0
61+50.00	63	0
62+00.00	59	0
62+50.00	40	0
63+00.00	22	0
63+50.00	25	0
64+00.00	34	0
64+50.00	35	0
65+00.00	30	0
65+50.00	27	0
66+00.00	24	0
66+50.00	27	3
67+00.00	31	8
67+50.00	31	11
68+00.00	31	10
68+50.00	27	5

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
69+50.00	0	0
70+00.00	28	8
70+50.00	28	16
71+00.00	29	12
71+50.00	32	6
72+00.00	34	2
72+50.00	34	4
73+00.00	34	6
73+50.00	36	4

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
74+00.00	40	0
74+50.00	39	0
75+00.00	37	0
75+50.00	38	0
76+00.00	22	0
76+50.00	6	0
77+00.00	6	0
77+50.00	6	0
78+00.00	6	0
78+50.00	6	0
79+00.00	6	0
79+50.00	6	0
80+00.00	6	0
80+50.00	6	0
81+00.00	6	0
81+50.00	6	0
82+00.00	6	0
82+50.00	25	0
83+00.00	53	0
83+50.00	62	0
84+00.00	66	0
84+50.00	71	0
85+00.00	75	0
85+50.00	75	0
86+00.00	74	0
86+50.00	52	0
87+00.00	30	0
87+50.00	30	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
89+50.00	0	0
90+00.00	29	7
90+50.00	29	8
91+00.00	30	7
91+50.00	38	7
92+00.00	46	7
92+50.00	45	7
93+00.00	45	7
93+50.00	43	9
94+00.00	35	13
94+50.00	31	17
95+00.00	34	18
95+50.00	47	8
96+00.00	62	0
96+50.00	72	0
97+00.00	80	0
97+50.00	80	0
98+00.00	69	0
98+50.00	44	0
99+00.00	30	0
99+50.00	31	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
100+70.00	5	0
112+00.00	17	0