PROJ. REFERENCE NO.	SHEET NO.
R-5930A	X-1A

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
25+80.00	0	0	
26+00.00	0	0	
26+50.00	5	106	
27+00.00	15	259	
27+50.00	25	298	
28+00.00	32	210	
28+50.00	37	118	
29+00.00	40	179	
29+50.00	40	320	
30+00.00	30	241	
30+33.03	7	31	

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
42+00.00	0	0	
42+20.00	40	13	
42+50.00	121	63	
43+00.00	289	284	
43+50.00	389	1475	
44+00.00	724	2132	
44+50.00	1335	1153	
45+00.00	1981	357	
45+50.00	2621	73	
46+00.00	3337	1	
46+50.00	4252	0	
47+00.00	4815	0	
47+50.00	4547	0	
48+00.00	4283	0	
48+50.00	4977	0	
49+00.00	6932	0	
49+50.00	7873	0	
50+00.00	6668	0	
50+50.00	5526	0	
51+00.00	4885	0	
51+50.00	4343	0	
52+00.00	4024	0	
52+50.00	3829	0	
53+00.00	3543	0	
53+50.00	3458	0	
54+00.00	2646	0	
54+50.00	1149	0	
55+00.00	314	145	
55+50.00	51	846	
56+00.00	15	1983	
56+50.00	10	2737	
57+00.00	33	2307	
57+50.00	105	1154	
58+00.00	342	373	175
58+50.00	669	88	342
59+00.00	851	42	336
59+50.00	793	40	336
60+00.00	533	37	336
60+50.00	250	45	336
61+00.00	104	74	335
61+50.00	157	95	335

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
62+00.00	392	50	336
62+50.00	857	5	336
63+00.00	1424	0	336
63+50.00	1888	0	336
64+00.00	2130	0	336
64+50.00	1990	0	169
65+00.00	1512	0	
65+50.00	1125	25	
66+00.00	627	124	
66+50.00	123	310	
67+00.00	11	841	
67+50.00	0	2022	
68+00.00	0	4344	
68+50.00	0	9609	
69+00.00	19	12059	
69+50.00	83	9208	
70+00.00	94	6726	
70+50.00	97	5441	
71+00.00	133	4236	
71+50.00	95	2522	
72+00.00	401	862	
72+50.00	2466	53	
73+00.00	4255	0	
73+50.00	4942	0	
74+00.00	5953	0	
74+50.00	6535	0	
75+00.00	6640	0	
75+50.00	6088	0	
76+00.00	4917	0	
76+50.00	3586	0	
77+00.00	2170	0	
77+50.00	905	3	
78+00.00	429	306	
78+50.00	898	339	
79+00.00	1825	35	
79+50.00	2408	0	
80+00.00	2249	0	
80+50.00	1286	0	
81+00.00	397	348	
81+50.00	176	646	
82+00.00	153	598	
82+50.00	140	770	
83+00.00	164	1106	
83+50.00	93	1364	
84+00.00	0	1611	
84+50.00	0	1598	
85+00.00	202	958	
85+50.00	1178	257	
86+00.00	2639	15	
86+50.00	3802	0	
87+00.00	4441	0	170
87+58.57	2697	0	

Station Y1Lpa	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
10+09.7	0	0	
10+50.00	17	67	
11+00.00	20	70	
11+44.10	8	25	