

8/17/99

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA



PROJECT REFERENCE NO.	SHEET NO.
HE-0011	EC-3A
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

# SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

SSS\JLERN\AMESS\$ 17-JUL-2023 15:23 pw\gflnet-pw.bentley.com\gflnet-01\Documents\Projects\691725-Working\Task\_017 - Chatham County SiteErosion Control\CADD\PS\HE-0011\_stabilization\_impacts.dgn