





CLASS II SURFACE PREPARATION





LINK SLAB AREA

AS-BUILT REPAIR QUANTITY TABLE					
TOP OF DECK REPAIRS	SPAN A				
	ESTIMATE	ACTUAL			
SCARIFYING BRIDGE DECK	227.0 SQ. YDS.				
HYDRO-DEMOLITION OF BRIDGE DECK	227.0 SQ. YDS.				
CLASS II SURFACE PREPARATION	0.0 SQ. YDS.				
LATEX MODIFIED CONCRETE OVERLAY - ES	14.2 CU. YDS.				
PLACING & FINISHING LATEX MODIFIED CONCRETE OVERLAY - ES	227.0 SQ. YDS.				
GROOVING BRIDGE FLOORS	1677.0 SQ. FT.				
LINK SLAB FOR PRESERVATION	153.0 SQ. FT.				

NOTES

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

FOR SHOTCRETE REPAIRS, SEE SPECIAL PROVISIONS.

FOR CONCRETE FOR DECK REPAIR, SEE SPECIAL PROVISIONS.

THE BOUNDARIES OF AREAS IDENTIFIED FOR CLASS II (PARTIAL DEPTH) SURFACE PREPARATION ARE APPROXIMATE AND MAY NOT REFLECT ACTUAL CONDITIONS THAT WILL BE ENCOUNTERED AT THE PROJECT SITE.

EXISTING JOINTS AND DECK DRAINS SHALL BE SEALED PRIOR TO BEGINNING SURFACE PREPARATION OF THE BRIDGE DECK.

FOR OVERLAY OF BRIDGE WITH LATEX MODIFIED CONCRETE - EARLY STRENGTH, SEE SPECIAL PROVISIONS.

PREVIOUSLY PLACED LMC OVERLAY AT STAGED EDGES SHALL BE DEMOLISHED BACK A MINIMUM OF 4 INCHES AND RECAST WITH LMC. SEE STAGED LMC OVERLAY - ES JOINT DETAIL.

FOR LMC OVERLAY - ES SURFACE PREPARATION, SEE SPECIAL PROVISIONS.

FINAL JOINT SEALS SHALL NOT BE INSTALLED UNTIL THE OVERLAY IS COMPLETE.

FOR BRIDGE JOINT DEMOLITION, SEE SPECIAL PROVISIONS.

FOR SECTION A-A, SEE LINK SLAB FOR PRESERVATION DETAILS SHEET.

	(CHER	OKEE	PR.125 CO 0009	5.3 UNTY	
SHEET 1 OF 5						
DEPARTMENT OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH						
SEAL 031583 Docusigned HAN Krishna P. Sedai EAGF794150BF4B7. 09/15/2023	DECK SURFACE REPAIR SPAN A					
03/13/2023					SHEET NO.	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	№. вү: 1 2	DATE:	NO. BY: 3 4	DATE:	S1-03 TOTAL SHEETS 25	