

AS-BUILT REPAIR QUANTITY TABLE

DECK SURFACE REPAIR - SPAN C

	ESTIMATE	ACTUAL
SCARIFYING BRIDGE DECK	465.0 SQ. YD.	
CLASS II SURFACE PREPARATION	0.0 SQ. YD.	
HYDRO-DEMOLITION OF BRIDGE DECK	465.0 SQ. YD.	
LATEX MODIFIED CONCRETE OVERLAY-ES	29.1 CU. YD.	
PLACING & FINISHING OF LATEX MOD. CON. OVERLAY-ES	465.0 SQ. YD.	
GROOVING BRIDGE FLOORS	3836.0 SQ. FT.	
LINK SLAB FOR PRESERVATION	317.0 SQ. FT.	

NOTES

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

EXISTING JOINTS AND DECK DRAINS SHALL BE SEALED PRIOR TO BEGINNING SURFACE PREPARATION OF THE BRIDGE DECK.

FOR "CONCRETE FOR DECK REPAIR", SEE SPECIAL PROVISIONS.

FOR SECTION B-B, SEE "JOINT DETAILS" SHEET.

FOR SECTION D-D, SEE "LINK SLAB FOR PRESERVATION DETAILS" SHEET.

FOR OVERLAY OF BRIDGE WITH LATEX MODIFIED CONCRETE-ES, SEE SPECIAL PROVISIONS.

FOR LMC OVERLAY-ES SURFACE PREPARATION, SEE SPECIAL PROVISIONS.

THE BOUNDARIES OF AREAS IDENTIFIED FOR CLASS II (PARTIAL DEPTH) SURFACE PREPARATION ARE APPROXIMATE AND MAY NOT REFLECT ACTUAL CONDITIONS THAT WILL BE ENCOUNTERED AT THE PROJECT SITE.

FINAL JOINT SEALS SHALL NOT BE INSTALLED UNTIL THE OVERLAY IS COMPLETE.

FOR BRIDGE JOINT DEMOLITION, SEE SPECIAL PROVISIONS.


PREVIOUSLY PLACED LMC OVERLAY AT STAGED EDGES SHALL BE DEMOLISHED BACK A MINIMUM OF 4 INCHES AND RECAST WITH LMC. SEE STAGED LMC OVERLAY-ES JOINT DETAIL.

 BRIDGE JOINT DEMOLITION

 CLASS II SURFACE PREPARATION

 LINK SLAB AREA

← TO RANGER RD.




PROJECT NO. 15BPR.125.3

CHEROKEE COUNTY

BRIDGE NO. 190010

SHEET 3 OF 5



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

DECK SURFACE REPAIRS
SPAN C

DRAWN BY : S. AGUILAR HERNANDEZ DATE : 6/2022
CHECKED BY : A. SORSENGINH DATE : 6/2022
DESIGN ENGINEER OF RECORD: DATE :

9/15/2023
S:\DPG3\15BPR.125.3\Final Plans\402.011.15BPR125.3.SMU.DSR.S06.190010.dgn
ksedai

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S2-06
1			3			TOTAL SHEETS
2			4			28