

-

+

SPLICE LENGTHS						
BAR SIZE	EPOXY COATED	UNCOATED				
#4	2'-0"	1'-9"				
#5	2'-6"	2'-2"				
#6	3'-0"	2'-7"				

BILL OF MATERIAL									
LINK SLAB AT BENT 3									
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT				
* A	27	#5	STR	39'-8"	1117 LBS.				
Α	27	#5	STR	39'-8"	1117 LBS.				
* B	74	#6	STR	15'-6"	1723 LBS.				
В	74	#6	STR	15'-6"	1723 LBS.				
REINFORCING STEEL				2840 LBS.					
		OATED CING S	2840 LBS.						
CLAS	S AA (	CONCR	C.Y.	17.1					

## NOTES

SEE TRAFFIC MANAGEMENT PLANS FOR LANE WIDTHS. SEQUENCING. AND OTHER TRAFFIC CONTROL MEASURES FOR STAGING OF JOINT REPAIR

FOR ESTIMATED LINK SLAB FOR PRESERVATION QUANTITIES, SEE PLAN OF SPAN SHEETS.

FOR LINK SLAB FOR PRESERVATION, SEE SPECIAL PROVISIONS.

## **CONSTRUCTION SEQUENCE**

- 1. CLOSE WORK AREA ACCORDING TO TRAFFIC MANAGEMENT PLANS.
- 2. MARK OUT PROPOSED LINK SLAB AREA AND REMOVE EXISTING JOINT MATERIAL
- 3. SAW CUT <sup>1</sup>/<sub>2</sub>" DEEP PERIMETER OF PROPOSED LINK SLAB AREA.
- BEGIN FULL DEPTH DEMOLITION OF PROPOSED LINK SLAB AREA, BEING CAREFUL NOT TO DAMAGE EXISTING REINFORCING STEEL, BEAM FLANGES, OR STAY-IN-PLACE FORMS. DEMOLISH EDGES OF LINK SLAB AREA AT A 2:1 RATIO, AS SHOWN.
- REMOVE DEMOLITIONED MATERIALS AND CLEAN LINK SLAB AREA.
- 6. REMOVE SHEAR STUDS/STIRRUPS WITHIN THE LINK SLAB AREA.
- 7. REPAIR EXISTING REINFORCING STEEL THAT WAS DAMAGED DURING DEMOLITION.
- 8. PLACE BOND BREAKER MATERIAL WITHIN THE LINK SLAB AREA.
- 9. PLACE ADDITIONAL REINFORCING STEEL AS SHOWN.
- 10. PLACE NEW CONCRETE FOLLOWING THE LINK SLAB FOR PRESERVATION SPECIAL PROVISION. AS AN ALTERNATIVE, THE CONTRACTOR CAN USE LMC MATERIAL FOR THE LINK SLAB, FOLLOWING THE LATEX MODIFIED CONCRETE-EARLY STRENGTH BRIDGE DECK OVERLAY SPECIAL PROVISIONS.
- 11. AFTER PROPOSED DECK OVERLAY WORK HAS CURED, SAW CUT CONTROL LINES AND FILL WITH SEALER MATERIAL.

PROJECT NO. <u>15BPR.125.3</u> <u>CHEROKEE</u> COUNT BRIDGE NO. <u>190010</u>							
A SE AL 031583 Docusigned 444 Krishna P. Sedai EA6F7941508F487 09/15/2023	DEPARTMENT OF TRANSPORTATION RALEIGH LINK SLAB FOR PRESERVATION DETAILS @ BENT 3						
	REVISIONS SHEET NO.						
DOCUMENT NOT CONSIDERED	NO. BY:		NO.	BY:	DATE:	S2-12	
FINAL UNLESS ALL SIGNATURES COMPLETED	1		<u>3</u> 4			total Sheets 28	