PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.05.04.10351.1,etc	23	

THERMOPLASTIC AND PAINT QUANTITIES

									4413000000-E	4447000000-E	4457000000-N	4685000000-E		4695000000-E	4700000000-E	4709000000-E	4720000000-E			4725000000-E						4770000000-E		4850000000-E	4905100000-N
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	PEDESTRIAN CHANNELIZING DEVICES	TEMPORARY TRAFFIC CONTROL	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	8" X 90 M YELLOW THERMO	12" X 90 M YELLOW THERMO	24" X 90 M WHITE THERMO	THERMO MSG STOP 90 M	THERMO MSG AHEAD 90 M	THERMO MSG SCHOOL 90 M	THERMO STR ARROW 90 M	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR & RT ARROW 90 M	THERMO LT STR RT ARROW 90 M	THERMO STR & LT ARROW 90 M	4" YELLOW COLD APPLIED PLASTIC, TYPE III	4" WHITE COLD APPLIED PLASTIC, TYPE III	4" LINE REMOVAL	NON-CAST IRON SNOWPLOW-ABLE PAVEMENT MARKER
							MI	FT	SF	LF	LS	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA
2024CPT.05.04.10351.1	Franklin	1	NC-96 E / NC 96 HWY W	US 1 TO GRANVILLE COUNTY	1	2	4.83	27 - 44	653			52,321	69,430		750	150	24	5		6	29	12	1						321
2024CPT.05.04.10351.1	Franklin	2	US-1 ALT N / S MAIN ST	PAVEMENT JOINT EAST OF US 1 TO PAVEMENT JOINT SOUTH OF NC 56	2	2	1.62	24	193	60	*	17,000	17,108			100			12										120
TOTAL FOR PROJ NO. 2024CPT.05.04.10351.1							**6.45**		**846**	**60**	*****	**69,321**	**86,538**		**750**	**250**	**24**	**5**	**12**	**6**	**29**	**12**	**1**						**441**
												155,859						**41**				**48**							
2024CPT.05.04.20351.1	Franklin	3	SR-1419 / RONALD THARRINGTON RD	NC 56 TO SR 1002 - SEVEN PATHS RD	2	2	5.4	20	126			58,104	57,024			45			6					1					
2024CPT.05.04.20351.1	Franklin	4	SR-1427 / A ALLEN RD	NC 561 TO SR 1451 - LEONARD RD	1	2	0.53	18	59			5,496	5,596																
2024CPT.05.04.20351.1	Franklin	5	SR-1100 / TARBORO RD/E MAIN ST	FROM US 401 TO BEGIN CURB AND GUTTER	1	2	5.971	24	669		*	63,150	64,554		280	100	32				4	1	1		1				
2024CPT.05.04.20351.1	Franklin	6	SR-1609 / E JEWETT AVE/ BAPTIST CHURCH RD	SR 1611 - SLEDGE RD TO NC 39	1	2	2.59	21	290			27,868	27,350			20	4									760	760	1,520	
2024CPT.05.04.20351.1	Franklin	7	SR-1100 / E MAIN ST	FROM BEGIN CURB AND GUTTER TO PVMT JT. EAST OF S CROSS ST	3	2	0.225	30 - 33	26	60		640	2,646	40							6		1						
TOTAL FOR PROJ NO. 2024CPT.05.04.20351.1							**14.716**		**1,170**	**60**	*****	**155,258**	**157,170**	**40**	**280**	**165**	**36**		**6**		**10**	**1**	**2**	**1**	**1**	**760**	**760**	**1,520**	
												312,428						**42**				**15**				**1,520**			
GRAND TOTAL							**21.166**		**2,016**	**120**	**1.00**	**224,579**	**243,708**	**40**	**1,030**	**415**	**60**	**5**	**18**	**6**	**39**	**13**	**3**	**1**	**1**	**760**	**760**	**1,520**	**441**
												468,287						**83**				**63**				**1,520**			