

**STATE OF NORTH CAROLINA  
 DIVISION OF HIGHWAYS**

<b>PAVEMENT REMOVAL SUMMARY</b>				
LINE	STATION	STATION	LOCATION	ASPHALT REMOVAL (SY)
L MEDIAN AREA	22+32	30+38	CL	1862
L, Y7	53+55	53+91	RT	110
L MEDIAN AREA	53+98	61+44	CL	1584
L	58+06	58+91	LT	91
L	63+77	64+05	LT	29
Y	19+31	19+69	LT	69
Y	24+31	25+76	LT	198
Y MEDIAN AREA	30+66	36+31	CL	1026
Y	33+70	35+60	LT	150
Y MEDIAN AREA	37+62	42+11	CL	476
Y2	13+25	13+52	RT	30
Y3	12+80	13+11	RT	215
Y4	10+40	11+25	LT,RT	493
Y6	12+14	12+51	RT	24
DRWY8	10+24	11+31	LT,RT	300
TEMPORARY PAVEMENT REMOVAL				
L	34+06	38+00	LT	163
TOTAL				6820
SAY				6820

<b>CHAIN LINK FENCE, 48" FABRIC</b>							
STATION TO STATION	LT OR RT	A	B	C	D	E	F
		FABRIC LF	END BRACE	CORNER BRACE	LINE BRACE	LINE POSTS EA	TERMINAL POSTS EA
-L- 25+20.00 TO 32+41.7	LT	747.97	2	0	1	62.16	3
-L- 61+17.78 TO 61+50.87	LT	37.61	2	0	0	2.80	2
Y 42+93.61 TO 43+13.17	RT	19.56	2	0	0	1.30	2
Y 43+47.04 TO 43+52.51	LT	55.27	2	0	0	4.27	2
TOTAL	0.00	860.41	0	0	0	70.53	9
SAY	0.00	861.00	0	0	0	71.00	9.00

<b>CHAIN LINK FENCE, 72" FABRIC</b>							
STATION TO STATION	LT OR RT	A	B	C	D	E	F
		FABRIC LF	END BRACE	CORNER BRACE	LINE BRACE	LINE POSTS EA	TERMINAL POSTS EA
-L- 37+13 TO 39+84	LT	633.00	2	5	0	53.25	7
0.00	0.00	0.00	0	0	0	0.00	0
0.00	0.00	0.00	0	0	0	0.00	0
0.00	0.00	0.00	0	0	0	0.00	0
TOTAL	0.00	633.00	0	0	0	53.25	7
SAY	0.00	633.00	0	0	0	54.00	7.00

<b>BREAKING OF EXISTING ASPHALT PAVEMENT</b>				
LINE	STATION	STATION	LOCATION	SQUARE YARDS
L	62+50	67+35	LT,RT	2473
L	67+64	67+11	LT,RT	151
L	67+64	70+51	LT,RT	715
TOTAL				3,339
SAY				3,340