Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
R-3833C	X-1B

CROSS-SECTION SUMMARY RIGHT

Station L_RT1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+00.00	141	3
19+50.00	175	3
20+00.00	120	15
20+50.00	40	27
21+00.00	13	19
21+50.00	32	6
22+00.00	79	0
22+50.00	81	13
23+00.00	74	30
23+50.00	91	38
24+00.00	103	45
24+50.00	123	51
25+00.00	192	52
25+50.00	181	85
26+00.00	61	116
26+50.00	17	141
27+00.00	209	123
27+50.00	496	64
28+00.00	546	49
28+50.00	474	45
29+00.00	484	30
29+50.00	541	12
30+00.00	559	6
30+50.00	511	5
31+00.00	386	5
31+50.00	202	3
32+00.00	87	4
32+50.00	84	23
33+00.00	64	54
33+50.00	17	143
34+00.00	0	270
34+50.00	0	347
35+00.00	0	831
35+50.00	0	1320
36+00.00	0	1476
36+50.00	0	1533
37+00.00	0	1431
37+50.00	0	1417
38+00.00	0	1222
38+50.00	0	779
39+00.00	0	480
39+50.00	0	389
40+00.00	15	253
40+50.00	40	134
41+00.00	49	169
41+50.00	28	124
42+00.00	10	61
42+50.00	28	112
43+00.00	50	163
43+50.00	29	268
44+00.00	5	419
44+50.00	4	458
45+00.00	3	347

Station L_RT1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
45+50.00	0	224
46+00.00	1	144
46+50.00	5	82
47+00.00	27	33
47+50.00	35	2
48+00.00	18	0

Station Y1_SOUTH	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+50.00	0	0
15+75.00	6	10
16+00.00	5	12
16+25.00	5	20
16+50.00	5	27
16+75.00	7	16
17+00.00	7	5
17+25.00	11	6
17+50.00	11	6
17+75.00	6	6
18+00.00	6	5
18+25.00	12	3
18+50.00	11	2
18+75.00	4	2

Station Drwy1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
11+00.00	53	13

Station Drwy2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0
11+50.00	7	387
11+60.00	3	5

Station Y4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
11+00.00	0	225
11+50.00	9	59

Station L_RT2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
48+50.00	2	1360
49+00.00	19	1373
49+50.00	19	906
50+00.00	6	970
50+50.00	10	130
51+00.00	12	90

Station L_RT2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
51+50.00	12	63
52+00.00	12	39
52+50.00	27	20
53+00.00	29	7
53+50.00	8	2
54+00.00	0	4
54+50.00	53	18
55+00.00	103	30
55+50.00	97	28
56+00.00	105	29
56+50.00	112	31
57+00.00	92	36
57+50.00	63	38
58+00.00	49	43
58+50.00	43	66
59+00.00	36	127
59+50.00	30	219
60+00.00	23	315
60+50.00	22	194
61+00.00	12	93
61+50.00	0	85

Station Y_RT2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
38+50.00	0	0
39+00.00	1	0
39+50.00	0	110
40+00.00	1	244
40+50.00	4	134
40+87.00	8	0
41+00.00	3	0
41+50.00	13	0
42+00.00	9	83
42+50.00	8	207
43+00.00	10	253
43+50.00	5	191
44+00.00	7	84
44+50.00	13	22
45+00.00	16	0
45+50.00	18	0
46+00.00	14	3
46+50.00	8	46
47+00.00	5	91
47+50.00	16	48
48+00.00	19	23
48+50.00	10	23
49+00.00	37	1
49+50.00	71	1
50+00.00	84	1
50+50.00	81	1
51+00.00	65	3
51+50.00	50	3

Station Y_RT2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
52+00.00	53	0
52+50.00	100	0
53+00.00	88	12
53+50.00	42	31
54+00.00	47	27
54+50.00	47	13
55+00.00	78	11
55+50.00	98	7
56+00.00	86	2
56+50.00	75	0
57+00.00	76	0

Station Y5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0
11+50.00	58	12
12+00.00	33	14
12+50.00	8	18
13+00.00	10	25
13+50.00	15	46
14+00.00	19	52
14+50.00	13	48
15+00.00	9	42
15+50.00	12	26
16+00.00	19	16
16+50.00	17	21
17+00.00	11	26
17+50.00	9	29

Station Y7	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+50.00	0	0
16+00.00	19	20

Station Y_RT1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+00.00	0	0
14+50.00	14	3
15+00.00	11	5
15+50.00	11	5
16+00.00	12	25
16+50.00	24	45
17+00.00	13	20
17+50.00	30	21
18+00.00	61	39
18+50.00	34	18
19+00.00	35	17
19+50.00	62	42
20+00.00	49	34
20+50.00	28	21

Station Y_RT1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
21+00.00	12	28
21+50.00	6	73
22+00.00	5	78
22+50.00	8	32
23+00.00	14	13
23+50.00	24	3
24+00.00	61	0
24+50.00	59	0
25+00.00	21	9
25+50.00	21	19
26+00.00	24	15
26+50.00	106	10
27+00.00	148	9
27+50.00	119	5
28+00.00	105	0
28+50.00	72	0
29+00.00	92	0
29+50.00	92	0
30+00.00	65	3
30+50.00	74	3
31+00.00	65	5
31+50.00	62	8
32+00.00	75	5
32+50.00	61	4
33+00.00	50	2
33+50.00	41	10
34+00.00	27	31
34+49.00	17	38
34+50.00	0	1
35+00.00	14	20
35+50.00	16	15
36+00.00	13	39
36+50.00	10	27
37+00.00	9	0
37+50.00	8	0
38+00.00	17	404