PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.07.11.20011, 2024CPT.07.11.20681	11	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	BORROW EXCAVATION	INCIDENTAL STONE	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	INCIDENTAL MILLING	ASPHALT CONC BASE COURSE, TYPE B25.0C	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	EMULSION FOR ASPHALT SURFACE TREATMENT	ADJ. OF MANHOLES	ADJUSTMENT OF METER BOXES OR VALVE BOXES	RESIDENTIAL SEEDING
														0106000000-E	1220000000-E	1245000000-E	1260000000-E	1330000000-E	1491000000-E	1519000000-E	1575000000-E	1704000000-E	1775000000-E	1838000000-E	2830000000-N	2845000000-N	6110000000-E
										MI	FT			CY	TONS	SMI	TON	SY	TON	TONS	TON	TONS	SY	GAL	EA	EA	AC
2024CPT.07.11.20011	Alamance	1	SR-1552 / BARBER RD	FROM SR 1504 ELON OSSIPEE RD. TO NC 87	1	2		NO	NO	0.8	22	0	0.8		36			384		994	74	200	10,718	3,537			
TOTAL FOR MAP NO. 1										**0.8**					**36**			**384**		**994**	**74**	**200**	**10,718**	**3,537**			
2024CPT.07.11.20011	Alamance	2	SR-1151 / TROXLER RD	FROM SR 1146 KIRKPATRICK RD. TO NC 62 (ALAMANCE RD.)	1	2		NO	NO	0.5	22	0	0.5		15			479		623	51	220	6,678	2,204	2	1	
TOTAL FOR MAP NO. 2										**0.5**					**15**			**479**		**623**	**51**	**220**	**6,678**	**2,204**	**2**	**1**	
2024CPT.07.11.20011	Alamance	3	SR-2146 / SAXAPAHAW BETHLEHEM CHURCH RD	FROM SR 1961 SAXAPAHAW BETHLEHEM CHURCH RD/ORANGE COUNTY LINE TO BRIDGE # 210 NEAR SR 2171 SWEPSONVILLE SAXAPAHAW RD	1	2		NO	NO	3.39	21	0	3.39		255			388		4,352	302	400	44,926	14,826	3	1	
TOTAL FOR MAP NO. 3										**3.39**					**255**			**388**		**4,352**	**302**	**400**	**44,926**	**14,826**	**3**	**1**	
2024CPT.07.11.20011	Alamance	4	SR-2153 / BRUCEWOOD RD	FROM NC 54 TO SR 2165 BRUCEWOOD RD (APPROX. 205 FEET WEST OF CENTERLINE OF SR 2153 WORMRANCH RD)	1	2		NO	NO	0.68	20	0	0.68		33			233		903	66	150	9,254	3,054			
TOTAL FOR MAP NO. 4										**0.68**					**33**			**233**		**903**	**66**	**150**	**9,254**	**3,054**			
2024CPT.07.11.20011	Alamance	5	SR-2131 / JONES DR	FROM SR 1123 JONES ROAD/OCL TO SR 2126 OLD HILLSBOROUGH RD	1	2		NO	NO	3.7	22	0	3.7		225			208		4,576	314	340	48,829	16,114		3	
TOTAL FOR MAP NO. 5										**3.7**					**225**			**208**		**4,576**	**314**	**340**	**48,829**	**16,114**		**3**	
2024CPT.07.11.20011	Alamance	6	SR-2165 / BRUCEWOOD RD	FROM SR 2153 WORMRANCH RD TO SR 2158 SWEPSONVILLE SAXAPAHAW RD	1	2		NO	NO	1.17	21	0	1.17		90			188		1,440	101	150	14,467	4,774			
TOTAL FOR MAP NO. 6										**1.17**					**90**			**188**		**1,440**	**101**	**150**	**14,467**	**4,774**			
2024CPT.07.11.20011	Alamance	7	SR-1001 / UNION RIDGE RD	FROM SOUTH SIDE OF INTERSECTION OF SR 1002 JEFFRIES CROSS RD TO CASWELL COUNTY LINE	1	2		NO	NO	3.3	21	4.9	8.2		135			367		4,065	293	600	42,338	13,971			
TOTAL FOR MAP NO. 7										**3.3**					**135**			**367**		**4,065**	**293**	**600**	**42,338**	**13,971**			
2024CPT.07.11.20011	Alamance	8	SR-1005 / W GREENSBORO CHAPEL HILL RD	FROM NC 49 TO SR 2371	2	2		NO	NO	3.6	22	14.82	11.22	142	210	7.06	400	383	4,403	5,119	564	700	49,942	16,481			1.00
TOTAL FOR MAP NO. 8										**3.6**				**142**	**210**	**7.06**	**400**	**383**	**4,403**	**5,119**	**564**	**700**	**49,942**	**16,481**			**1.00**
TOTAL FOR PROJ NO. 2024CPT.07.11.20011										**17.14**		**19.72**	**29.66**	**142**	**999**	**7.06**	**400**	**2,630**	**4,403**	**22,072**	**1,765**	**2,760**	**227,152**	**74,961**	**5**	**5**	**1.00**
2024CPT.07.11.20681	Orange	9	SR-1961 / SAXAPAHAW BETHLEHEM CHURCH RD	FROM NC 54 TO SR 2146 SAXAPAHAW BETHLEHEM CHURCH RD/ALAMANCE COUNTY LINE	1	2		NO	NO	0.385	21	0	0.385		24			589		536	35		5,227	1,725			
TOTAL FOR MAP NO. 9										**0.385**					**24**			**589**		**536**	**35**		**5,227**	**1,725**			
2024CPT.07.11.20681	Orange	10	SR-1123 / JONES RD	FROM SR 1007 MEBANE OAKS RD TO SR 2131 JONES DR./ALAMANCE COUNTY LINE	1	2		NO	NO	0.091	23	0	480					192		112	7		1,227	405			
TOTAL FOR MAP NO. 10										**0.091**								**192**		**112**	**7**		**1,227**	**405**			
TOTAL FOR PROJ NO. 2024CPT.07.11.20681										**0.476**		**0**	**480.385**		**24**			**781**		**648**	**42**		**6,454**	**2,130**			
GRAND TOTAL										**17.616**		**19.72**	**510.045**	**142**	**1,023**	**7.06**	**400**	**3,411**	**4,403**	**22,720**	**1,807**	**2,760**	**233,606**	**77,091**	**5**	**5**	**1.00**