



PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 165 LBS PER SQ YD.
C2	PROP. APPROX. 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ YD.
F	ASPHALT SURFACE TREATMENT, MATCOAT, #67M STONE TO BE APPLIED AT AN AVERAGE RATE OF 38 LBS PER SQ YD, EMULSION RATE OF 0.40 GAL PER SQ YD
M	MILL ASPHALT PAVEMENT, 1/2" DEPTH
M1	MILL ASPHALT PAVEMENT, 2 1/2" (OR DOWN TO CURB FLOW LINE) - 1/2" IN THE CROWN
M2	MILL ASPHALT PAVEMENT, 0" AT THE CROWN TO APPROX 3" AT THE CURB LINE OR DOWN TO 1/2" BELOW TOE OF CURB
M3	MILL ASPHALT PAVEMENT, 0-1/2" DEPTH @ 7' WIDTH
S	SHOULDER RECONSTRUCTION (SEE DETAIL)
U	EXISTING PAVEMENT