SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH		1704000000-E PATCHING EXISTING PAVEMENT	2549000000-E 2'-6" CURB & GUTTER	2591000000-E 4" CONCRETE SIDEWALK	2605000000-N CONCRETE CURB RAMPS	2613000000-N REMOVE AND REPLACE CURB RAMPS	2738000000-E GENERIC PAVING ITEM, REMOVE AND REPLACE SIDEWALK	2739000000-E GENERIC PAVING ITEM REMOVE SIDEWALK	2739000000-E GENERIC PAVING ITEM REMOVE AND REPLACE 5" MONOLITHIC CONCRETE ISLAND	2752000000-E GENERIC PAVING ITEM, REMOVE 2'-6" C&G	2759000000-N GENERIC PAVING ITEM, RETROFIT CURB RAMP DETECTABLE WARNINGS	2759000000-N GENERIC PAVING ITEM, REMOVE CURB RAMP	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	4116100000-N SIGN ERECTION, RELOCATE TYPE E (GROUND MOUNTED)	4600000000-N GENERIC TRAFFIC CONTROL ITEM PEDESTRIAN TRANSPORT SERVICE (PER TRIP)	4600000000-N GENERIC TRAFFIC CONTROL ITEM AUDIBLE WARNING DEVICES	7444000000-E INDUCTIVE LOOP SAWCUT
										MI	FT		TONS	LF	SY	EA	EA	SY	SY	SY	LF	EA	EA	EA	EA	EA	EA	EA	LF
2024CPT.05.03.10321.1	Durham	1	NC-54 E / NC 54 E HWY	FROM SR 1118 FAYETTEVILLE RD TO NC 55	1	2	2WU	NO	NO	2.295	40		261	125	27	5	36	62	30		83	7	6	1			10	2	2,700
2024CPT.05.03.10321.1	Durham	2	NC-98 E / HOLLOWAY ST/WAKE FOREST HWY	FROM END DIV HWY TO BEGIN HS-2005N	1	2	2WD	NO	NO	0.915	34		192	15	4		15	14		10		4		1	2				675
2024CPT.05.03.10321.1	Durham	3	NC-98 E / HOLLOWAY ST/WAKE FOREST HWY	END HS-2005N TO SR 1909	1	2	2WD	NO	NO	2.403	340		410	98	9		26	51			10	2	4			1	20	4	2,475
TOTAL FOR PROJ NO. 2024CPT.05.03.10321.1										**5.613**			**863**	**238**	**40**	**5**	**77**	**127**	**30**	**10**	**93**	**13**	**10**	**2**	**2**	**1**	**30**	**6**	**5,850**
2024CPT.05.03.20321.1	Durham	4	SR-1321 / HILLANDALE RD	FROM PAVEMENT CHANGE @ CAMMIE ST TO PAVEMENT JOINT NORTH OF PINETREE CT	2	2	2WU	NO	NO	0.221	28		16				4		6										
2024CPT.05.03.20321.1	Durham	5	SR-1321 / HILLANDALE RD	FROM SR 1407 TO PAVEMENT CHANGE @ CAMMIE ST	3	2	2WD	NO	NO	0.253	28		29		2		8												
2024CPT.05.03.20321.1	Durham	6	SR-1321 / HILLANDALE RD	FROM PAVEMENT JOINT NORTH OF PINETREE CT TO PAVEMENT JOINT SOUTH OF HORTON RD.	4	2	2WD	NO	NO	0.828	36		85	18	14		10						1						
2024CPT.05.03.20321.1	Durham	7	SR-1443 / HORTON RD	FROM NC 157 TO US 501	5	2	2WD	NO	NO	1.497	22		108	16	6		17	18					1	1		1			
2024CPT.05.03.20321.1	Durham	8	SR-1637 / REDWOOD RD	FROM SR 1670 TO SR 1690	1	2	2WD	NO	NO	0.425	24		29																
2024CPT.05.03.20321.1	Durham	9	SR-1818 / BURTON RD	FROM SR 1670 TO SR 1800	5	2	2WD	NO	NO	1.386	20		87																
2024CPT.05.03.20321.1	Durham	10	SR-1848 / GOOCH RD	FROM SR 1670 TO DEAD END	5	2	2WD	NO	NO	0.3	18		10																
2024CPT.05.03.20321.1	Durham	11	SR-1851 / FAITH DR	FROM SR 1800 TO SR 1852	5	2	2WD	NO	NO	0.142	20		7																
2024CPT.05.03.20321.1	Durham	12	SR-1852 / FOLKSTON DR	FROM SR 1851 TO SR 1851 +.1 MILES	5	2	2WD	NO	NO	0.099	20		6																
2024CPT.05.03.20321.1	Durham	13	SR-1853 / SUITT ST	FROM SR 1815 TO DEAD END	5	2	2WD	NO	NO	0.31	20		16											16	7				
2024CPT.05.03.20321.1	Durham	14	SR-1864 / MANNIX RD	FROM SR 1637 TO END PVMT	5	2	2WU	NO	NO	0.31	18		17																
2024CPT.05.03.20321.1	Durham	15	SR-1876 / ARDSLEY DR	FROM SR 1637 TO END PVMT	5	2	2WU	NO	NO	0.79	20		39																
2024CPT.05.03.20321.1	Durham	16	SR-1881 / BRAGG RD	FROM SR 1637 TO END MAINT	5	2	2WU	NO	NO	0.16	18		9																
2024CPT.05.03.20321.1	Durham	17	SR-1885 / BARWICK DR	FROM SR 1800 TO END MAINT	5	2	2WU	NO	NO	0.681	20		34																
2024CPT.05.03.20321.1	Durham	18	SR-2035 / LAUREL DR	FROM US 70 TO SP 2037	5	2	2WU	NO	NO	0.239	20		12																
2024CPT.05.03.20321.1	Durham	19	SR-2036 / BUNGALOW AVE	FROM SR 2035 TO SR 1926	5	2	2WD	NO	NO	0.125	20		8											2					
2024CPT.05.03.20321.1	Durham	20	SR-2037 / AUDREY ST/RURITAN RD	FROM SR 2035 TO SR 1926	5	2	2WD	NO	NO	0.385	20		14																
2024CPT.05.03.20321.1	Durham	21	SR-2510 / DINSMORE LN	FROM SR 1818 TO SR 1876	5	2	2WU	NO	NO	0.259	20		13																
2024CPT.05.03.20321.1	Durham	22	SR-2511 / CHADWICK PL	FROM SR 2510 TO END MAINT	5	2	2WU	NO	NO	0.16	20		5																
TOTAL FOR PROJ NO. 2024CPT.05.03.20321.1										**8.57**			**544**	**34**	**22**		**39**	**18**	**6**				**2**	**19**	**7**	**1**			
2024CPT.05.03.20322.1	Durham	23	SR-1459 / DUNNEGAN RD	FROM SR 1002 TO END MAINT	6	2	2WD	NO	NO	0.33	19		13																
2024CPT.05.03.20322.1	Durham	24	SR-1600 / HARRIS MILL RD	FROM US 501 TO PERSON CO	6	2	2WD	NO	NO	0.58	20		21																
2024CPT.05.03.20322.1	Durham	25	SR-1604 / CARVER RD	FROM SR 1471 TO PERSON CO	6	2	2WD	NO	NO	0.604	20		21																
2024CPT.05.03.20322.1	Durham	26	SR-2400 / REDPINE RD	FROM SR 1002 TO END MAINT	6	2	2WU	NO	NO	0.391	20		13																
2024CPT.05.03.20322.1	Durham	27	SR-2401 / HARDWOOD LN	FROM CUL-DE-SAC TO END MAINT	6	2	2WU	NO	NO	0.203	20		16																
2024CPT.05.03.20322.1	Durham	28	SR-2402 / BUSHMILL CT	FROM SR 2401 TO CUL-DE-SAC	6	2	2WU	NO	NO	0.128	20		6																
2024CPT.05.03.20322.1	Durham	29	SR-2470 / VISTA DEL RIO DR	FROM SR 1461 TO SR 2471	6	2	2WU	NO	NO	0.16	20		7																
2024CPT.05.03.20322.1	Durham	30	SR-2471 / VISTA DEL RIO DR	FROM CDS TO CDS	6	2	2WU	NO	NO	0.057	20		6																
2024CPT.05.03.20322.1	Durham	31	SR-2623 / ELYSIAN WAY	FROM SR 1471 TO DEAD END	6	2		NO	NO	0.512	22		19																
2024CPT.05.03.20322.1	Durham	32	SR-2624 / WOLF LAUREL CT	FROM SR 1605 TO DEAD END	6	2	2WD	NO	NO	0.278	20		11																
2024CPT.05.03.20322.1	Durham	33	SR-2629 / HALCYON PL	FROM SR 2623 TO DEAD END	6	2	2WU	NO	NO	0.257	20		10																
TOTAL FOR PROJ NO. 2024CPT.05.03.20322.1										**3.5**			**143**																
2024CPT.05.03.20732.1	Person	34	SR-1739 / HARRIS MILL RD	FROM DURHAM COUNTY TO END MAINTENANCE	6	2	2WD	NO	NO	0.591	20		22																
TOTAL FOR PROJ NO. 2024CPT.05.03.20732.1										**0.591**			**22**																
GRAND TOTAL										**18.274**			**1,572**	**272**	**62**	**5**	**116**	**145**	**36**	**10**	**93**	**13**	**12**	**21**	**9**	**2**	**30**	**6**	**5,850**

REVISIONS

8/17/99

10/9/2023
:\Proj\2025 Durham.SOO PSH .dgn
USERNAME=mcd