DocuSign Envelope ID: FD186A26-E739-4C1D-8273-BDD7004E2D64

PROJECT REFERENCE NO.	SHEET NO.
U-5824	SIGN-3

APPROVED: DocuSigned by: Chaolong Teng 8B6BA0DE5257455... 9/14/2023

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 032179 ENGINEER CHAOLONG TENG

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PREPARED IN THE OFFICE OF:

Accelerate Engineering, PLLC
875 Walnut Street, Suite 316
Cary, NC 27511
Tel: 919.263.5678 Fax: 919.263.5687
NC License No. P-1442

(401) QUANTITY REQ'D 2

24 X 30
R4-7

ONE "U" POST PER SIGN

(402) QUANTITY REQ'D 1



54 X 18
R6-1 (R)

TWO "U" POSTS PER SIGN

(403) QUANTITY REQ'D 9

36 X 12
R6-1 (R)

TWO "U" POSTS PER SIGN

(404) QUANTITY REQ'D 17

36 X 36
R1-1

ONE "U" POST PER SIGN
MOUNT BELOW SIGN NO. 403
IN 9 INSTALLATIONS

(405) QUANTITY REQ'D 2



36 X 36 X 36
R1-2

ONE "U" POST PER SIGN

(406) QUANTITY REQ'D 2

36 X 36
W11-2

YELLOW/GREEN REFLECTIVE SHEETING
ONE "U" POST PER SIGN

(407) QUANTITY REQ'D 2

24 X 12
W16-7P(R)

YELLOW/GREEN REFLECTIVE SHEETING
MOUNT BELOW SIGN NO. 406
IN 2 INSTALLATIONS

(408) QUANTITY REQ'D 7

30 X 36
R2-1

ONE "U" POST PER SIGN

(409) QUANTITY REQ'D 1

24 X 30
R2-1

ONE "U" POST PER SIGN

(410) QUANTITY REQ'D 2

54 X 18
R6-1 (L)

TWO "U" POSTS PER SIGN

(411) QUANTITY REQ'D 2

30 X 30
W11-1

ONE "U" POST PER SIGN

(412) QUANTITY REQ'D 2

18 X 24
W16-1P

MOUNT BELOW SIGN 411
IN 2 INSTALLATIONS

(413) QUANTITY REQ'D 2

36 X 36
R3-7

ONE "U" POST PER SIGN

(414) QUANTITY REQ'D 8

24 X 18
R3-17

ONE "U" POST PER SIGN

(415) QUANTITY REQ'D 2

24 X 8
R3-17aP

MOUNT BELOW SIGN 414
IN 2 INSTALLATIONS

(416) QUANTITY REQ'D 2

24 X 8
R3-17bP

MOUNT BELOW SIGN 414
IN 2 INSTALLATIONS

(417) QUANTITY REQ'D 1

36 X 36
W3-5

ONE "U" POST PER SIGN

(418) QUANTITY REQ'D 1



36 X 30
R4-4

ONE "U" POST PER SIGN

(419) QUANTITY REQ'D 1



36 X 36
W1-2 (R)

ONE "U" POST PER SIGN

TYPE "E" SIGNS

SYMBOL SIGN FRAME