


### 18 CHANNEL IP CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)

REMOVE DIODE JUMPERS 1-5, 1-6, 1-9, 1-11, 2-5, 2-6, 2-9, 2-11, 3-7, 3-8, 3-10, 3-12, 4-7, 4-8, 4-10, 4-12, 5-9, 5-11, 6-9, 6-11, 7-10, 7-12, 8-10, 8-12, 9-11 and 10-12.



REMOVE JUMPERS AS SHOWN

NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that Red Enable is active at all times during normal operation.

■ = DENOTES POSITION OF SWITCH

### NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Program phases 4 and 8 for Dual Entry.
- Program controller to start up in phase 2 Green No Walk and 6 Green No Walk.

### EQUIPMENT INFORMATION

CONTROLLER.....2070LX  
 CABINET.....332 W/AUX  
 SOFTWARE.....0-FREE MAXTIME  
 CABINET MOUNT.....BASE  
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE  
 LOAD SWITCHES USED.....S1,S2,S4,S5,S7,S8,S10,S11,  
 AUX S1,AUX S2,AUX S4,AUX S5  
 PHASES USED.....1,2,3,4,5,6,7,8  
 OVERLAP "1".....\*  
 OVERLAP "2".....\*  
 OVERLAP "3".....\*  
 OVERLAP "4".....\*  
 \* See overlap programming detail on sheet 2.

### SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OL1	OL2	SPARE	OL3	OL4	SPARE
SIGNAL HEAD NO.	11	82	21,22	22	31	41,42,43	51	61,62	62	71	81,82,83	91	101	111	121	131	141	151
RED	*	128		*	101			134	*	107								
YELLOW		129			102		*	135		108								
GREEN		130			103			136		109								
RED ARROW													A121	A124		A114	A101	
YELLOW ARROW	126			117						123			A122	A125		A115	A102	
FLASHING YELLOW ARROW													A123	A126		A116	A103	
GREEN ARROW	127	127		118	118			133		124	124							


NU = Not Used

\* Denotes install load resistor. See load resistor installation detail this sheet.

★ See pictorial of head wiring in detail this below.

### INPUT FILE POSITION LAYOUT

(front view)



EX.: 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE  
ST = STOP TIME

### SPECIAL DETECTOR NOTES

Install a video detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection scheme shown on the Signal Design Plans.  
 For the detectors to work as shown on the signal design plan, see the Maxtime Detector Programming Detail for Alternate Phasing Zones on Sheet 2.

### FLASHER CIRCUIT MODIFICATION DETAIL

IN ORDER TO ENSURE THAT SIGNALS FLASH CONCURRENTLY ON THE SAME APPROACH, MAKE THE FOLLOWING FLASHER CIRCUIT CHANGES:


- ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-4 AND TERMINATE ON T2-2.
- ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-5 AND TERMINATE ON T2-3.
- REMOVE FLASHER UNIT 2.

THE CHANGES LISTED ABOVE TIES ALL PHASES AND OVERLAPS TO FLASHER UNIT 1.

### LOAD RESISTOR INSTALLATION DETAIL


(install resistors as shown)

VALUE (ohms)	WATTAGE
1.5K - 1.9K	25W (min)
2.0K - 3.0K	10W (min)



### FYA SIGNAL WIRING DETAIL

(wire signal heads as shown)



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 09-0264T2  
 DESIGNED: August 2023  
 SEALED: 9/7/2023  
 REVISED: N/A

Prepared in the Office of:

NC FIRM LICENSE No: P-0339  
 320 Executive Court  
 Hillsborough, NC 27278  
 (919) 732-3883  
 (919) 732-6676 (FAX)

Electrical and Programming Details For:

750 N. Greenfield Pkwy, Corner, NC 27529

US 158 (Reidsville Road) at NC 66 (Old Hollow Road)

Division 9 Forsyth County Walkertown

PLAN DATE: August 2023 REVIEWED BY: E. Sirgany

PREPARED BY: J. Smith REVIEWED BY:

REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

DocuSigned by: Edward W. Sirgany 9/7/2023

SIG. INVENTORY NO. 09-0264T2