

PED 3 PROGRAMMING DETAIL

(program controller as shown below)

CHANGING OUTPUT ASSIGNMENTS

1. FROM MAIN MENU SELECT '6' (OUTPUTS), THEN '1' (OUTPUT ASSIGNMENTS)
2. ENTER 17 (PHASE 8 DW) FOR OUTPUT ASSIGNMENT #.
3. SCROLL DOWN TO 'PEDESTRIAN PHASE' AND ENTER 'Y' REGARDLESS OF DEFAULT PROGRAMMING
4. ENTER '3' FOR 'SELECT PEDESTRIAN PHASE'. NO CHANGE NEEDED FOR 'SELECT COLOR'
5. BACKUP TO 'OUTPUT ASSIGNMENTS AND SETTINGS MENU:' BY PRESSING THE 'ESC' BUTTON ON KEYBOARD.
6. SELECT '1' (OUTPUT ASSIGNMENTS)
7. ENTER 18 (PHASE 8 W) FOR OUTPUT ASSIGNMENT #.
8. REPEAT STEPS # 3 AND # 4.

CHANGING INPUT ASSIGNMENTS

1. FROM MAIN MENU SELECT '7' (DETECTORS), THEN '2' (PEDESTRIAN DETECTOR ASSIGNMENTS)
2. CYCLE TO PED DETECTOR #8 BY REPEATEDLY DEPRESSING '+' KEY
3. MODIFY PHASE ASSIGNED TO PED DETECTOR # 8 FROM PHASE 8 TO PHASE 3

PROGRAMMING COMPLETE

PHASE SEQUENCE PROGRAMMING DETAIL

(program controller as shown below)

FROM OASIS LOCAL CONTROLLER MAIN MENU
SELECT: 4 PHASE SEQUENCE

PHASE SEQUENCE: PAGE 1		NEXT: PAGES)					
RNG	LEAD	BARRIER 1	X-LAG	LEAD	BARRIER 2	X-LAG	
1	1	2	0	3	4	0	0
2	0	0	5	0	0	0	0
3	0	0	0	0	0	0	0
4	0	0	0	0	0	0	0

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 12-1689T3
DESIGNED: MAY 2022
SEALED: 3/24/2023
REVISED: N/A

Temporary Design 3 - TMP Phase III
Electrical Detail - Sheet 2 of 2

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

<p style="font-size: x-small;">Stantec Consulting Services Inc. 801 Jones Franklin Road-Suite 300 Raleigh, NC 27606 Tel. (919) 851-6866 Fax. (919) 851-7024 www.stantec.com License No. F-0672</p>	<p style="font-size: x-small;">Prepared for the Offices of:</p> <p style="font-size: x-small;">750 N. Greenfield Pkwy, Garner, NC 27529</p>	<p>SR 1100 (Brawley School Road) at SR 1116 (Talbert Road)/SR 2906 (Sunfish Drive)</p> <p>Division 12 Iredell County Mooresville</p> <table style="width: 100%; font-size: x-small;"> <tr> <td>PLAN DATE: May 2022</td> <td>REVIEWED BY: E D Harris</td> </tr> <tr> <td>PREPARED BY: D A Waller</td> <td>REVIEWED BY: R M Muncey</td> </tr> </table> <table border="1" style="width: 100%; border-collapse: collapse; font-size: x-small;"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	PLAN DATE: May 2022	REVIEWED BY: E D Harris	PREPARED BY: D A Waller	REVIEWED BY: R M Muncey	REVISIONS	INIT.	DATE							<p style="font-size: x-small;">SEAL</p> <p style="font-size: x-small;">DocuSigned by: Derrick Waller 3/24/2023</p> <p style="font-size: x-small;">SIG. INVENTORY NO. 12-1689T3</p>
PLAN DATE: May 2022	REVIEWED BY: E D Harris															
PREPARED BY: D A Waller	REVIEWED BY: R M Muncey															
REVISIONS	INIT.	DATE														

11:47:31 AM
U:\Projects\Signal Design\Temporary Design\SR-3833C.sig_eie.12_1689T3.dgn
User: dwall118r