Quantities are approximate only. The Resident Engineer will use methods including but not limited to recross–sectioning, truck measurement, and aerial surveys to compute final quantities for which the contractor will be paid.

PROJ. REFERENCE NO.	SHEET NO.
R-3833C	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY LEFT / WEST WILSON LT & RT

Station L_LT1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+50.00	14	3
20+00.00	21	21
20+50.00	11	95
21+00.00	7	136
21+50.00	3	61
22+00.00	3	2
22+50.00	7	2
23+00.00	9	23
23+50.00	11	39
24+00.00	7	77
24+50.00	2	229
25+00.00	2	723
25+50.00	1	855
26+00.00	1	606
26+50.00	1	559
27+00.00	2	404
27+50.00	2	291
28+00.00	2	440
28+50.00	2	872
29+00.00	2	1149
29+50.00	2	888
30+00.00	2	635
30+50.00	3	717
31+00.00	3	871
31+50.00	2	996
32+00.00	2	987
32+50.00	1	964
33+00.00	0	1071
33+50.00	0	1257
34+00.00	0	1242
34+50.00	0	1004
35+00.00	0	973
35+50.00	0	1045
36+00.00	0	1052
36+50.00	0	932
37+00.00	0	737
37+30.00	19500	22500
37+50.00	0	655
38+00.00	0	595
38+50.00	0	401
39+00.00	0	173
39+50.00	16	66
40+00.00	16	43
40+50.00	30	35
41+00.00	45	10
41+50.00	28	6
42+00.00	20	0
42+50.00	14	0
43+00.00	26	19
43+50.00	27	88
44+00.00	18	133
44+50.00	9	235
45+00.00	0	471

Station L_LT1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
45+50.00	0	693
46+00.00	0	729
46+50.00	4	904
47+00.00	8	1925
47+50.00	10	3176
48+00.00	7	3666

Station Y1_NORTH	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+00.00	0	0
13+25.00	4	0
13+50.00	5	0
13+75.00	7	5
14+00.00	11	5
14+25.00	38	0

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+00.00	0	0
13+50.00	29	65

Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+22.00	0	0
12+50.00	7	1
13+00.00	42	1

Station L_LT2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
48+50.00	1	1360
49+00.00	4	2400
49+50.00	4	1933
50+00.00	3	1598
50+50.00	4	1234
51+00.00	2	974
51+50.00	1	652
52+00.00	2	260
52+50.00	44	53
53+00.00	51	0
53+50.00	8	2
54+00.00	0	3
54+50.00	12	2
55+00.00	29	1
55+50.00	17	1
56+50.00	0	7
57+00.00	3	10
57+50.00	7	4
58+00.00	5	12
58+50.00	1	26
59+00.00	0	86

Station L_LT2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
59+50.00	0	139
60+00.00	0	127
60+50.00	0	130
61+00.00	0	151
61+50.00	0	85

Station Y6	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+70.00	0	0
11+80.00	7	0
12+00.00	20	1
12+50.00	63	51

Station Y_LT1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+50.00	5	1
15+00.00	8	9
15+50.00	4	22
16+00.00	2	31
16+50.00	2	16
17+00.00	3	0
17+50.00	5	22
18+00.00	5	22
18+50.00	4	14
19+00.00	3	18
19+50.00	2	14
20+00.00	2	49
20+50.00	4	82
21+00.00	8	94
21+50.00	8	65
22+00.00	5	27
22+50.00	6	22
23+00.00	5	39
23+50.00	1	80
24+00.00	1	241
24+50.00	1	239
25+00.00	5	69
25+50.00	11	32
26+00.00	7	20
26+50.00	5	24
27+00.00	5	47
27+50.00	1	65
28+00.00	10	60
28+50.00	27	48
29+00.00	38	36
29+50.00	43	22
30+00.00	42	18
30+50.00	38	19
31+00.00	28	28
31+50.00	14	30
32+00.00	3	49

Station Y_LT2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
34+50.00	0	0
35+00.00	0	357
35+50.00	0	740
36+00.00	0	555
36+50.00	2	212
37+00.00	2	105
37+50.00	1	145
38+00.00	13	496
38+50.00	22	660
39+00.00	9	407
39+50.00	0	213
40+00.00	13	81
40+50.00	96	28
40+87.00	131	13

Station Drwy3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
11+00.00	0	302

Station Drwy4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
11+00.00	6	115

Station Drwy6	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+75.00	0	0
11+00.00	0	270
11+24.06	25	102

Station Drwy7	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+84.67	0	0
11+00.00	25	1
11+25.00	77	0
11+50.00	151	0

Station Drwy8	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+25.00	0	0
10+50.00	56	0
10+75.00	23	8
11+00.00	0	30
11+25.00	0	31
11+50.00	0	10

Station Drwy5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
11+00.00	0	242
11+50.00	0	326

Station Y_LT3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
40+87.00	0	0
41+00.00	24	2
41+50.00	115	15
42+00.00	186	33
42+50.00	107	44
43+00.00	131	30
43+50.00	213	3
44+00.00	161	0
44+50.00	86	0
45+00.00	98	0
45+50.00	126	1
46+00.00	208	1
46+50.00	249	0
47+00.00	131	2
47+50.00	102	10
48+00.00	182	17
48+50.00	200	19
49+00.00	182	24
49+50.00	153	32
50+00.00	130	35
50+50.00	119	33
51+00.00	117	20
51+50.00	104	6
52+00.00	71	6
52+50.00	49	5
53+00.00	42	14
53+50.00	52	13
54+00.00	54	19
54+50.00	31	40
55+00.00	32	28
55+50.00	33	19
56+00.00	28	17

Station W. Wilson LT&RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
63+00.00	0	0
63+50.00	0	2282
64+00.00	0	3847
64+50.00	0	4333
65+00.00	0	4527
65+50.00	0	4382
66+00.00	0	3272
66+50.00	0	2489
67+00.00	0	2587
67+50.00	0	2254
68+00.00	0	1899
68+50.00	0	1819
69+00.00	0	1794
69+50.00	0	1540
70+00.00	0	1130
70+50.00	0	738
71+00.00	5	454
71+50.00	7	398
72+00.00	4	369
72+50.00	16	279
73+00.00	43	249
73+50.00	70	243
74+00.00	91	233
74+50.00	120	208
75+00.00	115	180
75+50.00	49	184