PROJECT REFERENCE NO.	SHEET NO.
I-5972	EC-03A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	RPC	12+00	15+50	LT	270
5	L	61+00	63+33	LT	465
5	L	46+00	46+50	RT	75
5	L	46+50	47+00	RT	75
5	RPA	20+75	21+42	LT	125
5	RPA	19+06	21+15	RT	415
5	RPB	16+46	19+00	RT	315
5	RPC	15+50	17+00	LT	175
5	RPC	17+00	18+00	LT	125
5	RPC	18+00	18+50	LT	75
5	RPC	20+00	21+50	LT	300
5	RPD	20+50	29+00	LT	980
5	RPD	29+00	29+25	LT	50
5	RPD	29+48	30+61	LT	225
5	RPD	15+50	16+00	RT	65
5	RPD	16+00	19+00	RT	375
5	RPD	19+00	21+00	RT	250
5	RPD	28+50	29+00	RT	40
5	Y1	44+50	45+50	RT	80
5	Y1	45+50	46+65	RT	145
7	Y1	21+73	26+03	LT	330
8	Y1	44+50	46+00	LT	445
8	Y1	50+00	53+75	LT	735
8	Y1	46+80	47+50	RT	90
				SUBTOTAL	6,225

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
8	Y2	30+50	33+00	LT	290
8	Y2	25+00	30+00	RT	770
8	Y2	30+00	32+00	RT	310
8	Y2	32+00	33+00	RT	115
8/9	Y2	20+00	25+00	RT	770
9	Y2	10+11	11+00	LT	105
9	Y2	11+00	12+50	LT	175
9	Y2	12+50	14+00	LT	300
9	Y2	14+00	15+50	LT	300
9	Y2	15+50	17+14	LT	330
9	Y2	11+00	12+50	RT	175
9	Y2	17+60	20+00	RT	370
				SUBTOTAL	4,010
				TOTAL	10,235
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					46,100
				SAY	56,335

7/17/2023
R:\Hydraulics\CADD\PSH\Erosion Control\I5972_EC_psh03A.dgn
mbailey