PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.08.04.10531, 2024CPT.08.04.20531	21	

THERMOPLASTIC AND PAINT QUANTITIES

												4810000000-E		4815000000-E		4825000000-E		4830000000-E	4835000000-E	4840000000-N	4845000000-N					4850000000-E	4855000000-E	4870000000-E	4875000000-N	4891000000-E	4905100000-N	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	4" WHITE PAINT	4" YELLOW PAINT	6" YELLOW PAINT	6" WHITE PAINT	12" WHITE PAINT	12" YELLOW PAINT	16" WHITE PAINT	24" WHITE PAINT	PAINT MSG RXR	PAINT MERGE ARROW	PAINT LT ARROW	PAINT RT ARROW	PAINT STR ARROW	PAINT STR & RT ARROW	4" LINE REMOVAL	6" LINE REMOVAL	24" LINE REMOVAL	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	GENERIC PAVEMENT MARKING ITEM - 16" LINE REMOVAL	NON-CAST IRON SNOWPLOW-ABLE PAVEMENT MARKER C&R	NON-CAST IRON SNOWPLOW-ABLE PAVEMENT MARKER Y&Y
								MI	FT			LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA	LF	EA	EA
2024CPT.08.04.10531	Lee	1	US-421 N	FROM BRIDGE OVER US 421/421 BUS TO BRIDGE OVER NC 42	1	2	MD	1	38	3.8	4.8			5,280	6,403	705					3										66	
TOTAL FOR MAP NO. 1								**1**						**5,280**	**6,403**	**705**					**3**										**66**	
2024CPT.08.04.10531	Lee	2	US-421 S	FROM BRIDGE OVER NC 42 TO BRIDGE OVER US 421/421 BUS	1	2	MD	1	38	10.17	11.17			5,280	6,539	905					3										66	
TOTAL FOR MAP NO. 2								**1**						**5,280**	**6,539**	**905**					**3**										**66**	
2024CPT.08.04.10531	Lee	3	NC-87 BYP N	FROM NC 87 TO BRIDGE OVER US 421/421 BUS	1	2	MD	1.36	38	0	1.36			7,671	9,626	1,184											551				90	
TOTAL FOR MAP NO. 3								**1.36**						**7,671**	**9,626**	**1,184**											**551**				**90**	
2024CPT.08.04.10531	Lee	4	NC-87 BYP S	FROM BRIDGE OVER US 421/421 BUS TO NC 87	1	2	MD	1.07	38	6.75	7.82			6,140	7,841	1,882					3						613				71	
TOTAL FOR MAP NO. 4								**1.07**						**6,140**	**7,841**	**1,882**					**3**						**613**				**71**	
2024CPT.08.04.10531	Lee	5	NC-87 N	FROM PVMT JT 210' SOUTH OF MEDIAN END TO NC 87 BYP	2	2	MD	0.17	38	3.12	3.29			1,056	1,273		57					2									11	
TOTAL FOR MAP NO. 5								**0.17**						**1,056**	**1,273**		**57**					**2**									**11**	
2024CPT.08.04.10531	Lee	6	NC-87 S	FROM NC 87 BYP TO PVMT JNT 210' SOUTH OF MEDIAN END	2	2	MD	0.45	38	12.21	12.66			2,433	3,250						3										30	
TOTAL FOR MAP NO. 6								**0.45**						**2,433**	**3,250**						**3**										**30**	
2024CPT.08.04.10531	Lee	7	NC-87	FROM PVMT JT 210' SOUTH OF MEDIAN END TO COMMERCE AVENUE	3	2	MU	0.24	68	2.88	3.12			4,046	3,562		385		52			4	3	2							16	
TOTAL FOR MAP NO. 7								**0.24**						**4,046**	**3,562**		**385**		**52**			**4**	**3**	**2**							**16**	
2024CPT.08.04.10531	Lee	8	US-1 N	FROM SPRING LANE OFF RAMP TO US 421 BUS (HORNER BLVD)	2	2	MD	0.89	34	10.7	11.59			4,699	5,881	1,984															59	
TOTAL FOR MAP NO. 8								**0.89**						**4,699**	**5,881**	**1,984**															**59**	
2024CPT.08.04.10531	Lee	9	RMP-868 OI	US 1 EXIT 68 NB OFF RAMP	4	2		0.305	25	0	0.305			1,610	1,610																	
TOTAL FOR MAP NO. 9								**0.305**						**1,610**	**1,610**																	
2024CPT.08.04.10531	Lee	10	RMP-869 OI	US 1 EXIT 68 NB ON RAMP	4	2		0.222	24	0	0.222			1,172	1,172																	
TOTAL FOR MAP NO. 10								**0.222**						**1,172**	**1,172**																	
2024CPT.08.04.10531	Lee	11	RMP-864 OI	US 1 EXIT 69A NB OFF RAMP	4	2		0.251	25	0	0.251			1,326	1,326																	
TOTAL FOR MAP NO. 11								**0.251**						**1,326**	**1,326**																	
2024CPT.08.04.10531	Lee	12	RMP-865 OI	US 1 EXIT 69 NB ON RAMP	5	2		0.15	21	0	0.15			792	792																	
TOTAL FOR MAP NO. 12								**0.15**						**792**	**792**																	
TOTAL FOR PROJ NO. 2024CPT.08.04.10531								**7.108**						**41,505**	**49,275**	**6,660**	**442**		**52**		**12**	**6**	**3**	**2**			**1,164**				**409**	
														90,780		**7,102**							**23**								**409**	
2024CPT.08.04.20531	Lee	13	SR-1239 / INDUSTRIAL DR	FROM SR 1133 (LEE AVENUE) TO THE END OF STATE MAINT.	6,7	2	2WU	1.01	20	0	1.01	10,868	10,868																			
TOTAL FOR MAP NO. 13								**1.01**				**10,868**	**10,868**																			
2024CPT.08.04.20531	Lee	14	SR-1318 / STEEL BRIDGE RD	FROM NC 42 TO SR 1007 (S.PLANK RD)	8	2	2WU	5.48	20	0	5.48	58,965	36,168													95,133						
TOTAL FOR MAP NO. 14								**5.48**				**58,965**	**36,168**													**95,133**						
2024CPT.08.04.20531	Lee	15	SR-1002 / LOWER MONCURE RD	FROM N. JOINT OF BRIDGE APPROACH AT US 421 BYPASS TO SR 1466 (DEEP RIVER RD)	6,7	2	2WU	10.21	22	2.47	12.68	109,860	67,386					200	100	8												
TOTAL FOR MAP NO. 15								**10.21**				**109,860**	**67,386**					**200**	**100**	**8**												
2024CPT.08.04.20531	Lee	16	SR-1502 / RAGAN RD	FROM SR 1002 (LOWER MONCURE RD) TO END OF STATE MAINT.	6	2	2WU	0.65	18	0	0.65																					
TOTAL FOR MAP NO. 16								**0.65**																								
2024CPT.08.04.20531	Lee	17	SR-1107 / FIELDS DR	FROM 600' WEST OF US 421 BUS (S. HORNER BLVD) TO US 421 BUS (S. HORNER BLVD)	7	2	2WU	0.115	30	0.875	0.99	1,238	1,238						30			1			1							8
TOTAL FOR MAP NO. 17								**0.115**				**1,238**	**1,238**						**30**			**1**			**1**							**8**
2024CPT.08.04.20531	Lee	18	SR-1107 / FIELDS DR	FROM APPROX. 300' EAST OF SR 1237 (CARTHAGE STREET) TO 600' WEST OF US 421 BUS (S. HORNER BLVD)	8,9	2	2WU	0.815	22	0.06	0.875															13,666		50	4	100		54
TOTAL FOR MAP NO. 18								**0.815**																		**13,666**		**50**	**4**	**100**		**54**
TOTAL FOR PROJ NO. 2024CPT.08.04.20531								**18.28**				**180,931**	**115,660**					**200**	**130**	**8**		**1**			**1**	**108,799**		**50**	**4**	**100**		**62**
												296,591											**2**								**62**	
GRAND TOTAL								**25.388**				**180,931**	**115,660**	**41,505**	**49,275**	**6,660**	**442**	**200**	**182**	**8**	**12**	**7**	**3**	**2**	**1**	**108,799**	**1,164**	**50**	**4**	**100**	**409**	**62**
												296,591		**90,780**		**7,102**							**25**								**471**	