PROJ. REFERENCE NO.	SHEET NO.
U-5312	X-1E

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station Y11	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+34.74	0	0
14+50.00	1	26
15+00.00	61	139
15+50.00	113	95
16+00.00	100	62
16+50.00	79	77
17+00.00	54	49
17+50.00	59	32
18+00.00	85	55
18+50.00	83	48
19+00.00	72	20
19+27.63	24	0