

SUMMARY OF QUANTITIES - ROADWAY

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	000100000-N	000400000-N	124500000-E	126000000-E	129700000-E	130800000-E	133000000-E
												MOBILIZATION	CONSTRUCTION SURVEYING	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	2" MILLING	1" TO 3" MILLING	INCIDENTAL MILLING
											MI	FT	LS	TON	SY	SY	SY	
49988.3.1	Robeson	1	US 74 WB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24						52,715	
		2	US 74 EB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24						52,072	
TOTAL FOR MAP NO. 1										2.98						52,715		
TOTAL FOR MAP NO. 2										2.98						52,072		
GRAND TOTAL										5.96		1	1	12.35	31,120	375	104,787	7,475
												1	1	12.35	31,120	375	104,790	7,475

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	149100000-E	152300000-E	157500000-E	184000000-E	303000000-E	315000000-N	
												ASPHALT CONC BASE COURSE, TYPE B25.0C	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	STEEL BEAM GUARDRAIL	ADDITIONAL GUARDRAIL POSTS	
											MI	FT	TONS	TONS	TONS	LF	LF	EA
49988.3.1	Robeson	1	US 74 WB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24	6,440	7,227	716	32,600			
		2	US 74 EB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24	6,421	7,152	711	32,600			
TOTAL FOR MAP NO. 1										2.98		6,440	7,227	716	32,600			
TOTAL FOR MAP NO. 2										2.98		6,421	7,152	711	32,600			
GRAND TOTAL										5.96		12,861	14,379	1,427	65,200	6,787.5	15	
												12,870	14,380	1,430	65,200	6,787.5	15	

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	321000000-N	328700000-N	331700000-N	336000000-E	350300000-E	350900000-E	351500000-E	
												GUARDRAIL END UNITS, TYPE CAT-1	GUARDRAIL END UNITS, TYPE TL-3	GUARDRAIL ANCHOR UNITS, TYPE B-77	REMOVE EXISTING GUARDRAIL	WOVEN WIRE FENCE, 47" FABRIC	4" TIMBER FENCE POSTS, 7'-6" LONG	5" TIMBER FENCE POSTS, 8'-0" LONG	
											MI	FT	EA	EA	EA	LF	LF	EA	EA
49988.3.1	Robeson	1	US 74 WB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24								
		2	US 74 EB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24								
TOTAL FOR MAP NO. 1										2.98									
TOTAL FOR MAP NO. 2										2.98									
GRAND TOTAL										5.96		4	14	22	7,989	470	21	24	
												4	14	22	7,989	470	21	24	