

SPAN B


	BEAM REPAIR QUANTITIY TABLE						
BOLTED STEEL PLATES		STEEL PLATES		STEEL DIAPHRAGM		BEAM REPAIR CUT-OUT	
LBS.		LBS.		LBS.		LBS.	
ESTIMATE	ACTUAL	ESTIMATE	ACTUAL	ESTIMATE	ACTUAL	ESTIMATE	ACTUAL
0.0		446.0		0.0		0.0	

ANTICIPATED STEEL REPAIR LOCATIONS						
REPAIR TYPE	BEAM	LOCATION	DIM. "A"	DIM. "B''	DIM. "C"	DIM. "D"
W	1	BENT 1	18"	16"		
W	2	BENT 1	18"	18"		
W	3	BENT 1	18"	18"		
W	1	BENT 2	18"	18"		

(SEE SHEETS S2-26, S2-27 AND S2-28 FOR BEAM REPAIR DETAILS AND DIMENSIONS.)

 DRAWN BY :
 S. T. SANDOR
 DATE :
 1/31/23

 CHECKED BY :
 W. C. SMITH
 DATE :
 5/31/23



LIMITS OF ZONE PAINTING

DECK UNDERSIDE	DECK UNDERSIDE REPAIR QUANTITY TABLE						
DECK UNDERSIDE REPAIRS	QUANTITIES						
SPAN B	ESTIN	ИАТЕ	ACTUAL				
SHOTCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF			
UNDERSIDE OF DECK	3.6	1.2					
CONCRETE DIAPHRAGM	47.7	36.8					
OVERHANG	11.4	3.9					
CONCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF			
UNDERSIDE OF DECK	0	0					
CONCRETE DIAPHRAGM	0	0					
OVERHANG	0	0					
EPOXY RESIN INJECTION	LINEAR FT		LINEAR FT				
CONCRETE DIAPHRAGM	0						
CONCRETE OVERHANG	0						
ZONE PAINTING		AREA SF		AREA SF			
BEAM ENDS		225.4					

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MIN. OF 1" BEHIND REBAR AND MIN. 2" CLEAR TO SAWCUT. SEE REPAIR DETAILS.

SHOTCRETE REPAIR AREA



CONCRETE REPAIR AREA



ZONE PAINTING



EPOXY RESIN INJECTION

B#) BEAM NUMBER

WEB PLATING REPAIR

F) BOTTOM FLANGE PLATING REPAIR

BOLTED WEB PLATE REPAIR

BF BOLTED FLANGE PLATE REPAIR

(BC) BEAM REPAIR CUT-OUT

PROJECT NO. B-5981

DUPLIN

____ COUNTY

BRIDGE NO. <u>300017</u>

SHEET 2 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

DECK UNDERSIDE REPAIR SPAN B

Docusigned by:

William C. Smith

6A2A92833F6241D...

10/24/2023

SEAL 054816

REVISIONS

OCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED 2

REVISIONS

REVISIONS

SHEET NO. BY: DATE: NO. BY: DATE: S2-11

SHEET NO. BY: DATE: NO. BY: DATE: S10TAL SHEETS

31