


TYPICAL SECTION AT INTERIOR DIAPHRAGM



TYPICAL SECTION AT END DIAPHRAGM

END BENT 1 SHOWN, END BENT 2 SIMILAR

NOTES

PROVIDE 1 1/4" HIGH BEAM BOLSTERS UPPER AT 4'-0" CTS. ATOP THE METAL STAY IN PLACE FORMS TO SUPPORT THE BOTTOM MAT OF "A" BARS. WHEN USING REMOVABLE FORMS, PROVIDE CONTINUOUS HIGH CHAIRS FOR METAL DECK (CHCM) AT 4'-0" CTS. WITH A HEIGHT TO SUPPORT THE BOTTOM MAT OF "A" BARS A CLEAR DISTANCE OF 2 1/2" ABOVE THE TOP OF THE REMOVABLE FORM.

LONGITUDINAL STEEL MAY BE SHIFTED SLIGHTLY, AS NECESSARY, TO AVOID INTERFERENCE WITH STIRRUPS IN PRESTRESSED CONCRETE GIRDERS.

PREVIOUSLY CAST CONCRETE IN A CONTINUOUS UNIT SHALL HAVE ATTAINED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI BEFORE ADDITIONAL CONCRETE IS CAST IN THE UNIT.

DOWELS SHALL BE PLACED IN THE SAME HORIZONTAL PLANE AS THE TOP AND BOTTOM SLAB REINFORCING STEEL.

SEE CONSTRUCTION SEQUENCE SHEETS FOR LOCATION OF TEMPORARY PORTABLE CONCRETE BARRIER.

SEE "FRAMING PLAN" SHEET FOR LOCATIONS OF STEEL INTERMEDIATE DIAPHRAGMS.

- * MEASURED RADIALLY FROM -L_LT-
- ** MEASURED RADIAL THROUGH WORK POINT
- *** MEASURED NORMAL TO C GIRDERS

- ① 8 - #5S1 & 8 - #4S3 @ END BENT 1 (TYP. BAYS 3-6) & 11 - #5S1 & 11 - #4S3 @ END BENT 2 (TYP. BAYS 3-6) AT 1'-0" MAX. CTS
- ② 3 - #5S2 @ END BENTS 1 & 2 (TYP. BAYS 3-6) AT 1'-0" MAX. CTS
- ③ 2 - #4K4 @ END BENT 1
2 - #4K5 @ END BENT 2 (TYP. AT BAYS 3 - 6) (CUT BARS TO FIT)

GIRDER	TOTAL NO OF #5K18 OR #5K19 BARS
3	105
4	107
5	109
6	113
7	115

BUILD UP REINFORCEMENT TABLE


THE CONTRACTOR IS ALLOWED TO PLACE BUILD-UP BAR DIAGONALLY IF NEEDED TO CLEAR THE REINFORCEMENT AT TOP OF BRIDGE DECK

PROJECT NO. B-3186 / B-5898

HAYWOOD COUNTY

STATION: 32+21.34 -L_LT-

SHEET 1 OF 3



REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S1-09
1			3			TOTAL SHEETS
2			4			43

DRAWN BY : A. K. VASUDEVAN DATE : 01/2023
 CHECKED BY : S. NATARAJAN DATE : 01/2023
 DESIGN ENGINEER OF RECORD: G.R. COLS DATE : 01/2023

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED